

---

---

# *Landfill Gas Monitoring Plan*

## *("As-Built")*

*Prepared for*

Franklin County  
Closed Unlined Municipal Solid Waste Landfill

Permit Number: 35-01  
Franklinton, North Carolina

*Prepared by:*


Municipal Engineering Services Company  
PO Box 97  
Garner, NC 27529  
Corporate License Number: C-0281  
MESCO Project Number: G14106.0

Plan Originally Submitted Before Construction: August 21, 2014  
Plan Submitted After Construction: October 30, 2014

This plan supersedes all previous landfill gas monitoring plans for this facility

---

---

  
Steven R. Gandy, Ph.D, P.E.  
Senior Project Manager

  
Jonathan Pfohl  
Environmental Specialist



## **DOCUMENT CONTROL**

This document is the current *Landfill Gas Monitoring Plan "As-Built"* for the subject facility. This plan is expected to perpetually kept up to date as inevitably site conditions and rules will change overtime. The original derivation of this plan "*pre-construction*" was submitted to the SWS prior to construction on June 23, 2014 which was approved by Ms. Christine Ritter via email on September 23, 2014. This is believed to be the first LFG monitoring plan drafted for this facility.

Minor deviations were encountered between the approved plan and this "As-Built" include:

- Added Appendix C to include all well completion logs (MP-1 though MP-7)
- Updated figures and tables to reflect actual surveyed probe locations

**TABLE OF CONTENTS**

**1 INTRODUCTION 2**  
1.1 BACKGROUND.....2  
1.2 SITE GEOLOGY AND HYDROGEOLOGY .....2  
1.3 REGULATORY LIMITS .....3  
**2 LANDFILL GAS MONITORING 3**  
2.1 LANDFILL GAS PROBES .....3  
2.1.1 LANDFILL GAS PROBE LOCATIONS .....3  
2.1.2 LANDFILL GAS PROBE CONSTRUCTION SPECIFICATIONS.....4  
2.2 STRUCTURE MONITORING .....4  
2.3 LANDFILL GAS MONITORING FREQUENCY .....4  
**3 LANDFILL GAS SAMPLING PROCEDURE 5**  
3.1 EQUIPMENT.....5  
3.2 MONITORING PROCEDURE .....5  
**4 RECORD KEEPING AND REPORTING 5**  
4.1 MONITORING DATA FORM.....5  
4.2 MONITORING REPORTS.....5  
4.3 PERMANENT RECORD KEEPING .....5  
**5 CONTINGENCY PLAN 6**  
**6 CERTIFICATION OF PROFESSIONAL GEOLOGIST OR PROFESSIONAL ENGINEER 6**

**TABLES**

LFG MOINTORING LOCATION DETAILS ..... Table 1

**FIGURES**

POTENTIOMETRIC MAP OF UPPERMOST AQUIFER ..... Figure 1  
LANDFILL GAS MONITORING LOCATIONS ..... Figure 2  
STOPCOCK VALVE CONSTRUCTION DETAILS..... Figure 3  
SITE VICINITY MAP.....Figure 4

**APPENDIX**

SWS LANDFILL GAS MONITORING (NOVEMBER 2010).....Appendix A  
LANDFILL GAS MONITORING DATA FORM (EXAMPLE)..... Appendix B  
LANDFILL GAS MONITORING PROBE COMPLETION LOGS ..... Appendix C

## 1 INTRODUCTION

### 1.1 BACKGROUND

The North Carolina Solid Waste Section (SWS) has requested that methane gas and other explosive landfill gases (LFG) be monitored to ensure that methane does not exceed the lower explosive limit (LEL) in the soil at the facility property boundary or 25 percent of the lower explosive limit within facility structures. If the concentration exceeds the specified limits, steps must be taken to ensure the protection of public health and a remediation plan must be implemented.

This *Landfill Gas Monitoring Plan*'s objective is to provide clear guidelines and procedures for field personnel when performing explosive gas monitoring. This plan applies to the entire Franklin County Solid Waste Facility located at 10 Landfill Road (SR 1153) near intersection with Timberlake Rd (SR1109) in Franklinton, NC. The facility is owned and operated by Franklin County under NC Solid Waste Permit No. 35-01. The facility contains a closed unlined municipal solid waste landfill (MSWLF), an operating beneficial fill area and a MSW transfer station (35-03T). The majority of the properties surrounding the facility are agricultural and a residential subdivision along "Pine Ridge Drive" adjoins to the east. Facility conditions or unforeseen sampling variables may warrant deviation from standard procedures, in which case alternative sampling procedures will conform to current NC Solid Waste Section guidelines and industry Standards. This LFG monitoring plan complies with the current version of the *NC Solid Waste Section Landfill Gas Monitoring Guidance* referenced henceforth as the *SWS Guidance Document*.

### 1.2 SITE GEOLOGY AND HYDROGEOLOGY

Franklin County is located in the NC Raleigh Belt which is characterized by gently rolling topography dissected by drainage features with narrow to moderately sloped sides. The lithology underlying the facility is saprolitic sandy silt overlaying gneiss and schist. Bedrock is not believed to influence LFG migration at this site since it is believed to be mostly beneath the water table which serves as the lower LFG confining feature.

Per the *SWS Guidance Document*, subsurface gas typically migrates above the groundwater table and is restricted laterally by streams. Two perennial tributaries flow north into wetlands and main channel of Cedar's Creek. The northern, eastern and most of the western property lines surrounding the waste units are isolated by these perennial hydraulic barriers which significantly decreases the potential for LFG migration beyond Franklin County's property boundaries. A USGS topographic map of the site is shown on **Figure 4**.

The uppermost aquifer across the entire site has been identified to be typically within the unconsolidated regolith. The natural ground elevation within the property boundary ranges from approximately 250 - 350 feet above mean sea level. The vertical LFG migration potential extent is the water table which ranges from approximately 0 to 45 feet below ground. MP-4 was installed in close proximity to the Transfer Station underground septic drain field. Although methane was not detected in MP-4 on September 29 and October 4, 2014 carbon dioxide levels were elevated (16%/volume). The septic system should be considered an alternative source if methane is detected above allowable limits at MP-4 in the future. Potentiometric groundwater contours of the uppermost aquifer from groundwater elevations reported in April 2014 are shown on **Figure 1**.

### **1.3 REGULATORY LIMITS**

Readings will be recorded quarterly and results will be kept in the facility operating records. Franklin County will follow all operational requirements for MSWLF facilities; ensuring the measured concentration of methane gas does not exceed the lower explosive limit (100% LEL or 5% by volume) at the facility boundary and (25% LEL or 1.25% by volume) in structures. If stabilized methane levels exceed these limits or upon SWS request the *Monitoring Data Form* and *Environmental Monitoring Report* sheet will be submitted to the SWS.

## **2 LANDFILL GAS MONITORING**

### **2.1 LANDFILL GAS PROBES**

#### **2.1.1 LANDFILL GAS PROBE LOCATIONS**

Franklin County Landfill facility consists of a closed unlined MSW landfill. Seven monitoring probes (MP-1 through MP-7) with an average spacing interval of 500 linear feet were installed on September 29, 2014 to monitor LFG levels along the south and east property lines originating from the closed MSWLF. The monitoring locations were chosen following careful consideration of spatial relationship between property boundaries, hydraulic barriers and both on and off-site structures. The layout of the monitoring system was previously discussed with the SWS on August 11, 2014 and the “pre-construction” plan was approved by the SWS on September 23, 2014.

A comprehensive facility wide color-coded drawing with an embedded table detailing the LFG monitoring locations is shown on **Figure 2**. Locations of probes GP-1 through GP-7 were surveyed by MESCO under supervision of a NC professional land surveyor.

LFG migration through soil is effectively bound by perennial water bodies on all sides except for along the northern boundary and half of the eastern boundary as shown **Figures 1 and 2**.

The closed MSWLF will be monitored by seven LFG probes (GP-1 through GP-7). Four on-site structures will also be monitored as described in Section 2.2. None of the probes are located within any future planned development areas; however, in the unlikely event their location inhibits any site development they will be properly abandoned per 15A NCAC2C.0113(d) following SWS notification.

### **2.1.2 LANDFILL GAS PROBE CONSTRUCTION SPECIFICATIONS**

Details of the existing LFG probe construction are shown on **Table 1**. All probes conform to specifications outlined in *SWS Guidance Document* with the exception the probes are constructed of 1” PVC (faster representative sample since less accumulated air to eradicate). All probes are equipped with a stopcock ball valve bushed to the well casing. However, a quick connect coupling threaded into the well cap or an equivalent device that allows air flow to be controlled at the wellhead may be used in the future if warranted as previously approved and shown on **Figure 3**.

### **2.2 STRUCTURE MONITORING**

The inside of four on-site structures (ATND\_BLG, OFFICE\_1, TRAN\_STN and SCALE\_HS) will be monitored quarterly for LFG accumulation in accordance with the *Guidance Document*. If new on-site structures (roof over 4 walls) are erected in the future they should also be monitored. On-site habitable structures are detailed on **Figures 1 & 2** and **Table 1**.

### **2.3 LANDFILL GAS MONITORING FREQUENCY**

LFG monitoring will be performed and documented on at least a quarterly basis (four times annually approximately three months apart). Monitoring frequency will not be decreased without pre-authorization by the SWS.

### **3 LANDFILL GAS SAMPLING PROCEDURE**

#### **3.1 EQUIPMENT**

Instrumentation must be capable of accurately reading percent methane, percent oxygen and percent carbon dioxide. Instruments shall be calibrated according to manufacturer's specifications prior to performing monitoring. Although other instrument(s) maybe available which meet or exceed these requirements that would also be deemed acceptable the most common instrument is a Landfill Gas Analyzer manufactured by LANDTEC which includes models such as GEM500, GEM2000 and GEM5000. Stopcock valves on monitoring probes should remain in a closed position until instrument tubing is tightly sealed.

#### **3.2 MONITORING PROCEDURE**

LFG monitoring will be performed by personnel that understand the principles of operation and use instruments per manufacturer's instructions. LFG monitoring including instrument calibration procedures shall be performed in accordance with procedures outlined in the most current NC SWS issued Landfill Gas Monitoring *Guidance Document*. A copy of the current *SWS Guidance Document* dated November 2010 is included in **Appendix A**. Deviation from procedures outlined in this plan may be warranted depending on facility conditions or unforeseen variables. Any variance from the methodology contained in the current *SWS Guidance Document* will be consistent with industry standards and be described in the associated LFG monitoring report.

### **4 RECORD KEEPING AND REPORTING**

#### **4.1 MONITORING DATA FORM**

LFG monitoring event results shall be recorded on a *Landfill Gas Monitoring Data Form*. The monitoring data form should contain at least the information outlined in the *SWS Guidance Document* as shown on the example form in **Appendix B**.

#### **4.2 MONITORING REPORTS**

A landfill gas monitoring report consisting of at a minimum the completed *Landfill Gas Monitoring Data Form* and a site drawing showing the location of each monitoring location shall be drafted shortly following every quarterly monitoring event.

#### **4.3 PERMANENT RECORD KEEPING**

Landfill gas monitoring records including monitoring plans, monitoring reports and remediation plans will be retained at the facility in an operating record and kept up to date as additional information becomes available. Reports which will include at least a completed *Monitoring Data Form* and *Environmental Monitoring Report* will be sent to the SWS only in the event methane is detected above allowable limits or upon request.

**5 CONTINGENCY PLAN**

If stabilized methane levels are detected above regulatory compliance levels, additional probe(s) may be installed closer towards the property boundary in order to determine the LFG migration extent. If stabilized methane readings are detected above regulatory limits at the facility boundary remedial actions may be required. The specific remedial actions taken to abate LFG migration will be chosen based on site specific circumstances and consistent with industry protocols. In the event facility conditions change which may hinder the effectiveness of this monitoring plan including but not limited to property relinquishment or construction of structures this plan is intended to be updated.


**6 CERTIFICATION OF PROFESSIONAL GEOLOGIST OR PROFESSIONAL ENGINEER**

This LFG monitoring plan is to be implemented at the Franklin County Landfill facility which operates under Permits 35-01. The landfill gas monitoring plan for this facility has been prepared by a qualified engineer who is licensed to practice in the State of North Carolina. The plan has been prepared based on knowledge of site conditions and familiarity with North Carolina solid waste rules and industry protocol. This certification is made in accordance with North Carolina Solid Waste Regulations, indicating this Landfill Gas Monitoring Plan should provide early detection of methane migration through the vadose zone, so as to be protective of public health and the environment. No other warranties, expressed or implied, are made.

Signed St R Gandy, Ph.D., PE

Printed Steven R. Gandy, Ph.D., PE

Date 10/30/14



# Tables

**Table 1: Landfill Gas Monitoring Location Details**


LFG Monitoring Location ID	Status	Type	Monitored Unit	Northing (Surveyed)	Easting (Surveyed)	Ground Elevation (Surveyed)	Proposed Sand Interval Exposed to LFG (ft BGS)		Depth to Groundwater <sup>1</sup> (ft BGS)	Predominant Screened Lithology
							Top	Bottom		
MP-1	Existing	Probe	MSWLF	839335.746	2183201.518	342.36	3	24.0	30.0 <sup>E</sup>	Saprolitic Silty Sand
MP-2	Existing	Probe	MSWLF	839375.880	2183580.322	343.17	3	32.0	32.0 <sup>O</sup>	Saprolitic Silty Sand
MP-3	Existing	Probe	MSWLF	839812.902	2184258.992	335.07	3	24.0	24.0 <sup>O</sup>	Saprolitic Silty Sand
MP-4	Existing	Probe	MSWLF	839941.341	2184541.036	336.63	3	26.5	39.0 <sup>E</sup>	Saprolitic Silty Sand
MP-5	Existing	Probe	MSWLF	840415.014	2184761.989	322.40	3	28.5	28.5 <sup>O</sup>	Saprolitic Silty Sand
MP-6	Existing	Probe	MSWLF	840960.554	2184691.573	295.17	3	8.0	8.0 <sup>O</sup>	Saprolitic Silty Sand
MP-7	Existing	Probe	MSWLF	841592.505	2184732.095	277.33	3	8.0	8.0 <sup>O</sup>	Saprolitic Silty Sand
ATND_BLG	Existing	Structure	MSWLF	-	-	-	-	-	25 <sup>E</sup>	-
OFFICE_1	Existing	Structure	MSWLF	-	-	-	-	-	25 <sup>E</sup>	-
TRAN_STN	Existing	Structure	MSWLF	-	-	-	-	-	25 <sup>E</sup>	-
SCALE_HS	Existing	Structure	MSWLF	-	-	-	-	-	25 <sup>E</sup>	-

Information compiled from prior hydrogeologic investigations documents, field observations on July 2, 2014 and September 29, 2014.

Probe locations surveyed by MESCO in October 2014 NC (NAD83)


<sup>1</sup> Depth to groundwater <sup>O</sup> = Observed, <sup>E</sup> = Estimated/Extrapolated

# Figures



**LEGEND**

- FRANKLIN OUTERMOST PROPERTY LINE
- CLOSED MSWLF ESTIMATED EXTENT OF WASTE
- PERENNIAL STREAM PER USGS MAPS
- INTERMITTENT STREAM
- POTENTIOMETRIC GROUNDWATER CONTOUR
- WETLANDS FROM GIS
- STRUCTURE TO BE MONITORED FOR LFG
- WATER MONITORING WELL
- LANDFILL GAS (LFG) MONITORING WELL



Groundwater Elevations  
April 29, 2014

WELL #	TOP OF CASING ELEVATION (FT AMSL)	DEPTH TO GROUNDWATER (FT BTOC)	GROUNDWATER POTENTIOMETRIC ELEVATION (FT AMSL)
MW-1	338.23	23.29	314.94
MW-1D	338.71	23.24	312.08*
MW-2	298.38	9.99	288.39
MW-3	278.85	16.34	262.51
MW-3D	277.61	13.85	262.14*
MW-4	268.54	8.20	260.34
MW-4D	268.19	6.45	258.91*
MW-4WR	na	na	na
MW-5	301.79	5.95	295.84
MW-6	264.89	8.65	256.24
MW-7	246.24	7.69	238.55
MW-8	261.25	6.59	254.66
MW-9	269.66	11.94	257.72
MW-10	265.18	8.85	256.33

NOTE:

AERIAL PHOTOGRAPHY WAS TAKEN FROM NCONEMAP AND IS DATED 2013

**FIGURE 1**

**Engineering Company, P.A.**  
P.O. BOX 349, BOONE, N.C. 28607  
(828) 262-1767  
LICENSE NUMBER: C-0281


**Municipal Services**  
P.O. BOX 97, GARNER, N.C. 27528  
(919) 772-5393  
LICENSE NUMBER: C-0281

**CLOSED UNLINED MSWLF  
FRANKLIN COUNTY  
FRANKLINTON  
NORTH CAROLINA**

DATE	REV.	DESCRIPTION


POTENTIOMETRIC MAP OF UPPERMOST AQUIFER  
APRIL 29, 2014

SCALE: SEE BAR SCALE  
DATE: 10/24/14  
DRWN BY: R. MOSS  
CHKD BY: J. PFOHL  
PROJECT NUMBER: G14106.0  
DRAWING NO. SHEET NO.  
FIGURE 1 1 OF 1



**LEGEND**

- FRANKLIN OUTERMOST PROPERTY LINE
- CLOSED MSWLF ESTIMATED EXTENT OF WASTE
- PERENNIAL STREAM PER USGS MAPS
- INTERMITTENT STREAM
- WETLANDS FROM GIS
- STRUCTURE PROPOSED TO BE MONITORED FOR LFG
- ▲ MW-2 WATER MONITORING WELL
- ⊕ MP-2 PROBE PROPOSED TO MONITOR LFG (SURVEYED)



Proposed Landfill Gas Monitoring Location Details

LFG Monitoring Location ID	Status	Type	Monitored Unit	Proposed Sand Interval Exposed to LFG (ft BGS)		Expected Depth to Groundwater (ft BGS)	Predominant Screened Lithology
				Top	Bottom		
MP-1	Proposed	Probe	MSWLF	3	30	10	Saprotic Sandy Silt
MP-2	Proposed	Probe	MSWLF	3	25	25	Saprotic Sandy Silt
MP-3	Proposed	Probe	MSWLF	3	32	32	Saprotic Sandy Silt
MP-4	Proposed	Probe	MSWLF	3	39	39	Saprotic Sandy Silt
MP-5	Proposed	Probe	MSWLF	3	28	28	Saprotic Sandy Silt
MP-6	Proposed	Probe	MSWLF	3*	7	7	Saprotic Sandy Silt
MP-7	Proposed	Probe	MSWLF	3*	7	7	Saprotic Sandy Silt
ATND BLDG	Existing	Structure	MSWLF	-	-	25	-
OFFICE_1	Existing	Structure	MSWLF	-	-	25	-
TRAN STN	Existing	Structure	MSWLF	-	-	25	-
SCALE HS	Existing	Structure	MSWLF	-	-	25	-

Information compiled from prior hydrogeologic investigations documents and field reconnaissance on July 2, 2014.  
 \* Sand pack may have to start as shallow as 1.0' bgs so vadose can be monitored due to shallow groundwater.

NOTE:  
 AERIAL PHOTOGRAPHY WAS TAKEN FROM NCONEMAP AND IS DATED 2013

**FIGURE 2**

**Engineering Company, P.A.**

P.O. BOX 349 BOONE, N.C. 28607  
 (828) 262-1767

**Municipal Services**

P.O. BOX 97, CARNER, N.C. 27529  
 (919) 772-5393

LICENSE NUMBER: C-0281

**CLOSED UNLINED MSWLF  
 FRANKLIN COUNTY  
 FRANKLINTON  
 NORTH CAROLINA**

DATE	BY	REVISION	DESCRIPTION

LANDFILL GAS MONITORING LOCATIONS

SCALE: SEE BAR SCALE  
 DATE: 7/28/14  
 DRWN. BY: R. MOSS  
 CHKD. BY: J. PFOHL  
 PROJECT NUMBER: G14106.0  
 DRAWING NO. SHEET NO.  
 FIGURE 2 1 OF 1

Figure 3  
Stop-Cock Valve Construction Details

## Ball Valve (Bushed onto Well Casing)



OR


## Quick Connect Coupling (Threaded into Cap)



OR  
Equivalent

# Site Vicinity Map

Franklin County Closed Unlined MSWLF(35-01)



## QUADRANGLE LEGEND

### ROAD CLASSIFICATION

Primary highway, hard surface		Light-duty road, hard or improved surface	
Secondary highway, hard surface		Unimproved road	
	Interstate Route		U. S. Route
	State Route		

NOTE: Topographical map assembled from corresponding subject region USGS 7.5-min quadrangles Franklinton and Louisburg.

**10 Landfill Road**  
**Off SR 1109 (Timberlake Rd)**  
**Franklinton, NC 27525**  
**Lat:36-03-17.1980**  
**Long:-78-22-34.6376**  
**Northing:839417.89**  
**Easting:2184367.15**



**FIGURE 4**

**Appendix A**  
**SWS Landfill Gas Monitoring**  
**Guidance Document**  
**(Intended to be most recent version)**

NORTH CAROLINA DEPARTMENT OF  
ENVIRONMENT AND NATURAL RESOURCES

DIVISION OF WASTE MANAGEMENT

SOLID WASTE SECTION

LANDFILL GAS MONITORING GUIDANCE

NOVEMBER 2010

TABLE OF CONTENTS

Section 1 – Introduction .....	Page 2
Section 2 – Factors Influencing Landfill Gas Generation and Migration .....	Page 3
Section 3 - Current Solid Waste Section Rules Pertaining to Landfill Gas Monitoring .....	Page 5
Section 4 – Landfill Gas Incidents and Explosions .....	Page 9
Section 5 – Landfill Gas Monitoring Wells.....	Page 11
Section 6 – Landfill Gas Monitoring Instrumentation .....	Page 14
Section 7 – References .....	Page 17
Section 8 – Suggested Outline for a Landfill Gas Monitoring Plan .....	Page 18
Section 9 – Checklist of Items to be Included in a Landfill Gas Monitoring Plan .....	Page 19

## **SECTION 1 - Introduction**

North Carolina Solid Waste Management Rules 15A NCAC 13B require quarterly monitoring of methane gas (at MSW landfills) and quarterly monitoring of methane and other explosive landfill gases (LFG) (at C&D and other landfills) to ensure that landfill gas does not exceed the lower explosive limit (LEL) at the facility property boundary or 25 percent of the lower explosive limit in facility structures. If the concentration exceeds the specified limits, steps must be taken to ensure the protection of public health and a remediation plan must be implemented immediately. A landfill gas monitoring plan is necessary to ensure that these performance standards are met and this guidance document was developed to assist in establishing a standardized procedure for the monitoring of landfill gas.

### ***Background***

Organic matter in landfills begins to decompose almost immediately after being placed in a disposal site. Putrescible wastes such as food products and sewage sludges begin to break down by biological processes very rapidly whereas paper, cardboard or cellulose based materials are slower to decompose. However, when conditions become favorable, most organic matter will decompose. The decomposition process typically goes through several stages that depend on conditions such as pH, temperature, and moisture content. The final stage results in the production of methane and although the rate of production may vary, most landfills produce methane.

### ***Landfill Gas Generation***

Landfill gas is a natural by-product of the anaerobic decomposition of organic waste in a landfill. The composition, quantity and rate of landfill gas generation are dependent on the types of waste that are decomposing and the level of microbial activity within the wastes. The decomposition of biodegradable waste begins with aerobic decomposition which lasts until the oxygen in the landfill is depleted. The anaerobic phase then begins, resulting in landfill gas production.

There are four stages of landfill gas composition: the first stage is characterized by elevated nitrogen levels and occurs when the landfill is new. The second stage is characterized by elevated carbon dioxide levels and occurs for a relatively short period of time after the initial stage is complete. The third and fourth stages are characterized by elevated methane concentrations and represent the active life of a landfill and the post-closure time frame.

Landfill gas is generally composed of 50-55% methane (CH<sub>4</sub>); 45-50% carbon dioxide (CO<sub>2</sub>); less than 5% nitrogen (N<sub>2</sub>); and less than 1% non-methane organic compounds. These individual gases generally remain co-mingled and do not naturally separate. The Solid Waste Section (SWS) Rules typically focus on methane (CH<sub>4</sub>) and its explosive properties due to public safety issues. Hydrogen sulfide (H<sub>2</sub>S) is also of particular concern in landfills and is typically recognized by its rotten egg odor. H<sub>2</sub>S is immediately dangerous to life and health at concentrations of 100 parts per million (ppm).

### ***Landfill Gas Migration***

The production of landfill gas creates a positive pressure within the landfill that forces the gas to migrate. Landfill gas migrates from place to place by diffusion and pressure gradient and will follow the path of least resistance. **Subsurface gas typically migrates above the groundwater table and is restricted laterally by streams.** Porous soils lying above the bedrock can serve as pathways to transmit large volumes of gas. Underground off-site migration is common and can be facilitated by the presence of pipelines, buried utility corridors or trenches located within or adjacent to the landfill boundaries. Movement depends on soil type and moisture, and migration distances of 1,500 feet have been observed. Barometric pressure also influences movement. Falling barometric pressure allows methane to migrate out of the landfill and into surrounding areas.

## **SECTION 2 - Factors Influencing Landfill Gas Generation and Migration**

Factors that affect landfill gas generation and migration through the subsurface include the following:

### ***Waste Composition***

The production of landfill gas is directly related to the amount of organic matter present in waste. The bacteria that break down the waste require small amounts of specific minerals such as calcium, potassium, magnesium and other micronutrients. Bacteria are able to thrive and produce landfill gas if the minerals/micronutrients are present. If the minerals/micronutrients are not present or if substances that inhibit bacterial growth exist, landfill gas production will occur at a reduced rate. Some forms of organic matter such as cellulose break down quickly whereas matter such as lignin breaks down more slowly. The rate at which landfill gas is produced depends on the proportions of each type of organic matter present in the waste.

### ***Moisture Content***

Landfills with higher moisture content generate higher concentrations of landfill gas in earlier stages of development (such as during leachate recirculation). Moisture accelerates the methanogenic process.

### ***Temperature***

Landfill bacteria are temperature dependant. They are able to survive and function below the freezing point, but they also function well at temperatures up to 65°C. Anaerobic bacteria produce small amounts of heat and may not be able to maintain the temperature of a shallow landfill when external temperatures decrease, so LFG generation may exhibit seasonal variations. Saturated landfills may not achieve ideal temperatures because the bacteria do not generate sufficient heat to raise the temperature of the excess water. Higher temperatures promote volatilization and chemical reactions with the waste so the trace gas component of landfill gas tends to increase with higher landfill temperatures.

### ***Age of Landfill***

Typically, landfills have an increasing generation of landfill gas for a number of years until closure at which time landfill gas generation reaches a peak and begins to subside. An evaluation of the age of the landfill and use of a landfill gas generation curve can be helpful in determining the likelihood of significant landfill gas concentrations from the landfill.

### ***Landfill Cap***

The type or presence of landfill cover can influence landfill gas generation and migration. Although a low permeability cap will reduce moisture and landfill gas generation over the longer term, initially, the installation of a landfill cap could drive landfill gas migration further from the landfill in the subsurface without proper ventilation (either passive or active). This is especially true in the case of unlined (unvented) landfills.

### ***Water Table***

Landfill gas movement in unlined landfills may be influenced by groundwater table variations. A rising water table could cause displacement and force upward movement of landfill gas.

### ***Man-made and Natural Conduits***

Structures such as drains, trenches, and buried utility corridors can act as conduits for landfill gas migration. Geologic features including fractured bedrock, porous soil, and permeable strata also provide conduits for landfill gas migration

### ***Landfill Liner Conditions***

The presence of a Subtitle-D (or equivalent) landfill liner has the capability to limit the lateral migration of landfill gas in the subsurface. Unlined landfills have no barrier to prevent lateral landfill gas migration in the subsurface.

### ***Weather Conditions***

Barometric pressure and precipitation have significant effects on landfill gas migration. Increased barometric pressure yields decreased landfill gas venting from the subsurface, until the pressure within the subsurface is greater than the atmospheric (barometric) pressure. Conversely, as the barometric pressure decreases, the landfill will vent the stored gas until pressure equilibrium is reached. Capping of a landfill can influence the effect of barometric pressure on landfill gas migration. Generally, a more permeable landfill cap will allow greater influence by barometric pressure than a less permeable landfill cap.

## **SECTION 3 – Current Solid Waste Section Rules Pertaining to Landfill Gas Monitoring**

**Web link to the 15A NCAC 13B rules - <http://portal.ncdenr.org/web/wm/sw/rules>**

### **15A NCAC 13B**

#### **.0101- DEFINITIONS**

.0101 (14) "Explosive gas" means Methane (CH<sub>4</sub>)

.0101(25) "Lower explosive limit" (LEL) means the lowest percent by volume of a mixture of explosive gases which will propagate a flame in air at 25 degrees Celsius and atmospheric pressure.

#### **.0503 - SITING AND DESIGN REQUIREMENTS FOR DISPOSAL FACILITIES**

.0503(2) A site shall meet the following design requirements:

- (a) The concentration of explosive gases generated by the site shall not exceed:
  - (i) twenty-five percent of the limit for the gases in site structures (excluding gas control or recovery system components); and
  - (ii) the lower explosive limit for the gases at the property boundary;

#### **.0543 - CLOSURE AND POST-CLOSURE REQUIREMENTS FOR C&DLF FACILITIES**

.0543(e) Post-closure criteria.

- (1) Following closure of each C&DLF unit, the owner and operator must conduct post-closure care. Postclosure care must be conducted for 30 years, except as provided under Subparagraph (2) of this Paragraph, and consist of at least the following:
  - (C) maintaining and operating the gas monitoring system in accordance with the requirements of Rule .0544 of this Section; and
- (2) The length of the post-closure care period may be:
  - (A) decreased by the Division if the owner or operator demonstrates that the reduced period is sufficient to protect human health and the environment and this demonstration is approved by the Division; or
  - (B) increased by the Division if the Division determines that the lengthened period is necessary to protect human health and the environment.

#### **.0544 - MONITORING PLANS AND REQUIREMENTS FOR C&DLF FACILITIES**

.0544(d) Gas Control Plan

- (1) Owners and operators of all C&DLF units must ensure that:
  - (A) the concentration of methane gas or other explosive gases generated by the facility does not exceed 25 percent of the lower explosive limit in on-site facility structures (excluding gas control or recovery system components);
  - (B) the concentration of methane gas or other explosive gases does not exceed the lower explosive limit for methane or other explosive gases at the facility property boundary; and
  - (C) the facility does not release methane gas or other explosive gases in any concentration that can be detected in offsite structures.
- (2) Owners and operators of all C&DLF units must implement a routine methane monitoring program to ensure that the standards of this Paragraph are met.
  - (A) The type of monitoring must be determined based on soil conditions, the Hydrogeologic conditions under and surrounding the facility, hydraulic conditions on and surrounding the facility, the location of facility structures and property boundaries, and the location of all offsite structures adjacent to property boundaries.

- (B) The frequency of monitoring shall be quarterly or as approved by the Division.
- (3) If methane or explosive gas levels exceeding the limits specified in Subparagraph (d)(1) of this Rule are detected, the owner and operator must:
  - (A) immediately take all steps necessary to ensure protection of human health and notify the Division;
  - (B) within seven days of detection, place in the operating record the methane or explosive gas levels detected and a description of the steps taken to protect human health; and
  - (C) within 60 days of detection, implement a remediation plan for the methane or explosive gas releases, place a copy of the plan in the operating record, and notify the Division that the plan has been implemented. The plan must describe the nature and extent of the problem and the proposed remedy.
- (4) Based on the need for an extension demonstrated by the operator, the Division may establish alternative schedules for demonstrating compliance with Parts (3)(B) and (3)(C) of this Paragraph.
- (5) For purposes of this Item, "lower explosive limit" means the lowest percent by volume of a mixture of explosive gases in air that will propagate a flame at 25 C and atmospheric pressure.

#### **.0566 - OPERATIONAL REQUIREMENTS FOR LAND CLEARING/INERT DEBRIS (LCID) LANDFILLS**

- .0566(13) The concentration of explosive gases generated by the facility shall not exceed:
  - (a) Twenty-five percent of the lower explosive limit for the gases in facility structures.
  - (b) The lower explosive limit for the gases at the property boundary.

#### **.1626 – OPERATIONAL REQUIREMENTS FOR MSWLF FACILITIES**

- .1626(4) Explosive gases control.
  - (a) Owners or operators of all MSWLF units must ensure that:
    - (i) The concentration of methane gas generated by the facility does not exceed 25 percent of the lower explosive limit for methane in facility structures (excluding gas control or recovery system components); and
    - (ii) The concentration of methane gas does not exceed the lower explosive limit for methane at the facility property boundary.
  - (b) Owners or operators of all MSWLF units must implement a routine methane monitoring program to ensure that the standards of (4)(a) are met. A permanent monitoring system shall be constructed on or before October 9, 1994. A temporary monitoring system shall be used prior to construction of the permanent system.
    - (i) The type and frequency of monitoring must be determined based on the following factors:
      - (A) Soil conditions;
      - (B) The hydrogeologic conditions surrounding the facility;
      - (C) The hydraulic conditions surrounding the facility; and
      - (D) The location of facility structures and property boundaries.
    - (ii) The minimum frequency of monitoring shall be quarterly.
  - (c) If methane gas levels exceeding the limits specified in (4)(a) are detected, the owner or operator must:
    - (i) Immediately take all necessary steps to ensure protection of human health and notify the Division;
    - (ii) Within seven days of detection, place in the operating record the methane gas levels detected and a description of the steps taken to protect human health; and
    - (iii) Within 60 days of detection, implement a remediation plan for the methane gas releases, place a copy of the plan in the operating record, and notify the Division that the

plan has been implemented. The plan shall describe the nature and extent of the problem and the proposed remedy.

(iv) Based on the need for an extension demonstrated by the operator, the Division may establish alternative schedules for demonstrating compliance with (4)(c)(ii) and (iii) of this Rule.

(d) For purposes of this Item, "lower explosive limit" means the lowest percent by volume of a mixture of explosive gases in air that will propagate a flame at 25°C and atmospheric pressure.

.1626(10) Recordkeeping requirements.

(a) The owner or operator of a MSWLF unit must record and retain at the facility, or an alternative location near the facility approved by the Division, in an operating record the following information as it becomes available:

(iii) Gas monitoring results and any remediation plans required by Item (4) of this Rule;

### **.1627 – CLOSURE AND POST CLOSURE REQUIREMENTS FOR MSWLF ACTIVITIES**

.1627(d) Post-Closure Criteria

(1) Following closure of each MSWLF unit, the owner or operator shall conduct post-closure care. Post-closure care shall be conducted for 30 years, except as provided under Subparagraph (2) of this Paragraph, and consist of at least the following:

(D)-Maintaining and operating the gas monitoring system in accordance with the requirements of Rule .1626 of this Section.

(2) The length of the post-closure care period may be:

(A) Decreased by the Division if the owner or operator demonstrates that the reduced period is sufficient to protect human health and the environment and this demonstration is approved by the Division; or

(B) Increased by the Division if the Division determines that the lengthened period is necessary to protect human health and the environment.

(3) Following completion of the post-closure care period for each MSWLF unit, the owner or operator shall notify the Division that a certification, signed by a registered professional engineer, verifying that post-closure care has been completed in accordance with the post-closure plan, has been placed in the operating record.

### **NOTES:**

Based on the referenced rules above, the following words / phrases are presently in the Solid Waste Section rules pertaining to methane and explosive landfill gas.

Rule .0101(14) states: "*Explosive gas means Methane (CH)*".

Rule .0503 (2)(a) refers to "*explosive gases*".

Rule .0544(d) refers to "*Gas Control Plan*"

Rule .0544(d)(1) refers to "*methane or other explosive gases*".

Rule .0544(d)(2) refers to "*methane monitoring program*"

Rule .0544(d)(3) refers to "*methane or explosive gas levels*"

Rule .0566 (13) refers to "*explosive gases*".

Rule .1626 (4) refers to "*explosive gases control*"

Rule .1626(4)(a-b) refers to "*methane monitoring*" and "*methane monitoring program*".

### ***Monitoring Goals***

Landfill design and landfill gas monitoring regulations in North Carolina require that there not be an exceedance of 100% of the Lower Explosion Limit (LEL) (equivalent to 5% methane) at the property boundary, or 25% LEL in on-site structures. These regulations were developed over time to protect the health and safety of the citizens of North Carolina and the U.S. from the asphyxiation and explosive hazards of landfill gas.

### ***NC Rule History***

A review of NC landfill guidance documents and regulations from 1972 to the present indicates that from 1972 through 1982, there was no mention of design requirements regarding the control of landfill gas, nor were there any landfill monitoring requirements for landfill gas. In 1982, the regulations were changed to require that sanitary landfill design prevent landfill gas concentrations of 100% LEL at the property boundary line and 25% inside on-site structures. Although a design requirement was added, no design requirement was established to determine if the design requirement was being met. In 1993 with the establishment of .1600 rules, requirements for designs to limit landfill gas levels to below 100% at the property boundary line and 25% in on-site structures and monitoring of landfill gas concentrations around the perimeter of the landfill and inside on-site structures were adopted.

## SECTION 4 – Landfill Gas Incidents and Explosions

### *Hazards Involving Landfill Gas*

Landfill fires may or may not be directly caused by landfill gas. The primary concern with these fires is air contamination from the resulting smoke; however they also present a variety of additional problems. In addition to concerns with containing and extinguishing landfill fires, potential reactions involving unknown chemicals in the landfill can cause uncertain hazards. Discarded consumer products in a landfill, such as pesticides, paints, solvents, cleaners, and other material can be the source of chemical releases. Heat from the fire can cause chemicals to volatilize, breakdown, and enter the environment. Also to be considered is the presence of other combustible gases in addition to methane. Whenever an environmental investigation of a landfill is prompted by odorous compounds or explosive gases, the presence of toxic substances should also be investigated. One example is hydrogen sulfide (H<sub>2</sub>S) that can cause asphyxiation and is flammable. An analysis should include alkyl benzenes, sulfur compounds, vinyl chloride, and methane, and other products associated with industrial wastes, construction and debris waste, and normal organic and inorganic waste.

Fires and explosion hazards become a concern when gases collect in confined spaces. Buildings, basements, and pits are typically regarded as confined spaces. However, landfill gases also collect in and migrate to cracks in the landfill cover, leachate “springs”, cracks in adjacent structures, paved parking areas, etc. Fires can occur on the surface and underground. Surface fires involve recently buried waste near the surface in an aerobic decomposing layer, typically 1 to 4 feet below ground. These fires can be intensified by subsurface landfill gas and spread throughout the landfill. Subsurface fires occur deeper within the landfill, involve material buried for months or years, and can burn for days and months.

The following is a brief summary of some incidents involving landfill gas migration from landfills:

- 2007 Four employees died as a result of exposure to high concentrations of hydrogen sulfide while attempting to repair a leachate pump at a C&D landfill in Superior, Wisconsin (Journal of Environmental Health 2008).
- 1999 An 8-year old girl was burned on her arms and legs when playing in an Atlanta, Georgia playground. The area was reportedly used as an illegal dumping ground many years ago (Atlanta Journal-Constitution 1999).
- 1994 While playing soccer in a park built over an old landfill in Charlotte, North Carolina, a woman was seriously burned by a methane explosion (Charlotte Observer 1994).
- 1987 Offsite landfill gas migration is suspected to have caused a house to explode in Pittsburgh, Pennsylvania (EPA 1991).
- 1984 Landfill gas migrated to and destroyed one house near a landfill in Akron, Ohio. Ten houses were temporarily evacuated (EPA 1991).
- 1983 An explosion destroyed a residence across the street from a landfill in Cincinnati, Ohio. Minor injuries were reported (EPA 1991).
- 1975 In Sheridan, Colorado, landfill gas accumulated in a storm drain pipe that ran through a landfill. An explosion occurred when several children playing in the pipe lit a candle, resulting in serious injury.

1969 Methane gas migrated from an adjacent landfill into the basement of an armory in Winston-Salem, North Carolina. A lit cigarette caused the gas to explode, killing three men and seriously injuring five others (USACE 1984).

## SECTION 5 - Landfill Gas Monitoring Wells

### *Locations*

Landfill gas monitoring well locations will be site specific depending upon site geology, depth to groundwater, surface water features, on-site and off-site structures and sensitive receptors. The landfill gas monitoring wells must be spaced no more than 500 feet apart depending upon site specifics. A readily accessible, unobstructed path must be maintained so that landfill gas monitoring wells are always accessible using four-wheel drive vehicles. Regardless of site specifics, the permittee must obtain approval from the Solid Waste Section for the design and installation of any landfill gas monitoring well system.

### *Well Construction and Installation*

Landfill gas monitoring wells are the same as groundwater monitoring wells with two exceptions. Landfill gas monitoring wells are installed just above the water table within the unsaturated zone and are equipped with a stopcock valve or a quick connect coupling on the cap, which allows for accurate landfill gas measurements. The stopcock valve must be equipped with flexible tubing and a barb connection that will fit the gas meter's inlet tube. The stopcock valve or a quick connect coupling must be closed between monitoring events. The landfill gas monitoring well must also be capped, locked, and labeled with a permanently affixed identification plate stating the well contractor name and certification number, date of well completion, total depth of well, screen length and well ID number. See detailed schematics of a landfill gas monitoring well (Figure 1).

1" or

The depth of each landfill gas monitoring well will be site specific depending upon depth to groundwater. Landfill gas monitoring wells must be constructed the same as groundwater monitoring wells as described in 15A NCAC Subchapter 2C. Typically landfill gas monitoring wells must be installed using 2" PVC piping and screen. The screen length, also site specific, must span the majority of the unsaturated zone while still allowing for proper well construction. A North Carolina Licensed/Professional Geologist must be present to supervise the installation of all landfill gas monitoring wells. The exact locations, screened intervals, and nesting of the wells must be approved by the Solid Waste Section Hydrogeologist prior to landfill gas monitoring well installation. Each landfill gas monitoring well must be surveyed for location and elevation by a North Carolina Registered Land Surveyor. Within thirty (30) days of the completed construction of each new landfill gas monitoring well, the well construction record (Division of Water Quality form GW-1b) and the boring log/well detail diagram of each well must be submitted to the Solid Waste Section. The submittal must also include a scaled topographic map showing the location and identification of new, existing and abandoned landfill gas monitoring wells.

### *Nested and Clustered Landfill Gas Monitoring Wells*

Nested and/or clustered landfill gas monitoring wells may be required in unsaturated zones of 45 feet or more to measure specific depths of the unsaturated zone. Initially, the installation of one long screen shall be sufficient. If a monitoring event shows an exceedance of the lower explosive limit, then the Solid Waste Section may require the installation of nested and/or clustered landfill gas monitoring wells.

### *Abandonment of Wells*

An abandonment record must be submitted to the Solid Waste Section within 30 (thirty) days of the abandonment of a landfill gas monitoring well. The landfill gas monitoring well(s) must be overdrilled and sealed with grout in accordance with 15A NCAC 2C .0113(d) and certified by a North Carolina Licensed/Professional Geologist.

if located within a waste unit footprint

**Professional Certification**

The certification statement below must be signed and sealed by a Professional Geologist and submitted with the Landfill Gas Monitoring Plan.

The landfill gas monitoring plan for this facility has been prepared by a qualified geologist who is licensed to practice in the State of North Carolina. The plan has been prepared based on first-hand knowledge of site conditions and familiarity with North Carolina solid waste rules and industry standard protocol. This certification is made in accordance with North Carolina Solid Waste Regulations, indicating this Landfill Gas Monitoring Plan should provide early detection of ~~any release of hazardous constituents to the uppermost aquifer~~, so as to be protective of public health and the environment. No other warranties, expressed or implied, are made.

Signed \_\_\_\_\_


methane migration through the vadose

Printed \_\_\_\_\_

Date \_\_\_\_\_

Not valid unless this document bears the seal of the above mentioned licensed professional.

Figure 1 – Landfill Gas Monitoring Well Detail



## **SECTION 6 – Landfill Gas Monitoring Instrumentation**

The person using the landfill gas monitoring instrument must understand the principles of operation and follow the manufacturer's instructions. This includes calibrating the instrument according to the manufacturer's specifications. Include the following on the top portion of the landfill gas monitoring form (See example below) : facility name, permit number, type and serial number of gas monitoring instrument, calibration date of the instrument, date and time of field calibration, type of gas used for field calibration (15/15 or 35/50), expiration date of field calibration gas canister, date of landfill gas monitoring event, name and position of sample collector, pump rate of instrument being used, ambient air temperature, and general weather conditions. Verification that the equipment was calibrated in accordance with the manufacturer's specifications is also required. When determining which field calibration gas to use, take into consideration the expected levels of methane in the landfill gas monitoring wells. If the methane levels are expected to be low, use the 15/15 gas canister (15% CO<sub>2</sub>/15% CH<sub>4</sub>). If the methane levels are expected to be high, use the 35/50 gas canister (35% CO<sub>2</sub>/50% CH<sub>4</sub>).

For every landfill gas monitoring well, please include the following: verification of sample tube purge prior to each sample taken (should be one minute), the time pumped in seconds (should be at least one minute), barometric pressure, time stabilized reading collected, percent lower explosive limit, percent methane by volume, percent oxygen, percent carbon dioxide, and any observations or comments. Most modern gas monitoring instruments will measure percent oxygen and carbon dioxide in addition to the methane and display the results on the same instrument. Recording the levels of percent oxygen and carbon dioxide should require little or no extra effort.

The landfill gas monitoring data form (See example below) and results should be retained in the facility's operating record unless an exceedance has occurred and/or is requested by the Solid Waste Section.

Landfill gas monitoring readings from non-calibrated or inaccurately calibrated instruments are not reliable, and will therefore be rejected by the Solid Waste Section. Landfill gas monitoring readings collected with monitoring equipment that was not designed for landfill gas monitoring will also be rejected by the Solid Waste Section. There are several different landfill gas monitoring instruments on the market which may be used in order to obtain all of the information required by the Solid Waste Section.

### ***Monitoring Times***

Monitoring times are also important when conducting landfill gas monitoring. Proper landfill gas monitoring should include sampling during times when landfill gas is most likely to migrate. Landfill gas can migrate and accumulate not only in landfill gas monitoring wells; it can also migrate and accumulate in buildings and other structures. Because subsurface gas pressures are considered to be at a maximum during the afternoon hours, monitoring should be conducted in the afternoon or whenever the barometric pressure is low.

Scientific evidence also indicates that weather and soil conditions influence the migration of landfill gas. Barometric pressure and precipitation have significant effects on landfill gas migration. Increased barometric pressure generates decreased landfill gas venting from the subsurface, until the pressure within the subsurface is greater than the atmospheric (barometric) pressure. On the other hand, when the barometric pressure decreases, the landfill will vent the stored gas until a pressure equilibrium is reached. Capping of a landfill can influence the effect of barometric pressure on landfill gas migration. Generally, a more permeable landfill cap will allow greater influence by barometric pressure than a less permeable

landfill cap. As a result, landfill gas monitoring should be conducted when the barometric pressure is low and soils are saturated. During the winter season when snow cover is just beginning to melt or when the ground is frozen or ice covered, landfill gas monitoring should be conducted when the barometric pressure is low.

### ***Landfill Gas Sampling Procedures***

Any accumulation of landfill gas in the landfill gas monitoring wells is the result of landfill gas migration. The following procedure is a recommended example for conducting landfill gas monitoring well sampling, but always read and follow the manufacturer's instructions because each instrument will be different.

**Step 1** – Calibrate the instrument according to the manufacturer's specifications. In addition, prepare the instrument for monitoring by allowing it to properly warm up as directed by the manufacturer. Make sure the static pressure shows a reading of zero on the instrument prior to taking the first sample.

**Step 2** – Purge sample tube for at least one minute prior to taking reading. Connect the instrument tubing to the landfill gas monitoring well cap fitted with a stopcock valve or quick connect coupling.

**Step 3** – Open the valve and record the initial reading and then the stabilized reading. A stable reading is one that does not vary more than 0.5 percent by volume on the instrument's scale.

**Step 4** - Record the stabilized reading including the oxygen concentration and barometric pressure. A proper reading should have two percent oxygen by volume or less. If levels of oxygen are higher, it may indicate that air is being drawn into the system giving a false reading.

**Step 5** – Turn the stopcock valve to the off position and disconnect the tubing.

**Step 6** – Proceed to the next landfill gas monitoring well and repeat Steps 2 – 5.

### ***Landfill Gas Constituent Sampling and Analysis***

Sampling of landfill gas to determine volume percentages/concentrations of each constituent can be accomplished through the use of canisters which are specifically designed for landfill gas analysis.

Several analytical methods are available to determine the concentrations of a variety of constituents.

Typically, landfill gas analysis of this type is performed to determine the non-methane organic compounds emission rate for Tier 2 testing under the Clean Air Act (Title V Subpart WWW 60.754).

Isotopic identification of landfill methane can be accomplished to identify one source of methane from another. In this case, isotopes of carbon and hydrogen in the methane are analyzed to determine the methane source.

**NC Division of Waste Management - Solid Waste Section**

**Landfill Gas Monitoring Data Form**

**Notice:** This form and any information attached to it are "Public Records" as defined in NC General Statute 132-1. As such, these documents are available for inspection and examination by any person upon request (NC General Statute 132-6).

Facility Name: \_\_\_\_\_ Permit Number: \_\_\_\_\_

Date of Sampling: \_\_\_\_\_ NC Landfill Rule (.0500 or .1600): \_\_\_\_\_

Name and Position of Sample Collector: \_\_\_\_\_

Type and Serial Number of Gas Meter: \_\_\_\_\_ Calibration Date of Gas Meter: \_\_\_\_\_

Date and Time of Field Calibration: \_\_\_\_\_

Type of Field Calibration Gas (15/15 or 35/50): \_\_\_\_\_ Expiration Date of Field Calibration Gas Canister: \_\_\_\_\_

Pump Rate of Gas Meter: \_\_\_\_\_

Ambient Air Temperature: \_\_\_\_\_ Barometric Pressure: \_\_\_\_\_ General Weather Conditions: \_\_\_\_\_

**Instructions:** Under "Location or LFG Well" identify the monitoring wells or describe the location for other tests (e.g., inside buildings). A drawing showing the location of test must be attached. Report methane readings in both % LEL and % methane by volume. A reading in percent methane by volume can be converted to % LEL as follows: % methane by volume = % LEL/20

Location or LFG Well ID	Sample Tube Purge	Time	Time Pumped (s)	Initial %LEL	Stabilized %LEL	%CH4 by Volume	%O2	%CO2	Notes

If your facility has more gas monitoring locations than there is room on this form, please attach additional sheets listing the same information as contained on this form.

**Certification**

**To the best of my knowledge, the information reported and statements made on this data submittal and attachments are true and correct. I am aware that there are significant penalties for making any false statement, representation, or certification including the possibility of a fine and imprisonment.**

\_\_\_\_\_  
SIGNATURE

\_\_\_\_\_  
TITLE

## SECTION 7 - References

Agency for Toxic Substances & Disease Registry. “Landfill Gas Primer- An Overview for Environmental Health Professionals. 2001.” <http://www.atsdr.cdc.gov/HAC/landfill/html/toc.html> (accessed February 24, 2010).

California Environmental Protection Agency. “Landfill Gas Monitoring Well Functionality at 20 California Landfills, 2008”. <http://www.calrecycle.ca.gov/Publications/Organics/2008022.pdf> (accessed February 24 2010).

Florida Department of Environmental Protection. Gas Management Systems, under Rule 62-701.530. [http://www.dep.state.fl.us/waste/quick\\_topics/rules/default.htm](http://www.dep.state.fl.us/waste/quick_topics/rules/default.htm) (accessed February 24, 2010).

Missouri Department of Natural Resources, Flood Grant Team. “An Analysis of Landfill Gas Monitoring Well Design and Construction, 2007”. [http://www.clu-in.org/conf/itrc/directpush/prez/Missouri\\_Study.pdf](http://www.clu-in.org/conf/itrc/directpush/prez/Missouri_Study.pdf) (accessed February 24, 2010).

Missouri Department of Natural Resources. “Design and Construction of Landfill Gas Monitoring Wells”. <http://www.dnr.missouri.gov/pubs/pub2054.pdf> (accessed February 24, 2010).

Wisconsin Department of Natural Resources. Environmental Monitoring for Landfills, under Chapter NR 507.22. <http://www.dnr.state.wi.us/org/aw/wm/information/wiacss.htm> (accessed February 24, 2010).

“Landfill Gas-an Overview” Landfill-gas.com. Web, 22, Feb. 2010  
<http://www.landfill-gas.com/webpage -LFG-overview.doc>

## **SECTION 8 – Suggested Outline for a Landfill Gas Monitoring Plan**

1. Introduction
  - 1.1. Background (project overview, site observations, NCDENR rules referenced)
  - 1.2. Site Geology with discussion of groundwater depth and flow (potentiometric surface map)
  - 1.3. Regulatory Limits
2. Landfill Gas Monitoring
  - 2.1. Landfill Gas Monitoring Well Locations (discussion of reasoning behind proposed locations, discussion of well construction, reference map showing proposed locations, reference table displaying well ID, well depth, screen interval and depth to groundwater)
  - 2.2. Structure and Ambient Sampling
  - 2.3. Landfill Gas Monitoring Frequency
3. Landfill Gas Sampling Procedures
  - 3.1. Detection Equipment Used (discussion of calibration procedures)
  - 3.2. Landfill Gas Sampling Procedure
4. Record Keeping and Reporting
  - 4.1. Landfill Gas Monitoring Data Form
  - 4.2. Sampling Reports
  - 4.3. Permanent Record Keeping
5. Contingency Plan
6. Certification of Professional Geologist
7. Certification of Registered Land Surveyor

### **Figures**

Map displaying proposed landfill gas monitoring well locations

Potentiometric Surface Map

Diagram showing construction of stopcock valve or quick connect coupling on well cap

Diagram showing well construction of each landfill gas monitoring well

### **Table**

Table displaying well ID, well depth, screen interval, depth to groundwater

Example of landfill gas monitoring data form

## **SECTION 9 – Checklist of Items to be Included in a Landfill Gas Monitoring Plan**

1. Depth to groundwater discussion
2. Well locations
  - a. Number of wells
  - b. Well spacing
3. Instrumentation being used
  - a. Calibration procedures
4. Sampling procedures as per the manufacture's instructions
5. Map of well locations
6. Table describing each well location
  - a. Well ID
  - b. Well depth
  - c. Screen interval
  - d. Depth to groundwater
  - e. Subsurface lithology
7. Diagram of cap construction w/ stopcock valve or quick connect coupling
8. Diagram of well construction
9. Potentiometric surface map
10. Professional Geologist certification
11. Registered Land Surveyor certification

**Appendix B**  
**Landfill Gas Monitoring Data Form**  
**(Intended to be most recent version)**



**Appendix C**  
**LFG Probe Completion Logs**

MP-1

**WELL CONSTRUCTION RECORD**

This form can be used for single or multiple wells

**1. Well Contractor Information:**

Steve Thompson

Well Contractor Name

3579-A

NC Well Contractor Certification Number

Akers Environmental

Company Name

**2. Well Construction Permit #:**

List all applicable well permits (i.e. County, State, Variance, Injection, etc.)

**3. Well Use (check well use):**

**Water Supply Well:**

- Agricultural  Municipal/Public
- Geothermal (Heating/Cooling Supply)  Residential Water Supply (single)
- Industrial/Commercial  Residential Water Supply (shared)
- Irrigation

**Non-Water Supply Well:**

- Monitoring LFG Migration Monitoring  Recovery

**Injection Well:**

- Aquifer Recharge  Groundwater Remediation
- Aquifer Storage and Recovery  Salinity Barrier
- Aquifer Test  Stormwater Drainage
- Experimental Technology  Subsidence Control
- Geothermal (Closed Loop)  Tracer
- Geothermal (Heating/Cooling Return)  Other (explain under #21 Remarks)

4. Date Well(s) Completed: 9/29/14 Well ID# MP-1

**5a. Well Location:**

Franklin Co. Landfill

35-01

Facility/Owner Name

Facility ID# (if applicable)

10 Landfill Road

Physical Address, City, and Zip

Franklinton 27525

007591

County

Parcel Identification No. (PIN)

**5b. Latitude and Longitude in degrees/minutes/seconds or decimal degrees:**

(if well field, one lat/long is sufficient)

36.054577 N 78.380324 W

6. Is (are) the well(s):  Permanent or  Temporary

7. Is this a repair to an existing well:  Yes or  No

If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. Number of wells constructed: 1  
For multiple injection or non-water supply wells ONLY with the same construction, you can submit one form.

9. Total well depth below land surface: 24 (ft.)  
For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: Dry (ft.)  
If water level is above casing, use "+"

11. Borehole diameter: 2.5 (in.)

12. Well construction method: direct push  
(i.e. auger, rotary, cable, direct push, etc.)

**FOR WATER SUPPLY WELLS ONLY:**

13a. Yield (gpm) \_\_\_\_\_ Method of test: \_\_\_\_\_

13b. Disinfection type: \_\_\_\_\_ Amount: \_\_\_\_\_

For Internal Use ONLY:

**14. WATER ZONES**

FROM	TO	DESCRIPTION
ft.	ft.	Dry
ft.	ft.	

**15. OUTER CASING (for multi-cased wells) OR LINER (if applicable)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
ft.	ft.	in.		

**16. INNER CASING OR TUBING (geothermal closed-loop)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
ft.	ft.	in.		
ft.	ft.	in.		

**17. SCREEN**

FROM	TO	DIAMETER	SLOT SIZE	THICKNESS	MATERIAL
3.5 ft.	22.40 ft.	1 in.	0.01"	sch40	PVC
ft.	ft.	in.			

**18. GROUT**

FROM	TO	MATERIAL	EMPLACEMENT METHOD & AMOUNT
0 ft.	2.5 ft.	Concrete	Mix & pour 400 lbs
2.5 ft.	3.0 ft.	Bent. Chips	Pour 15 lbs than hydrated
ft.	ft.		

**19. SAND/GRAVEL PACK (if applicable)**

FROM	TO	MATERIAL	EMPLACEMENT METHOD
3.0 ft.	24 ft.	#3 Filter Sand	Gravity Pour
ft.	ft.		

**20. DRILLING LOG (attach additional sheets if necessary)**

FROM	TO	DESCRIPTION (color, hardness, soil/rock type, grain size, etc.)
0 ft.	0.5 ft.	TOP SOIL; Dark Brown with vegetation
0.5 ft.	4 ft.	SILTY SAND w/ CLAY; Gray, coarse
4 ft.	12 ft.	SILTY SAND; Gray, mottled, coarse
12 ft.	24 ft.	SILTY SAND; White, coarse
24 ft.	ft.	ROCK, refusal
ft.	ft.	
ft.	ft.	

**21. REMARKS**

LFG Migration Monitoring Well.  
Locking steel above ground case & pad installed.

**22. Certification:**

 10/14/14  
Signature of Certified Well Contractor Date

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

**23. Site diagram or additional well details:**

You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

**SUBMITTAL INSTRUCTIONS**

24a. **For All Wells:** Submit this form within 30 days of completion of well construction to the following:


Division of Water Resources, Information Processing Unit,  
1617 Mail Service Center, Raleigh, NC 27699-1617

24b. **For Injection Wells ONLY:** In addition to sending the form to the address in 24a above, also submit a copy of this form within 30 days of completion of well construction to the following:

Division of Water Resources, Underground Injection Control Program,  
1636 Mail Service Center, Raleigh, NC 27699-1636


**24c. For Water Supply & Injection Wells:**

Also submit one copy of this form within 30 days of completion of well construction to the county health department of the county where constructed.



**LEGEND**

- FRANKLIN OUTWAST PROPERTY LINE
- - - - - CLOSED MSWLF ESTIMATED EXTENT OF WASTE
- - - - - FEDERAL STREAM PER USGS MAPS
- - - - - INTERMITTENT STREAM
- [Hatched Box] WETLANDS FROM GIS
- [Rectangle] STRUCTURE MONITORED FOR LFG
- [Circle with X] MW-2 WATER MONITORING WELL
- [Circle with Arrow] MP-2 LFG MONITORING POINT (NOT SURVEYED LOCATION)



Landfill Gas Monitoring Location Details

LFG Monitoring Location ID	Status	Type	Monitoring Use	Estimated Extent of LFG (ft)	Depth to Groundwater (ft)	Prevalence & Comment
MP-1	Active	Point	CH4	10	10	Monitoring of CH4
MP-2	Active	Point	CH4	10	10	Monitoring of CH4
MP-3	Active	Point	CH4	10	10	Monitoring of CH4
MP-4	Active	Point	CH4	10	10	Monitoring of CH4
MP-5	Active	Point	CH4	10	10	Monitoring of CH4
MP-6	Active	Point	CH4	10	10	Monitoring of CH4
MP-7	Active	Point	CH4	10	10	Monitoring of CH4
MP-8	Active	Point	CH4	10	10	Monitoring of CH4
MP-9	Active	Point	CH4	10	10	Monitoring of CH4
MP-10	Active	Point	CH4	10	10	Monitoring of CH4
MP-11	Active	Point	CH4	10	10	Monitoring of CH4
MP-12	Active	Point	CH4	10	10	Monitoring of CH4
MP-13	Active	Point	CH4	10	10	Monitoring of CH4
MP-14	Active	Point	CH4	10	10	Monitoring of CH4
MP-15	Active	Point	CH4	10	10	Monitoring of CH4
MP-16	Active	Point	CH4	10	10	Monitoring of CH4
MP-17	Active	Point	CH4	10	10	Monitoring of CH4
MP-18	Active	Point	CH4	10	10	Monitoring of CH4
MP-19	Active	Point	CH4	10	10	Monitoring of CH4
MP-20	Active	Point	CH4	10	10	Monitoring of CH4
MP-21	Active	Point	CH4	10	10	Monitoring of CH4
MP-22	Active	Point	CH4	10	10	Monitoring of CH4
MP-23	Active	Point	CH4	10	10	Monitoring of CH4
MP-24	Active	Point	CH4	10	10	Monitoring of CH4
MP-25	Active	Point	CH4	10	10	Monitoring of CH4
MP-26	Active	Point	CH4	10	10	Monitoring of CH4
MP-27	Active	Point	CH4	10	10	Monitoring of CH4
MP-28	Active	Point	CH4	10	10	Monitoring of CH4
MP-29	Active	Point	CH4	10	10	Monitoring of CH4
MP-30	Active	Point	CH4	10	10	Monitoring of CH4
MP-31	Active	Point	CH4	10	10	Monitoring of CH4
MP-32	Active	Point	CH4	10	10	Monitoring of CH4
MP-33	Active	Point	CH4	10	10	Monitoring of CH4
MP-34	Active	Point	CH4	10	10	Monitoring of CH4
MP-35	Active	Point	CH4	10	10	Monitoring of CH4
MP-36	Active	Point	CH4	10	10	Monitoring of CH4
MP-37	Active	Point	CH4	10	10	Monitoring of CH4
MP-38	Active	Point	CH4	10	10	Monitoring of CH4
MP-39	Active	Point	CH4	10	10	Monitoring of CH4
MP-40	Active	Point	CH4	10	10	Monitoring of CH4
MP-41	Active	Point	CH4	10	10	Monitoring of CH4
MP-42	Active	Point	CH4	10	10	Monitoring of CH4
MP-43	Active	Point	CH4	10	10	Monitoring of CH4
MP-44	Active	Point	CH4	10	10	Monitoring of CH4
MP-45	Active	Point	CH4	10	10	Monitoring of CH4
MP-46	Active	Point	CH4	10	10	Monitoring of CH4
MP-47	Active	Point	CH4	10	10	Monitoring of CH4
MP-48	Active	Point	CH4	10	10	Monitoring of CH4
MP-49	Active	Point	CH4	10	10	Monitoring of CH4
MP-50	Active	Point	CH4	10	10	Monitoring of CH4

NOTE:  
AERIAL PHOTOGRAPHY WAS TAKEN FROM NCONEMAP AND IS DATED 2013

**FIGURE 1**

**Engineering Company, P.A.**  
  
**Municipal Services, Inc.**  
 P.O. BOX 987 CARRIER, N.C. 27513  
 (910) 772-5333  
 LICENSE NUMBER: C-1526

**CLOSED UNLINED MSLWF  
FRANKLIN COUNTY  
FRANKLINTON  
NORTH CAROLINA**

DATE	BY	REVISION

PROJECT: SET BAR SCALE  
 DATE: 12/14/14  
 DRAWN BY: J. FITZ  
 CHECKED BY: J. FITZ  
 PROJECT NUMBER: G14106.0  
 SHEET NO.: 1 OF 1

MP-2

**WELL CONSTRUCTION RECORD**

This form can be used for single or multiple wells

**1. Well Contractor Information:**

Steve Thompson

Well Contractor Name

3579-A

NC Well Contractor Certification Number

Akers Environmental

Company Name

**2. Well Construction Permit #:**

List all applicable well permits (i.e. County, State, Variance, Injection, etc.)

**3. Well Use (check well use):**

**Water Supply Well:**

- Agricultural  Municipal/Public
- Geothermal (Heating/Cooling Supply)  Residential Water Supply (single)
- Industrial/Commercial  Residential Water Supply (shared)
- Irrigation

**Non-Water Supply Well:**

- Monitoring  LFG Migration Monitoring  Recovery

**Injection Well:**

- Aquifer Recharge  Groundwater Remediation
- Aquifer Storage and Recovery  Salinity Barrier
- Aquifer Test  Stormwater Drainage
- Experimental Technology  Subsidence Control
- Geothermal (Closed Loop)  Tracer
- Geothermal (Heating/Cooling Return)  Other (explain under #21 Remarks)

4. Date Well(s) Completed: 9/29/14 Well ID# MP-2

**5a. Well Location:**

Franklin Co. Landfill

35-01

Facility/Owner Name

Facility ID# (if applicable)

10 Landfill Road

Physical Address, City, and Zip

Franklinton 27525

007591

County

Parcel Identification No. (PIN)

**5b. Latitude and Longitude in degrees/minutes/seconds or decimal degrees:**

(if well field, one lat/long is sufficient)

36.054711 N 78.378892 W

6. Is (are) the well(s):  Permanent or  Temporary

7. Is this a repair to an existing well:  Yes or  No

If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. Number of wells constructed: 1

For multiple injection or non-water supply wells ONLY with the same construction, you can submit one form.

9. Total well depth below land surface: 29 (ft.)  
For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: Dry but at 32' bgs (ft.)  
If water level is above casing, use "+"

11. Borehole diameter: 2.5 (in.)

12. Well construction method: direct push  
(i.e. auger, rotary, cable, direct push, etc.)

**FOR WATER SUPPLY WELLS ONLY:**

13a. Yield (gpm) \_\_\_\_\_ Method of test: \_\_\_\_\_

13b. Disinfection type: \_\_\_\_\_ Amount: \_\_\_\_\_

For Internal Use ONLY:

**14. WATER ZONES**

FROM	TO	DESCRIPTION
32 ft.	ft.	
ft.	ft.	

**15. OUTER CASING (for multi-cased wells) OR LINER (if applicable)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
ft.	ft.	in.		

**16. INNER CASING OR TUBING (geothermal closed-loop)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
ft.	ft.	in.		
ft.	ft.	in.		

**17. SCREEN**

FROM	TO	DIAMETER	SLOT SIZE	THICKNESS	MATERIAL
3.5 ft.	29 ft.	1 in.	0.01"	sch40	PVC
ft.	ft.	in.			

**18. GROUT**

FROM	TO	MATERIAL	EMPLACEMENT METHOD & AMOUNT
0 ft.	2.5 ft.	Concrete	Mix & pour 400 lbs
2.5 ft.	3.0 ft.	Bent. Chips	Pour 7 lbs than hydrated
ft.	ft.		

**19. SAND/GRAVEL PACK (if applicable)**

FROM	TO	MATERIAL	EMPLACEMENT METHOD
3.0 ft.	32 ft.	#3 Filter Sand	Gravity Pour
ft.	ft.		

**20. DRILLING LOG (attach additional sheets if necessary)**

FROM	TO	DESCRIPTION (color, hardness, soil/rock type, grain size, etc.)
0 ft.	1 ft.	TOP SOIL; Dark Brown, vegetation
1 ft.	18 ft.	SILTY SAND; Pinkish white, mottled, coarse
18 ft.	32 ft.	SILTY SAND; White, mottled, coarse, dense
ft.	ft.	
ft.	ft.	
ft.	ft.	No rock refusal
ft.	ft.	

**21. REMARKS**

LFG Migration Monitoring Well.  
Locking steel above ground case & pad installed.

**22. Certification:**

  
Signature of Certified Well Contractor 10/14/14  
Date

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

**23. Site diagram or additional well details:**

You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

**SUBMITTAL INSTRUCTIONS**

24a. **For All Wells:** Submit this form within 30 days of completion of well construction to the following:

Division of Water Resources, Information Processing Unit,  
1617 Mail Service Center, Raleigh, NC 27699-1617

24b. **For Injection Wells ONLY:** In addition to sending the form to the address in 24a above, also submit a copy of this form within 30 days of completion of well construction to the following:

Division of Water Resources, Underground Injection Control Program,  
1636 Mail Service Center, Raleigh, NC 27699-1636

**24c. For Water Supply & Injection Wells:**

Also submit one copy of this form within 30 days of completion of well construction to the county health department of the county where constructed.



**WELL CONSTRUCTION RECORD**

This form can be used for single or multiple wells

**1. Well Contractor Information:**

Steve Thompson

Well Contractor Name

3579-A

NC Well Contractor Certification Number

Akers Environmental

Company Name

**2. Well Construction Permit #:**

List all applicable well permits (i.e. County, State, Variance, Injection, etc.)

**3. Well Use (check well use):**

**Water Supply Well:**

- Agricultural  Municipal/Public
- Geothermal (Heating/Cooling Supply)  Residential Water Supply (single)
- Industrial/Commercial  Residential Water Supply (shared)
- Irrigation

**Non-Water Supply Well:**

- Monitoring LFG Migration Monitoring  Recovery

**Injection Well:**

- Aquifer Recharge  Groundwater Remediation
- Aquifer Storage and Recovery  Salinity Barrier
- Aquifer Test  Stormwater Drainage
- Experimental Technology  Subsidence Control
- Geothermal (Closed Loop)  Tracer
- Geothermal (Heating/Cooling Return)  Other (explain under #21 Remarks)

4. Date Well(s) Completed: 9/29/14 Well ID# MP-3

**5a. Well Location:**

Franklin Co. Landfill

35-01

Facility/Owner Name

Facility ID# (if applicable)

10 Landfill Road

Physical Address, City, and Zip

Franklinton 27525

007591

County

Parcel Identification No. (PIN)

**5b. Latitude and Longitude in degrees/minutes/seconds or decimal degrees:**

(if well field, one lat/long is sufficient)

36.055804

N

78.376617

W

6. Is (are) the well(s):  Permanent or  Temporary

7. Is this a repair to an existing well:  Yes or  No

If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. Number of wells constructed: 1

For multiple injection or non-water supply wells ONLY with the same construction, you can submit one form.

9. Total well depth below land surface: 22.7 (ft.)

For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: Dry but at 24' bgs (ft.)

If water level is above casing, use "+"

11. Borehole diameter: 2.5 (in.)

12. Well construction method: direct push

(i.e. auger, rotary, cable, direct push, etc.)

**FOR WATER SUPPLY WELLS ONLY:**

13a. Yield (gpm) \_\_\_\_\_ Method of test: \_\_\_\_\_

13b. Disinfection type: \_\_\_\_\_ Amount: \_\_\_\_\_

For Internal Use ONLY:

14. WATER ZONES					
FROM	TO	DESCRIPTION			
24 ft.	ft.				
ft.	ft.				
15. OUTER CASING (for multi-cased wells) OR LINER (if applicable)					
FROM	TO	DIAMETER	THICKNESS	MATERIAL	
ft.	ft.	in.			
ft.	ft.	in.			
16. INNER CASING OR TUBING (geothermal closed-loop)					
FROM	TO	DIAMETER	THICKNESS	MATERIAL	
ft.	ft.	in.			
ft.	ft.	in.			
17. SCREEN					
FROM	TO	DIAMETER	SLOT SIZE	THICKNESS	MATERIAL
3.5 ft.	22.7 ft.	1 in.	0.01"	sch40	PVC
ft.	ft.	in.			
18. GROUT					
FROM	TO	MATERIAL		EMPLACEMENT METHOD & AMOUNT	
0 ft.	2.5 ft.	Concrete		Mix & pour 400 lbs	
2.5 ft.	3.0 ft.	Bent. Chips		Pour 7 lbs than hydrated	
24 ft.	31 ft.	Bent. Chips		Tremied 17 pounds	
19. SAND/GRAVEL PACK (if applicable)					
FROM	TO	MATERIAL		EMPLACEMENT METHOD	
3.0 ft.	24 ft.	#3 Filter Sand		Gravity Pour	
ft.	ft.				
20. DRILLING LOG (attach additional sheets if necessary)					
FROM	TO	DESCRIPTION (color, hardness, soil/rock type, grain size, etc.)			
0 ft.	1 ft.	TOP SOIL; Brown, vegetation			
1 ft.	10 ft.	SILTY SAND; Pinkish white, mottled, coarse			
10 ft.	16 ft.	SILTY SAND; White, coarse			
16 ft.	31 ft.	SILTY SAND; Pinkish white, mottled, coarse			
ft.	ft.	No Rock encountered			
ft.	ft.				
ft.	ft.				
21. REMARKS					
LFG Migration Monitoring Well.					
Locking steel above ground case & pad installed.					

**22. Certification:**



Signature of Certified Well Contractor

10/14/14  
Date

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

**23. Site diagram or additional well details:**

You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

**SUBMITTAL INSTRUCTIONS**

24a. **For All Wells:** Submit this form within 30 days of completion of well construction to the following:


Division of Water Resources, Information Processing Unit,  
1617 Mail Service Center, Raleigh, NC 27699-1617

24b. **For Injection Wells ONLY:** In addition to sending the form to the address in 24a above, also submit a copy of this form within 30 days of completion of well construction to the following:

Division of Water Resources, Underground Injection Control Program,  
1636 Mail Service Center, Raleigh, NC 27699-1636

**24c. For Water Supply & Injection Wells:**

Also submit one copy of this form within 30 days of completion of well construction to the county health department of the county where constructed.



GRAPHIC SCALE  
 1 INCH = 20 FT  
 1 inch = 20 ft

LEGEND

- FRANKLIN OUTWASH PROPERTY LINE
- CLOSED MSWLF ESTIMATED EXTENT OF WASTE
- FEDERAL STREAM PER USGS MAPS
- NONFEDERAL STREAM
- WETLANDS FROM GIS
- STRUCTURE MONITORED FOR LFD
- WATER MONITORING WELL
- LFD MONITORING PROBE (NOT SURVEYED LOCATION)

**Engineering Company, P.A.**

**Municipal Services**

100 BOX 30, DANIEL, N.C. 27834  
 TEL: 703-777-2331 FAX: 703-777-2332  
 WWW.MUNISERV.COM

**CLOSED UNLINED MSWLF  
 FRANKLIN COUNTY  
 FRANKLINTON  
 NORTH CAROLINA**

ATND: BLC  
 SCALE: HS

Landfill Gas Monitoring Location Details

LED Number	Depth	Type	Vertical Displacement	Land Inward From Edge of LFD (ft)	Depth to Gas (ft)	Predefined Estimated Location
MP-1	10	Probe	0	0	10	Structure
MP-2	10	Probe	0	0	10	Structure
MP-3	10	Probe	0	0	10	Structure
MP-4	10	Probe	0	0	10	Structure
MP-5	10	Probe	0	0	10	Structure
MP-6	10	Probe	0	0	10	Structure

NOTE:  
 AERIAL PHOTOGRAPHY WAS TAKEN FROM MCONEMAP AND IS DATED 2013

**FIGURE 1**

DATE	BY	DESCRIPTION

SCALE: 1/4" = 20' HORIZ SCALE  
 DATE: 10/14/14  
 DRAWN BY: J. PFDL  
 CHECKED BY: J. PFDL  
 PROJECT NUMBER: C14105.0  
 SHEET NO. 1 OF 1  
 FIGURE: 1 OF 1

MP-4

**WELL CONSTRUCTION RECORD**

This form can be used for single or multiple wells

**1. Well Contractor Information:**

Steve Thompson

Well Contractor Name

3579-A

NC Well Contractor Certification Number

Akers Environmental

Company Name

**2. Well Construction Permit #:**

List all applicable well permits (i.e. County, State, Variance, Injection, etc.)

**3. Well Use (check well use):**

**Water Supply Well:**

- Agricultural  Municipal/Public
- Geothermal (Heating/Cooling Supply)  Residential Water Supply (single)
- Industrial/Commercial  Residential Water Supply (shared)
- Irrigation

**Non-Water Supply Well:**

- Monitoring LFG Migration Monitoring  Recovery

**Injection Well:**

- Aquifer Recharge  Groundwater Remediation
- Aquifer Storage and Recovery  Salinity Barrier
- Aquifer Test  Stormwater Drainage
- Experimental Technology  Subsidence Control
- Geothermal (Closed Loop)  Tracer
- Geothermal (Heating/Cooling Return)  Other (explain under #21 Remarks)

4. Date Well(s) Completed: 9/29/14 Well ID# MP-4

**5a. Well Location:**

Franklin Co. Landfill

35-01

Facility/Owner Name

Facility ID# (if applicable)

10 Landfill Road

Physical Address, City, and Zip

Franklinton 27525

007591

County

Parcel Identification No. (PIN)

**5b. Latitude and Longitude in degrees/minutes/seconds or decimal degrees:**

(if well field, one lat/long is sufficient)

36.056124 N 78.375640 W

6. Is (are) the well(s):  Permanent or  Temporary

7. Is this a repair to an existing well:  Yes or  No

If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. Number of wells constructed: 1

For multiple injection or non-water supply wells ONLY with the same construction, you can submit one form.

9. Total well depth below land surface: 25.85 (ft.)

For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: Dry (ft.)

If water level is above casing, use "+"

11. Borehole diameter: 2.5 (in.)

12. Well construction method: direct push  
(i.e. auger, rotary, cable, direct push, etc.)

**FOR WATER SUPPLY WELLS ONLY:**

13a. Yield (gpm) \_\_\_\_\_ Method of test: \_\_\_\_\_

13b. Disinfection type: \_\_\_\_\_ Amount: \_\_\_\_\_

For Internal Use ONLY:

14. WATER ZONES					
FROM	TO	DESCRIPTION			
ft.	ft.	Dry. Refused on rock before water			
ft.	ft.				
15. OUTER CASING (for multi-cased wells) OR LINER (if applicable)					
FROM	TO	DIAMETER	THICKNESS	MATERIAL	
ft.	ft.	in.			
ft.	ft.	in.			
16. INNER CASING OR TUBING (geothermal closed-loop)					
FROM	TO	DIAMETER	THICKNESS	MATERIAL	
ft.	ft.	in.			
ft.	ft.	in.			
17. SCREEN					
FROM	TO	DIAMETER	SLOT SIZE	THICKNESS	MATERIAL
3.5 ft.	25.85 ft.	1 in.	0.01"	sch40	PVC
ft.	ft.	in.			
18. GROUT					
FROM	TO	MATERIAL	EMPLACEMENT METHOD & AMOUNT		
0 ft.	2.5 ft.	Concrete	Mix & pour 400 lbs		
2.5 ft.	3.0 ft.	Bent. Chips	Pour 7 lbs than hydrated		
ft.	ft.				
19. SAND/GRAVEL PACK (if applicable)					
FROM	TO	MATERIAL	EMPLACEMENT METHOD		
3.0 ft.	26.5 ft.	#3 Filter Sand	Gravity Pour		
ft.	ft.				
20. DRILLING LOG (attach additional sheets if necessary)					
FROM	TO	DESCRIPTION (color, hardness, soil/rock type, grain size, etc.)			
0 ft.	1 ft.	TOP SOIL; Dark Brown, vegetation			
1 ft.	7 ft.	SANDY SILT; Reddish Brown			
7 ft.	11 ft.	SILTY SAND w/ CLAY; Pinkish white			
11 ft.	16 ft.	SILTY SAND; Pinkish white, fine/mod. grains			
16 ft.	26.5 ft.	SILTY SAND; White, fine/mod. grains			
26.5 ft.	ft.	Rock. refusal			
ft.	ft.	DRY			
21. REMARKS					
LFG Migration Monitoring Well.					
Locking steel above ground case & pad installed.					

**22. Certification:**

John S. Thompson 10/14/14  
Signature of Certified Well Contractor Date

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

**23. Site diagram or additional well details:**

You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

**SUBMITTAL INSTRUCTIONS**

24a. For All Wells: Submit this form within 30 days of completion of well construction to the following:

Division of Water Resources, Information Processing Unit,  
1617 Mail Service Center, Raleigh, NC 27699-1617

24b. For Injection Wells ONLY: In addition to sending the form to the address in 24a above, also submit a copy of this form within 30 days of completion of well construction to the following:

Division of Water Resources, Underground Injection Control Program,  
1636 Mail Service Center, Raleigh, NC 27699-1636

**24c. For Water Supply & Injection Wells:**

Also submit one copy of this form within 30 days of completion of well construction to the county health department of the county where constructed.



MP-5

**WELL CONSTRUCTION RECORD**

This form can be used for single or multiple wells

**1. Well Contractor Information:**

Steve Thompson

Well Contractor Name

3579-A

NC Well Contractor Certification Number

Akers Environmental

Company Name

**2. Well Construction Permit #:**

List all applicable well permits (i.e. County, State, Variance, Injection, etc.)

**3. Well Use (check well use):**

**Water Supply Well:**

- Agricultural  Municipal/Public
- Geothermal (Heating/Cooling Supply)  Residential Water Supply (single)
- Industrial/Commercial  Residential Water Supply (shared)
- Irrigation

**Non-Water Supply Well:**

- Monitoring LFG Migration Monitoring  Recovery

**Injection Well:**

- Aquifer Recharge  Groundwater Remediation
- Aquifer Storage and Recovery  Salinity Barrier
- Aquifer Test  Stormwater Drainage
- Experimental Technology  Subsidence Control
- Geothermal (Closed Loop)  Tracer
- Geothermal (Heating/Cooling Return)  Other (explain under #21 Remarks)

4. Date Well(s) Completed: 9/29/14 Well ID# MP-5

**5a. Well Location:**

Franklin Co. Landfill

35-01

Facility/Owner Name

Facility ID# (if applicable)

10 Landfill Road

Physical Address, City, and Zip

Franklinton 27525

007591

County

Parcel Identification No. (PIN)

**5b. Latitude and Longitude in degrees/minutes/seconds or decimal degrees:**

(if well field, one lat/long is sufficient)

36.057484 N 78.374953 W

6. Is (are) the well(s):  Permanent or  Temporary

7. Is this a repair to an existing well:  Yes or  No

If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. Number of wells constructed: 1

For multiple injection or non-water supply wells ONLY with the same construction, you can submit one form.

9. Total well depth below land surface: 28 (ft.)

For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: Dry (ft.)

If water level is above casing, use "+"

11. Borehole diameter: 2.5 (in.)

12. Well construction method: direct push

(i.e. auger, rotary, cable, direct push, etc.)

**FOR WATER SUPPLY WELLS ONLY:**

13a. Yield (gpm) \_\_\_\_\_ Method of test: \_\_\_\_\_

13b. Disinfection type: \_\_\_\_\_ Amount: \_\_\_\_\_

For Internal Use ONLY:

**14. WATER ZONES**

FROM	TO	DESCRIPTION
28.5 ft.	ft.	
ft.	ft.	

**15. OUTER CASING (for multi-cased wells) OR LINER (if applicable)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
ft.	ft.	in.		

**16. INNER CASING OR TUBING (geothermal closed-loop)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
ft.	ft.	in.		
ft.	ft.	in.		

**17. SCREEN**

FROM	TO	DIAMETER	SLOT SIZE	THICKNESS	MATERIAL
3.5 ft.	28 ft.	1 in.	0.01"	sch40	PVC
ft.	ft.	in.			

**18. GROUT**

FROM	TO	MATERIAL	EMPLACEMENT METHOD & AMOUNT
0 ft.	2.5 ft.	Concrete	Mix & pour 400 lbs
2.5 ft.	3.0 ft.	Bent. Chips	Pour 7 lbs than hydrated
ft.	ft.		

**19. SAND/GRAVEL PACK (if applicable)**

FROM	TO	MATERIAL	EMPLACEMENT METHOD
3.0 ft.	28.5 ft.	#3 Filter Sand	Gravity Pour
ft.	ft.		

**20. DRILLING LOG (attach additional sheets if necessary)**

FROM	TO	DESCRIPTION (color, hardness, soil/rock type, grain size, etc.)
0 ft.	1 ft.	TOP SOIL; Dark Brown, vegetation
1 ft.	28.5 ft.	SILTY SAND; White, mottled, coarse grains
ft.	ft.	
ft.	ft.	
ft.	ft.	
ft.	ft.	No rock refusal
ft.	ft.	

**21. REMARKS**

LFG Migration Monitoring Well.  
Locking steel above ground case & pad installed.

**22. Certification:**

Signature of Certified Well Contractor [Signature] Date 10/14/14

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

**23. Site diagram or additional well details:**

You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

**SUBMITTAL INSTRUCTIONS**

24a. For All Wells: Submit this form within 30 days of completion of well construction to the following:

Division of Water Resources, Information Processing Unit,  
1617 Mail Service Center, Raleigh, NC 27699-1617

24b. For Injection Wells ONLY: In addition to sending the form to the address in 24a above, also submit a copy of this form within 30 days of completion of well construction to the following:

Division of Water Resources, Underground Injection Control Program,  
1636 Mail Service Center, Raleigh, NC 27699-1636

**24c. For Water Supply & Injection Wells:**

Also submit one copy of this form within 30 days of completion of well construction to the county health department of the county where constructed.



MP-6

**WELL CONSTRUCTION RECORD**

This form can be used for single or multiple wells

**1. Well Contractor Information:**

Steve Thompson

Well Contractor Name

3579-A

NC Well Contractor Certification Number

Akers Environmental

Company Name

**2. Well Construction Permit #:**

List all applicable well permits (i.e. County, State, Variance, Injection, etc.)

**3. Well Use (check well use):**

**Water Supply Well:**

- Agricultural  Municipal/Public
- Geothermal (Heating/Cooling Supply)  Residential Water Supply (single)
- Industrial/Commercial  Residential Water Supply (shared)
- Irrigation

**Non-Water Supply Well:**

- Monitoring LFG Migration Monitoring  Recovery

**Injection Well:**

- Aquifer Recharge  Groundwater Remediation
- Aquifer Storage and Recovery  Salinity Barrier
- Aquifer Test  Stormwater Drainage
- Experimental Technology  Subsidence Control
- Geothermal (Closed Loop)  Tracer
- Geothermal (Heating/Cooling Return)  Other (explain under #21 Remarks)

4. Date Well(s) Completed: 9/29/14 Well ID# MP-6

**5a. Well Location:**

Franklin Co. Landfill

35-01

Facility/Owner Name

Facility ID# (if applicable)

10 Landfill Road

Physical Address, City, and Zip

Franklinton 27525

007591

County

Parcel Identification No. (PIN)

**5b. Latitude and Longitude in degrees/minutes/seconds or decimal degrees:**  
(if well field, one lat/long is sufficient)

36.059014 N 78.375110 W

6. Is (are) the well(s):  Permanent or  Temporary

7. Is this a repair to an existing well:  Yes or  No  
If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. Number of wells constructed: 1  
For multiple injection or non-water supply wells ONLY with the same construction, you can submit one form.

9. Total well depth below land surface: 7.40 (ft.)  
For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: Dry but 8' bgs (ft.)  
If water level is above casing, use "+"

11. Borehole diameter: 2.5 (in.)

12. Well construction method: direct push  
(i.e. auger, rotary, cable, direct push, etc.)

**FOR WATER SUPPLY WELLS ONLY:**

13a. Yield (gpm) \_\_\_\_\_ Method of test: \_\_\_\_\_

13b. Disinfection type: \_\_\_\_\_ Amount: \_\_\_\_\_

For Internal Use ONLY:

**14. WATER ZONES**

FROM	TO	DESCRIPTION
8 ft.		

**15. OUTER CASING (for multi-cased wells) OR LINER (if applicable)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
			in.	

**16. INNER CASING OR TUBING (geothermal closed-loop)**

FROM	TO	DIAMETER	THICKNESS	MATERIAL
			in.	
			in.	

**17. SCREEN**

FROM	TO	DIAMETER	SLOT SIZE	THICKNESS	MATERIAL
3.5 ft.	7.40 ft.	1 in.	0.01"	sch40	PVC

**18. GROUT**

FROM	TO	MATERIAL	EMPLACEMENT METHOD & AMOUNT
0 ft.	2.5 ft.	Concrete	Mix & pour 400 lbs
2.5 ft.	3.0 ft.	Bent. Chips	Pour 7 lbs than hydrated

**19. SAND/GRAVEL PACK (if applicable)**

FROM	TO	MATERIAL	EMPLACEMENT METHOD
3.0 ft.	8 ft.	#3 Filter Sand	Gravity Pour

**20. DRILLING LOG (attach additional sheets if necessary)**

FROM	TO	DESCRIPTION (color, hardness, soil/rock type, grain size, etc.)
0 ft.	1 ft.	TOP SOIL; Dark Brown, vegetation, moist
1 ft.	6 ft.	SILTY SAND; Brown, coarse grained
6 ft.	8 ft.	SILTY SAND; White, mottled, coarse grains
		No rock refusal

**21. REMARKS**

LFG Migration Monitoring Well.  
Locking steel above ground case & pad installed.

**22. Certification:**

  
Signature of Certified Well Contractor Date 10/14/14

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

**23. Site diagram or additional well details:**

You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

**SUBMITTAL INSTRUCTIONS**

**24a. For All Wells:** Submit this form within 30 days of completion of well construction to the following:


Division of Water Resources, Information Processing Unit,  
1617 Mail Service Center, Raleigh, NC 27699-1617

**24b. For Injection Wells ONLY:** In addition to sending the form to the address in 24a above, also submit a copy of this form within 30 days of completion of well construction to the following:

Division of Water Resources, Underground Injection Control Program,  
1636 Mail Service Center, Raleigh, NC 27699-1636

**24c. For Water Supply & Injection Wells:**

Also submit one copy of this form within 30 days of completion of well construction to the county health department of the county where constructed.



GRAPHIC SCALE  
1 IN FEET  
1 Inch = 800 Ft.

LEGEND

- FRANKLIN OUTMOST PROPERTY LINE
- CLOSED MSLWF ESTIMATED EXTENT OF WASTE
- FEDERAL STREAM FOR USGS MAPS
- INTERMITTENT STREAM
- WETLANDS FROM OS
- STRUCTURE MONITORED FOR LFG
- WATER MONITORING WELL
- MP-2 LFG MONITORING PROBE (NOT SURVEYED LOCATION)

**Engineering Company, P.A.**

**Municipal Services**

REGISTERED PROFESSIONAL ENGINEER  
STATE OF NORTH CAROLINA, LICENSE NO. 10177  
REGISTERED PROFESSIONAL ENGINEER  
STATE OF NORTH CAROLINA, LICENSE NO. 10177

CLOSED UNLINED MSLWF  
FRANKLIN COUNTY  
FRANKLINTON  
NORTH CAROLINA

Landfill Gas Monitoring Location Details

LFG Monitoring Location ID	Phase	Type	Horizontal Size	Estimated Depth to LFG (ft.)	Depth to Groundwater (ft.)	Proximate Estimated Structure
MP-2	Phase 1	Probe	10' x 10'	10'	10'	None
MP-3	Phase 1	Probe	10' x 10'	10'	10'	None
MP-4	Phase 1	Probe	10' x 10'	10'	10'	None
MP-5	Phase 1	Probe	10' x 10'	10'	10'	None
MP-6	Phase 1	Probe	10' x 10'	10'	10'	None
MP-7	Phase 1	Probe	10' x 10'	10'	10'	None

NOTE:  
AERIAL PHOTOGRAPHY WAS TAKEN FROM NCONEMAP AND IS DATED 2013

**FIGURE 1**

LANDFILL GAS MONITORING LOCATIONS

DATE	BY	CHKD BY

SCALE: SEE DRAWING SCALE  
DATE: 10/21/14  
DRAWN BY: J. PFDL  
CHKD BY: J. PFDL  
PROJECT NUMBER: G14105.0  
SHEET NO. 1 OF 1

MP-7

WELL CONSTRUCTION RECORD

This form can be used for single or multiple wells

For Internal Use ONLY:

1. Well Contractor Information:

Steve Thompson

Well Contractor Name

3579-A

NC Well Contractor Certification Number

Akers Environmental

Company Name

2. Well Construction Permit #:

List all applicable well permits (i.e. County, State, Variance, Injection, etc.)

3. Well Use (check well use):

Water Supply Well:

- Agricultural, Geothermal, Industrial/Commercial, Irrigation, Municipal/Public, Residential Water Supply (single/shared)

Non-Water Supply Well:

- Monitoring, LFG Migration Monitoring, Recovery

Injection Well:

- Aquifer Recharge, Storage and Recovery, Test, Experimental Technology, Geothermal (Closed Loop/Heating/Cooling Return), Groundwater Remediation, Salinity Barrier, Stormwater Drainage, Subsidence Control, Tracer, Other

4. Date Well(s) Completed: 9/29/14 Well ID# MP-7

5a. Well Location:

Franklin Co. Landfill

35-01

Facility/Owner Name

Facility ID# (if applicable)

10 Landfill Road

Physical Address, City, and Zip

Franklinton 27525

007591

County

Parcel Identification No. (PIN)

5b. Latitude and Longitude in degrees/minutes/seconds or decimal degrees:

(if well field, one lat/long is sufficient)

36.060723 N 78.375032 W

6. Is (are) the well(s): Permanent or Temporary

7. Is this a repair to an existing well: Yes or No

If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. Number of wells constructed: 1

For multiple injection or non-water supply wells ONLY with the same construction, you can submit one form.

9. Total well depth below land surface: 7.6 (ft.)

For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: Dry but 8' bgs (ft.)

If water level is above casing, use "+"

11. Borehole diameter: 2.5 (in.)

12. Well construction method: direct push

(i.e. auger, rotary, cable, direct push, etc.)

FOR WATER SUPPLY WELLS ONLY:

13a. Yield (gpm) Method of test:

13b. Disinfection type: Amount:

14. WATER ZONES table with columns FROM, TO, DESCRIPTION

15. OUTER CASING (for multi-cased wells) OR LINER (if applicable) table with columns FROM, TO, DIAMETER, THICKNESS, MATERIAL

16. INNER CASING OR TUBING (geothermal closed-loop) table with columns FROM, TO, DIAMETER, THICKNESS, MATERIAL

17. SCREEN table with columns FROM, TO, DIAMETER, SLOT SIZE, THICKNESS, MATERIAL

18. GROUT table with columns FROM, TO, MATERIAL, EMPLACEMENT METHOD & AMOUNT

19. SAND/GRAVEL PACK (if applicable) table with columns FROM, TO, MATERIAL, EMPLACEMENT METHOD

20. DRILLING LOG (attach additional sheets if necessary) table with columns FROM, TO, DESCRIPTION

21. REMARKS: LFG Migration Monitoring Well. Locking steel above ground case & pad installed.

22. Certification:

Signature of Certified Well Contractor: John S. Thompson Date: 10/14/14

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

23. Site diagram or additional well details:

You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

SUBMITTAL INSTRUCTIONS

24a. For All Wells: Submit this form within 30 days of completion of well construction to the following:


Division of Water Resources, Information Processing Unit, 1617 Mail Service Center, Raleigh, NC 27699-1617

24b. For Injection Wells ONLY: In addition to sending the form to the address in 24a above, also submit a copy of this form within 30 days of completion of well construction to the following:


Division of Water Resources, Underground Injection Control Program, 1636 Mail Service Center, Raleigh, NC 27699-1636

24c. For Water Supply & Injection Wells:

Also submit one copy of this form within 30 days of completion of well construction to the county health department of the county where constructed.



- LEGEND**
- FRANKLIN OUTERMOST PROPERTY LINE
  - CLOSED MSWLF ESTIMATED EXTENT OF WASTE
  - FEDERAL STREAM PER USFS MAPS
  - INTERMITTENT STREAM
  - WETLANDS FROM GIS
  - STRUCTURE MONITORED FOR LFG
  - WATER MONITORING WELL
  - MP-2 LFG MONITORING POINT (NOT SURVEYED LOCATION)



Landfill Gas Monitoring Location Details

LFG Monitoring Location ID	Name	Type	Monitoring Date	Event Interval	Depth to LFG	Depth to Groundwater	Permeability Coefficient
MP-1	Structure	Structure	1/1/13	1	1.0	1.0	0.0001
MP-2	Structure	Structure	1/1/13	1	1.0	1.0	0.0001
MP-3	Structure	Structure	1/1/13	1	1.0	1.0	0.0001
MP-4	Structure	Structure	1/1/13	1	1.0	1.0	0.0001
MP-5	Structure	Structure	1/1/13	1	1.0	1.0	0.0001
MP-6	Structure	Structure	1/1/13	1	1.0	1.0	0.0001
MP-7	Structure	Structure	1/1/13	1	1.0	1.0	0.0001

NOTE:  
 AERIAL PHOTOGRAPHY WAS TAKEN FROM NCGEMAP AND IS DATED 2013

**FIGURE 1**