

4. During construction, the ash fill shall be graded (max. 5%) and a smooth surface maintained as to provide for sheet flow runoff and to prevent dusting.
5. Run-off from all disturbed areas shall be controlled and contained by the erosion control measures as shown in this set of plans.
6. All areas exterior slopes shall be covered with 12" compacted earth. Other surface areas shall be covered with 6" minimum earth.

