

Red House Trade STOP AM-4
15

Marketing & Transportation
Engineering Department



**Marathon
Oil Company**

539 South Main Street
Findlay, OH 45840-3295
Telephone 419/422-2121
Fax 419/421-2509

May 7, 1996

DEHNR/DEM/Groundwater Section/UST Unit
Post Office Box 29578
Raleigh, North Carolina 27626-0578

RECEIVED
N.C. Dept. of EHN

MAY 13 1996

Winston-Salem
Regional Office

RE: UST Installation
SPEEDWAY #8490
1342 Trollingwood Road
Mebane, North Carolina

To Whom It May Concern:

Please find enclosed a Notice of Intent to Install Underground Storage Tanks, check #14534 for \$1575.00 for the operating fees, and one (1) piping plan for the proposed work to be completed at the referenced location. Please accept this letter as the 30 day notification.

The proposed scope of work consists of installing three (3) 20,000 gallon, three (3) 12,000 gallon and one (1) 8,000 split compartment singlewall steel underground storage tanks. The piping will consist of 3" fiberglass on the diesel lines and Environ Geoflex on the gasoline lines. The lines will be monitored by electronic line leak detection. The tanks will be equipped with submersible pump containment sumps, spill containment manholes, and overfill protection.

Please review the application and drawings and advise if you have any questions. We anticipate construction to commence on June 3, 1996. If you need additional information or have any questions, please call me at 419/421-2756.

Sincerely,

Greg B. Amburgey
Engineer

GBA/pfk
k:\proj\amburgey\tanks
Enclosures

cc: Rick Abt - Interplan
Mr. Waddell Waters, P.E. - NCDEHNR
585 Waughtown St.
Winston-Salem, NC 27107