ENVIRO-PRO
PROFESSIONAL CORPORATION

Copy

November 30, 2012

Mr. Rick Caudle
G&B Energy
667 North Bridge Street
Elkin, North Carolina 28621

RE: Former Bulk Fuel Facility
208 Poplar Grove Road
Boone, North Carolina
EP Project No. EP-1468

Dear Mr. Caudle:

In accordance with our Proposal dated July 18, 2012, Enviro-Pro, P.C. (EP) is pleased to submit the attached Site Assessment Report.

Please contact me at 803-547-4955 if you have any questions or concerns regarding this Report or if we may be of any further service. We have appreciated the opportunity to provide our environmental services to you on this project.

Sincerely,
ENVIRO-PRO, P.C.

Thomas H. Bolyard

Thomas H. Bolyard, P.G.
Senior Hydrogeologist

SITE ASSESSMENT REPORT

Former Bulk Fuel Storage Facility
208 Poplar Grove Road
Boone, North Carolina

Prepared For:

Mr. Rick Caudle
G&B Energy
667 North Bridge Street
Elkin, North Carolina 28621

Consultant:

Enviro-Pro, P.C.
2646 Farmlake Lane
Fort Mill, South Carolina 29708

Project No. EP-1468

November 30, 2012

NORTH CAROLINA LICENSED GEOLOGIST THOMAS H. BOLYARD

1.0 BACKGROUND INFORMATION

The subject site is a former bulk fuel storage facility located at 208 Poplar Grove Road in Boone, North Carolina.

Enviro-Pro, P.C. (EP) has completed this soil/groundwater site assessment in accordance with a request from G&B Energy as part of a leasing deal.

2.0 FIELD ASSESSMENT ACTIVITIES

2.1 Soil Assessment

On September 24, 2012, EP Senior Hydrogeologist Tom Bolyard, P.G. supervised soil sampling activities at the subject site. Probing services were provided by Environmental Drilling & Probing Services, LLC (EDPS) from Charlotte, North Carolina. A track-mounted Geoprobe 7728DT rig was mobilized to the site to collect the soil/groundwater samples.

During advancement of the soil borings (SS-1 through SS-19), EP personnel collected continuous macrocore soil samples at 5-foot intervals from the ground surface to the termination depth of 5-foot to 9-feet in all soil borings (Figure 1). No petroleum staining or odors were observed in any of the soil borings. Soil samples were submitted for laboratory analysis from SS-1 through SS-6 at a depth of approximately 4 feet below ground surface (bgs) and from SS-7, SS-8, SS-9, SS-10, SS-11, SS-13, SS-16, SS-17-, SS-18, and SS-19 at a depth of 5 feet bgs. Soil sample SS-12 was collected at a depth of 3 feet bgs. Soil samples SS-14 and SS-15 were collected a depth of 9 feet bgs. The soil samples were analyzed for volatile organic compounds (VOCs) via Method 8260B by Shealy Environmental Services in West Columbia, South Carolina, a North Carolina certified laboratory.

2.2 Groundwater Assessment

On September 24, 2012 EP personnel also supervised the installation of eight temporary 1-inch Schedule 40 PVC piezometers (GW-1 through GW-8) at the approximate locations indicated on Figure 1. GW-7 was installed to a depth of 3 feet bgs; GW-2, GW-3, and GW-4 were installed to a depth of 4 feet bgs; GW-1 and GW-8 were installed to a depth of 5 feet bgs; GW-6 was installed to a depth of 6 feet bgs; GW-5 was installed to a depth of 7 feet bgs. All piezometers were constructed using 5 feet of 0.010-inch

slot (1") PVC screen and a washed #2 sand pack to 2 feet above the screen top. After completion the monitor well was allowed to recharge for 30 minutes and was subsequently sampled via a new disposable polyethylene bailer. After sample collection, the PVC pipe and screen were removed and the borehole was backfilled with grout to ground surface. The groundwater sample was shipped to Shealy's facility for analysis of volatile organic compounds (VOCs) via Method 6200B.

3.0 LABORATORY ANALYTICAL RESULTS

Several petroleum compounds were detected in the groundwater samples collected. Benzene was detected in groundwater samples GW-3, GW-5, GW-7, and GW-8 at a concentration above its 2L Standard. Ethylbenzene, MTBE, and Xylenes were also detected in GW-5 at concentrations above their 2L Standards. Naphthalene was detected in groundwater samples GW-2, GW-3, GW-5, GW-6, GW-7, and GW-8 at a concentration above its 2L Standard. The groundwater sampling results are summarized in Table 1.

The Executive Summary sheet from Shealy's Report of Analysis is attached as the Appendix to this report. Several petroleum compounds were detected in the soil samples collected. Benzene was detected in soil samples SS-2, SS-3, SS-9, SS-11, SS-12, SS-13, and, SS-19 at concentrations above its Maximum Soil Contamination Concentration (MSCC). Ethylbenzene was detected at a concentration above its MSCC in soil samples SS-4 and SS-8. Xylenes were also detected at a concentration above its MSCC in soil samples SS-4, SS-8, SS-13, SS-17, SS-18, and SS-19. The soil sampling results are summarized in Table 2.

4.0 CONCLUSIONS AND RECOMMENDATIONS

The analysis of the soil and groundwater samples resulted in the detection of several VOC compounds at levels exceeding the state standards.

Based on the results of these soil and groundwater site assessment activities, EP recommends excavating and removing as much of the contaminated soil as possible. This will allow the petroleum constituents in the groundwater to decrease more rapidly over time. EP has identified ten areas of soil contamination which would require excavation. These areas are indicated on the attached Site Map (Figure 1). An estimated total of 900 cubic yards (or 1,300 tons) of petroleum impacted soil would need to be removed from the site and taken to the EVO Soil Disposal facility located in Winston-Salem, North Carolina.

Due to the uncertainty of the exact extent of the soil contamination in some of the areas sampled, it is recommended that 1,500 tons (worst case) volume of soil to be removed. Based on the removal of 1,500 tons of contamination soil, the following cost estimate would apply:

- Excavation, loading, and transportation = $44,000.00
- Laboratory Analysis of soil samples from 10 areas of excavation = $5,500.00
- Disposal @ EVO facility = $31,000.00
- Backfilling with 6 inches of gravel on surface = $27,000.00
- Geologist Field Supervision = $3,000.00
- Summary Report = $1,500.00

TOTAL = $112,000.00

Although groundwater contamination exists at this site, the site would likely be classified as low risk according to the North Carolina DENR and no groundwater remediation would be required. In order to verify this, EP personnel will conduct a water supply well survey within 1,000 feet of the site. Once the contaminated soil is removed, the groundwater quality of the site should begin improving over time. In order to confirm that natural attenuation is occurring, groundwater monitor wells should be installed and sampled periodically. Based on the installation of five shallow groundwater monitor wells, the following cost estimate would apply:

- Well Installation = $3,750.00
- Semi-Annual Groundwater Sampling/Reporting = $2,200.00 per sampling event

Semi-Annual sampling should be conducted for the first two years. The sampling frequency could then be reduced to annually thereafter.

Please contact me to discuss the results of this report and the recommendations for further action.

TABLE 1

Groundwater Sampling Results for the Former Bulk Fuel Facility
208 Poplar Grove Road
Boone, North Carolina
November 28, 2012

Analytical Method →			6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B
Contaminant of Concern →			Benzene	IPE	Ethylbenzene	MTBE	Toluene	o-Xylenes	M+P-Xylenes	1,3,5-Trimethylbenzene	1,2,4-Trimethylbenzene	n-Propylbenzene	Naphthalene	Isopropylbenzene	Chloroform	n-Butylbenzene
Well ID	Sample ID	Date Collected														
GW-1	GW-1	9/24/12	BDL	BDL	BDL	BDL	6.0	BDL	1.1	BDL	BDL	BDL	BDL	BDL	BDL	BDL
GW-2	GW-2	9/24/12	BDL	BDL	BDL	BDL	BDL	BDL	7.9	11	43	8.6	**65**	7.3	BDL	6.4
GW-3	GW-3	9/24/12	**74**	BDL	46	BDL	BDL	BDL	53	11	**460**	69	**73**	22	BDL	25
GW-4	GW-4	9/24/12	BDL	BDL	1.6	BDL	0.54	BDL	3.9	1.2	2.0	0.72	0.85	BDL	BDL	0.55
GW-5	GW-5	9/24/12	**170**	14	**1,600**	**25**	27	59	**2,000**	62	**3,200**	120	**1,200**	60	3.7	17
GW-6	GW-6	9/24/12	0.60	BDL	1.1	0.97	BDL	BDL	2.9	1.1	5.9	0.79	**14**	BDL	BDL	0.99
GW-7	GW-7	9/24/12	**9.0**	BDL	21	0.58	BDL	1.0	21	1.7	34	7.6	**21**	4.7	BDL	1.8
GW-8	GW-8	9/24/12	**1.9**	BDL	10	BDL	1.5	BDL	17	8.8	19	4.8	**11**	1.4	BDL	2.8
2L Standard (ug/l) →			1	70	600	20	600	500	500	400	400	70	6	70	70	70
GCL (ug/l) →			5,000	70,000	84,500	20,000	260,000	85,500	85,500	25,000	28,500	30,000	6,000	25,000	70,000	6,900

NOTES: * All results presented in micrograms per liter (ug/L)
* Shaded areas represent results above their 2L Standards.
* BDL = below detection limit
* NE = None Established

TABLE 1 (continued)
Groundwater Sampling Results for the Former Bulk Fuel Facility
208 Poplar Grove Road
Boone, North Carolina
November 28, 2012

Analytical Method →			6200B	6200B	6200B	6200B	6200B	6200B	6200B	6200B
Contaminant of Concern →			sec-butylbenzene	tert-butylbenzene	2-Chlorotoluene	p-isopropyltoluene	1,1,2,2-Tetrachloroethane	1,2-Dichloroethane	1,2-Dichloropropane	1,1,2-Trichloroethane
Well ID	Sample ID	Date Collected								
GW-1	GW-1	9/24/12	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
GW-2	GW-2	9/24/12	8.0	5.3	1.6	**3.8**	**4.8**	BDL	BDL	BDL
GW-3	GW-3	9/24/12	13	BDL	BDL	**8.9**	BDL	BDL	BDL	BDL
GW-4	GW-4	9/24/12	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
GW-5	GW-5	9/24/12	14	**120**	43	**14**	BDL	**4.1**	**2.1**	**15**
GW-6	GW-6	9/24/12	0.87	BDL	BDL	**0.50**	BDL	BDL	BDL	BDL
GW-7	GW-7	9/24/12	2.3	BDL	BDL	**0.73**	BDL	BDL	BDL	BDL
GW-8	GW-8	9/24/12	1.5	BDL	BDL	**1.3**	BDL	BDL	BDL	BDL
2L Standard (ug/l) →			70	70	100	NE	0.7	0.4	0.6	3
GCL (ug/l) →			8,500	15,000	NE	NE	700	400	600	3,000

NOTES: * All results presented in micrograms per liter (ug/L)
* Shaded areas represent results above their 2L Standards.
* BDL = below detection limit
* NE = None Established

TABLE 2

Soil Sampling Results for the Former Bulk Fuel Facility
208 Poplar Grove Road
Boone, North Carolina
November 28, 2012

Analytical Method →			8260B	8260B	8260B	8260B	8260B	8260B	8260B	8260B	8260B	8260B
Sample ID	Contaminant of Concern → Date Collected (mo/dd/yy)	Sample Depth (ft BGS)	Acetone	Benzene	Chloroform	Ethylbenzene	Toluene	MTBE	Xylenes	Isopropylbenzene	4-Methyl-2-pentanone	Methylcyclohexane
SS-1	9/24/12	4	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
SS-2	9/24/12	4	0.55	**0.063**	0.210	0.36	0.02	BDL	3	0.9	**1.9**	**3**
SS-3	9/24/12	4	0.066	**0.039**	BDL	BDL	BDL	0.044	0.06	0.034	BDL	**0.03**
SS-4	9/24/12	4	BDL	BDL	BDL	**28**	BDL	BDL	**160**	BDL	BDL	BDL
SS-5	9/24/12	4	0.055	BDL	BDL	BDL	BDL	BDL	0.085	0.0097	BDL	**0.016**
SS-6	9/24/12	4	0.12	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	**0.069**
SS-7	9/24/12	5	0.024	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
SS-8	9/24/12	5	BDL	BDL	BDL	**6.4**	BDL	BDL	**28**	BDL	BDL	**5.1**
SS-9	9/24/12	5	0.72	**0.0068**	0.13	1.3	0.038	BDL	3.3	0.58	BDL	**1.1**
SS-10	9/24/12	5	0.022	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
SS-11	9/24/12	5	0.076	**0.2**	BDL	0.34	0.0098	BDL	0.46	0.19	BDL	**0.13**
SS-12	9/24/12	3	0.07	**0.02**	0.0081	0.21	0.018	BDL	0.23	0.1	BDL	**0.17**
SS-13	9/24/12	5	BDL	**3.3**	BDL	19	BDL	BDL	**73**	**3.3**	BDL	**7.3**
SS-14	9/24/12	9	0.074	BDL	BDL	BDL	BDL	0.011	BDL	BDL	BDL	BDL
SS-15	9/24/12	9	0.064	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL
SS-16	9/24/12	5	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	BDL	**1.1**
SS-17	9/24/12	5	BDL	BDL	BDL	17	BDL	BDL	**62**	BDL	BDL	**7.8**
SS-18	9/24/12	5	BDL	BDL	BDL	3.6	BDL	BDL	**11**	BDL	BDL	**2.2**
SS-19	9/24/12	5	2	**1.2**	BDL	15	0.94	BDL	**50**	**2.4**	**1.5**	**4**
Soil to groundwater MSCC (mg/kg)			24	0.0056	0.37	4.9	4.3	0.091	4.6	1.7	NE	NE

Notes:
* MSCC = maximum soil contamination concentration
* NE = None Established
* Results are reported in milligrams per kilogram (mg/kg)
* BDL = Below detection limit

TABLE 2 (continued)
Soil Sampling Results for the Former Bulk Fuel Facility
208 Poplar Grove Road
Boone, North Carolina
November 28, 2012

Analytical Method →			8260B	8260B	8260B	8260B	8260B
Sample ID	Contaminant of Concern → Date Collected (mm/dd/yy)	Sample Depth (ft BGS)	MEK	Cyclohexane	2-Hexanone	1,1,2-Trichloroethane	Methyl acetate
SS-1	9/24/12	4	BDL	BDL	BDL	BDL	BDL
SS-2	9/24/12	4	BDL	BDL	BDL	BDL	BDL
SS-3	9/24/12	4	BDL	BDL	BDL	BDL	BDL
SS-4	9/24/12	4	BDL	BDL	BDL	BDL	BDL
SS-5	9/24/12	4	BDL	BDL	BDL	BDL	BDL
SS-6	9/24/12	4	0.032	BDL	BDL	BDL	BDL
SS-7	9/24/12	5	BDL	BDL	BDL	BDL	BDL
SS-8	9/24/12	5	BDL	**6.6**	BDL	BDL	BDL
SS-9	9/24/12	5	BDL	**0.83**	1.1	0.49	BDL
SS-10	9/24/12	5	BDL		BDL	BDL	BDL
SS-11	9/24/12	5	0.016	**0.028**	0.52	BDL	BDL
SS-12	9/24/12	3	BDL	BDL	BDL	BDL	BDL
SS-13	9/24/12	5	BDL	BDL	BDL	BDL	BDL
SS-14	9/24/12	9	BDL	BDL	BDL	BDL	BDL
SS-15	9/24/12	9	BDL	BDL	BDL	BDL	BDL
SS-16	9/24/12	5	BDL	BDL	BDL	BDL	BDL
SS-17	9/24/12	5	BDL	BDL	BDL	BDL	BDL
SS-18	9/24/12	5	BDL	BDL	BDL	BDL	BDL
SS-19	9/24/12	5	BDL	BDL	1.3	BDL	**0.54**
Soil to groundwater MSCC (mg/kg)			16	NE	1.9	1.6	NE

Notes:
* MSCC = maximum soil contamination concentration
* Results are reported in milligrams per kilogram (mg/kg)
* BDL = Below detection limit
* NE = None Established



FIGURE 1: SITE MAP
208 Poplar Grove Road
Boone, North Carolina

DRAWN BY: THB	ENVIRO-PRO	SCALE: 1" = 20'
PROJ. MGR: THB		PROJ.NO: EP-1468
DATE 11/30/10	PROFESSIONAL CORPORATION	

APPENDIX

Executive Summary
Enviro-Pro, P.C.
Lot Number: NI26080

Sample	Sample ID	Matrix	Parameter	Method	Result	Q	Units	Page
001	GW-1	Aqueous	Toluene	SM 6200B	6.0		ug/L	9
001	GW-1	Aqueous	m+p - Xylenes	SM 6200B	1.1		ug/L	9
002	GW-2	Aqueous	n-Butylbenzene	SM 6200B	6.4		ug/L	10
002	GW-2	Aqueous	sec-Butylbenzene	SM 6200B	8.0		ug/L	10
002	GW-2	Aqueous	tert-Butylbenzene	SM 6200B	5.3		ug/L	10
002	GW-2	Aqueous	2-Chlorotoluene	SM 6200B	1.6		ug/L	10
002	GW-2	Aqueous	Isopropylbenzene (Cumene)	SM 6200B	7.3		ug/L	10
002	GW-2	Aqueous	p-Isopropyltoluene (p-Cymene)	SM 6200B	3.8		ug/L	10
002	GW-2	Aqueous	Naphthalene	SM 6200B	65		ug/L	10
002	GW-2	Aqueous	n-Propylbenzene	SM 6200B	8.6		ug/L	10
002	GW-2	Aqueous	1,1,2,2-Tetrachloroethane	SM 6200B	4.8		ug/L	11
002	GW-2	Aqueous	1,3,5-Trimethylbenzene (Mesitylene)	SM 6200B	11		ug/L	11
002	GW-2	Aqueous	1,2,4-Trimethylbenzene	SM 6200B	43		ug/L	11
002	GW-2	Aqueous	m+p - Xylenes	SM 6200B	7.9		ug/L	11
003	GW-3	Aqueous	Benzene	SM 6200B	74		ug/L	12
003	GW-3	Aqueous	n-Butylbenzene	SM 6200B	25		ug/L	12
003	GW-3	Aqueous	sec-Butylbenzene	SM 6200B	13		ug/L	12
003	GW-3	Aqueous	Ethylbenzene	SM 6200B	46		ug/L	12
003	GW-3	Aqueous	Isopropylbenzene (Cumene)	SM 6200B	22		ug/L	12
003	GW-3	Aqueous	p-Isopropyltoluene (p-Cymene)	SM 6200B	8.9		ug/L	12
003	GW-3	Aqueous	Naphthalene	SM 6200B	73		ug/L	12
003	GW-3	Aqueous	n-Propylbenzene	SM 6200B	69		ug/L	12
003	GW-3	Aqueous	1,3,5-Trimethylbenzene (Mesitylene)	SM 6200B	11		ug/L	13
003	GW-3	Aqueous	1,2,4-Trimethylbenzene	SM 6200B	460		ug/L	13
003	GW-3	Aqueous	m+p - Xylenes	SM 6200B	53		ug/L	13
004	GW-4	Aqueous	n-Butylbenzene	SM 6200B	0.55		ug/L	14
004	GW-4	Aqueous	Ethylbenzene	SM 6200B	1.6		ug/L	14
004	GW-4	Aqueous	Naphthalene	SM 6200B	0.85		ug/L	14
004	GW-4	Aqueous	n-Propylbenzene	SM 6200B	0.72		ug/L	14
004	GW-4	Aqueous	Toluene	SM 6200B	0.54		ug/L	15
004	GW-4	Aqueous	1,3,5-Trimethylbenzene (Mesitylene)	SM 6200B	1.2		ug/L	15
004	GW-4	Aqueous	1,2,4-Trimethylbenzene	SM 6200B	2.0		ug/L	15
004	GW-4	Aqueous	m+p - Xylenes	SM 6200B	3.9		ug/L	15
005	GW-5	Aqueous	Benzene	SM 6200B	170		ug/L	16
005	GW-5	Aqueous	n-Butylbenzene	SM 6200B	17		ug/L	16
005	GW-5	Aqueous	sec-Butylbenzene	SM 6200B	14		ug/L	16
005	GW-5	Aqueous	tert-Butylbenzene	SM 6200B	120		ug/L	16
005	GW-5	Aqueous	Chloroform	SM 6200B	3.7		ug/L	16
005	GW-5	Aqueous	2-Chlorotoluene	SM 6200B	43		ug/L	16
005	GW-5	Aqueous	1,2-Dichloroethane	SM 6200B	4.1		ug/L	16
005	GW-5	Aqueous	1,2-Dichloropropane	SM 6200B	2.1		ug/L	16
005	GW-5	Aqueous	Diisopropyl ether (IPE)	SM 6200B	14		ug/L	16
005	GW-5	Aqueous	Ethylbenzene	SM 6200B	1600		ug/L	16
005	GW-5	Aqueous	Isopropylbenzene (Cumene)	SM 6200B	60		ug/L	16
005	GW-5	Aqueous	p-Isopropyltoluene (p-Cymene)	SM 6200B	14		ug/L	16

Sample	Sample ID	Matrix	Parameter	Method	Result	Q	Units	Page
005	GW-5	Aqueous	Methyl tertiary butyl ether (MTBE)	SM 6200B	25		ug/L	16
005	GW-5	Aqueous	Naphthalene	SM 6200B	1200		ug/L	17
005	GW-5	Aqueous	n-Propylbenzene	SM 6200B	120		ug/L	17
005	GW-5	Aqueous	Toluene	SM 6200B	27		ug/L	17
005	GW-5	Aqueous	1,1,2-Trichloroethane	SM 6200B	15		ug/L	17
005	GW-5	Aqueous	1,3,5-Trimethylbenzene (Mesitylene)	SM 6200B	62		ug/L	17
005	GW-5	Aqueous	1,2,4-Trimethylbenzene	SM 6200B	3200		ug/L	17
005	GW-5	Aqueous	m+p - Xylenes	SM 6200B	2000		ug/L	17
005	GW-5	Aqueous	o - Xylenes	SM 6200B	59		ug/L	17
006	GW-6	Aqueous	Benzene	SM 6200B	0.60		ug/L	18
006	GW-6	Aqueous	n-Butylbenzene	SM 6200B	0.99		ug/L	18
006	GW-6	Aqueous	sec-Butylbenzene	SM 6200B	0.87		ug/L	18
006	GW-6	Aqueous	Ethylbenzene	SM 6200B	1.1		ug/L	18
006	GW-6	Aqueous	p-Isopropyltoluene (p-Cymene)	SM 6200B	0.50		ug/L	18
006	GW-6	Aqueous	Methyl tertiary butyl ether (MTBE)	SM 6200B	0.97		ug/L	18
006	GW-6	Aqueous	Naphthalene	SM 6200B	14		ug/L	18
006	GW-6	Aqueous	n-Propylbenzene	SM 6200B	0.79		ug/L	19
006	GW-6	Aqueous	1,3,5-Trimethylbenzene (Mesitylene)	SM 6200B	1.1		ug/L	19
006	GW-6	Aqueous	1,2,4-Trimethylbenzene	SM 6200B	5.9		ug/L	19
006	GW-6	Aqueous	m+p - Xylenes	SM 6200B	2.9		ug/L	19
007	GW-7	Aqueous	Benzene	SM 6200B	9.0		ug/L	20
007	GW-7	Aqueous	n-Butylbenzene	SM 6200B	1.8		ug/L	20
007	GW-7	Aqueous	sec-Butylbenzene	SM 6200B	2.3		ug/L	20
007	GW-7	Aqueous	Ethylbenzene	SM 6200B	21		ug/L	20
007	GW-7	Aqueous	Isopropylbenzene (Cumene)	SM 6200B	4.7		ug/L	20
007	GW-7	Aqueous	p-Isopropyltoluene (p-Cymene)	SM 6200B	0.73		ug/L	20
007	GW-7	Aqueous	Methyl tertiary butyl ether (MTBE)	SM 6200B	0.58		ug/L	20
007	GW-7	Aqueous	Naphthalene	SM 6200B	21		ug/L	20
007	GW-7	Aqueous	n-Propylbenzene	SM 6200B	7.6		ug/L	20
007	GW-7	Aqueous	1,3,5-Trimethylbenzene (Mesitylene)	SM 6200B	1.7		ug/L	21
007	GW-7	Aqueous	1,2,4-Trimethylbenzene	SM 6200B	34		ug/L	21
007	GW-7	Aqueous	m+p - Xylenes	SM 6200B	21		ug/L	21
007	GW-7	Aqueous	o - Xylenes	SM 6200B	1.0		ug/L	21
008	GW-8	Aqueous	Benzene	SM 6200B	1.9		ug/L	22
008	GW-8	Aqueous	n-Butylbenzene	SM 6200B	2.8		ug/L	22
008	GW-8	Aqueous	sec-Butylbenzene	SM 6200B	1.5		ug/L	22
008	GW-8	Aqueous	Ethylbenzene	SM 6200B	10		ug/L	22
008	GW-8	Aqueous	Isopropylbenzene (Cumene)	SM 6200B	1.4		ug/L	22
008	GW-8	Aqueous	p-Isopropyltoluene (p-Cymene)	SM 6200B	1.3		ug/L	22
008	GW-8	Aqueous	Naphthalene	SM 6200B	11		ug/L	22
008	GW-8	Aqueous	n-Propylbenzene	SM 6200B	4.8		ug/L	22
008	GW-8	Aqueous	Toluene	SM 6200B	1.5		ug/L	23
008	GW-8	Aqueous	1,3,5-Trimethylbenzene (Mesitylene)	SM 6200B	8.8		ug/L	23
008	GW-8	Aqueous	1,2,4-Trimethylbenzene	SM 6200B	19		ug/L	23
008	GW-8	Aqueous	m+p - Xylenes	SM 6200B	17		ug/L	23
010	SS-2	Solid	Acetone	8260B	550	Q	ug/kg	26
010	SS-2	Solid	Benzene	8260B	63	Q	ug/kg	26
010	SS-2	Solid	Chloroform	8260B	210	Q	ug/kg	26

Sample	Sample ID	Matrix	Parameter	Method	Result	Q	Units	Page
010	SS-2	Solid	Ethylbenzene	8260B	360	Q	ug/kg	26
010	SS-2	Solid	Isopropylbenzene	8260B	900	QE	ug/kg	26
010	SS-2	Solid	4-Methyl-2-pentanone	8260B	1900	QE	ug/kg	26
010	SS-2	Solid	Methylcyclohexane	8260B	3000	QE	ug/kg	26
010	SS-2	Solid	Toluene	8260B	20	Q	ug/kg	26
010	SS-2	Solid	Xylenes (total)	8260B	3000	QE	ug/kg	27
011	SS-3	Solid	Acetone	8260B	66		ug/kg	28
011	SS-3	Solid	Ethylbenzene	8260B	39		ug/kg	28
011	SS-3	Solid	Isopropylbenzene	8260B	34		ug/kg	28
011	SS-3	Solid	Methyl tertiary butyl ether (MTBE)	8260B	44		ug/kg	28
011	SS-3	Solid	Methylcyclohexane	8260B	30		ug/kg	28
011	SS-3	Solid	Xylenes (total)	8260B	60		ug/kg	29
012	SS-4	Solid	Ethylbenzene	8260B	28000	Q	ug/kg	30
012	SS-4	Solid	Xylenes (total)	8260B	160000	Q	ug/kg	31
013	SS-5	Solid	Acetone	8260B	55		ug/kg	32
013	SS-5	Solid	Isopropylbenzene	8260B	9.7		ug/kg	32
013	SS-5	Solid	Methylcyclohexane	8260B	16		ug/kg	32
013	SS-5	Solid	Xylenes (total)	8260B	85		ug/kg	33
014	SS-6	Solid	Acetone	8260B	120		ug/kg	34
014	SS-6	Solid	2-Butanone (MEK)	8260B	32		ug/kg	34
014	SS-6	Solid	Methylcyclohexane	8260B	69		ug/kg	34
015	SS-7	Solid	Acetone	8260B	24		ug/kg	36
016	SS-8	Solid	Cyclohexane	8260B	6600	Q	ug/kg	38
016	SS-8	Solid	Ethylbenzene	8260B	6400	Q	ug/kg	38
016	SS-8	Solid	Methylcyclohexane	8260B	5100	Q	ug/kg	38
016	SS-8	Solid	Xylenes (total)	8260B	28000	Q	ug/kg	39
017	SS-9	Solid	Acetone	8260B	720		ug/kg	40
017	SS-9	Solid	Benzene	8260B	6.8		ug/kg	40
017	SS-9	Solid	Chloroform	8260B	130		ug/kg	40
017	SS-9	Solid	Cyclohexane	8260B	830	E	ug/kg	40
017	SS-9	Solid	Ethylbenzene	8260B	1300	Q	ug/kg	40
017	SS-9	Solid	2-Hexanone	8260B	1100	E	ug/kg	40
017	SS-9	Solid	Isopropylbenzene	8260B	580	E	ug/kg	40
017	SS-9	Solid	Methylcyclohexane	8260B	1100	E	ug/kg	40
017	SS-9	Solid	Toluene	8260B	38		ug/kg	40
017	SS-9	Solid	1,1,2-Trichloroethane	8260B	490	E	ug/kg	41
017	SS-9	Solid	Xylenes (total)	8260B	3300	Q	ug/kg	41
018	SS-10	Solid	Acetone	8260B	22		ug/kg	42
019	SS-11	Solid	Acetone	8260B	76		ug/kg	44
019	SS-11	Solid	Benzene	8260B	200		ug/kg	44
019	SS-11	Solid	2-Butanone (MEK)	8260B	16		ug/kg	44
019	SS-11	Solid	Cyclohexane	8260B	28		ug/kg	44
019	SS-11	Solid	Ethylbenzene	8260B	340		ug/kg	44
019	SS-11	Solid	2-Hexanone	8260B	520	L	ug/kg	44
019	SS-11	Solid	Isopropylbenzene	8260B	190		ug/kg	44
019	SS-11	Solid	Methylcyclohexane	8260B	130		ug/kg	44
019	SS-11	Solid	Toluene	8260B	9.8		ug/kg	44
019	SS-11	Solid	Xylenes (total)	8260B	460		ug/kg	45

Sample	Sample ID	Matrix	Parameter	Method	Result	Q	Units	Page
020	SS-12	Solid	Acetone	8260B	70		ug/kg	46
020	SS-12	Solid	Benzene	8260B	20		ug/kg	46
020	SS-12	Solid	Chloroform	8260B	8.1		ug/kg	46
020	SS-12	Solid	Ethylbenzene	8260B	210		ug/kg	46
020	SS-12	Solid	Isopropylbenzene	8260B	100		ug/kg	46
020	SS-12	Solid	Methylcyclohexane	8260B	170		ug/kg	46
020	SS-12	Solid	Toluene	8260B	18		ug/kg	46
020	SS-12	Solid	Xylenes (total)	8260B	230		ug/kg	47
021	SS-13	Solid	Benzene	8260B	3300	Q	ug/kg	48
021	SS-13	Solid	Ethylbenzene	8260B	19000	Q	ug/kg	48
021	SS-13	Solid	Isopropylbenzene	8260B	3300	Q	ug/kg	48
021	SS-13	Solid	Methylcyclohexane	8260B	7300	Q	ug/kg	48
021	SS-13	Solid	Xylenes (total)	8260B	73000	Q	ug/kg	49
022	SS-14	Solid	Acetone	8260B	74		ug/kg	50
022	SS-14	Solid	Methyl tertiary butyl ether (MTBE)	8260B	11		ug/kg	50
023	SS-15	Solid	Acetone	8260B	64		ug/kg	52
024	SS-16	Solid	Methylcyclohexane	8260B	1100		ug/kg	54
025	SS-17	Solid	Ethylbenzene	8260B	16000	Q	ug/kg	56
025	SS-17	Solid	Methylcyclohexane	8260B	7800	Q	ug/kg	56
025	SS-17	Solid	Xylenes (total)	8260B	62000	Q	ug/kg	57
026	SS-18	Solid	Ethylbenzene	8260B	3600		ug/kg	58
026	SS-18	Solid	Methylcyclohexane	8260B	2200		ug/kg	58
026	SS-18	Solid	Xylenes (total)	8260B	11000		ug/kg	59
027	SS-19	Solid	Acetone	8260B	2000	Q	ug/kg	60
027	SS-19	Solid	Benzene	8260B	1200	Q	ug/kg	60
027	SS-19	Solid	Ethylbenzene	8260B	15000	Q	ug/kg	60
027	SS-19	Solid	2-Hexanone	8260B	1300	Q	ug/kg	60
027	SS-19	Solid	Isopropylbenzene	8260B	2400	Q	ug/kg	60
027	SS-19	Solid	Methyl acetate	8260B	540	Q	ug/kg	60
027	SS-19	Solid	4-Methyl-2-pentanone	8260B	1500	Q	ug/kg	60
027	SS-19	Solid	Methylcyclohexane	8260B	4000	Q	ug/kg	60
027	SS-19	Solid	Toluene	8260B	940	Q	ug/kg	60
027	SS-19	Solid	Xylenes (total)	8260B	50000	Q	ug/kg	61

(174 detections)