Clayton, Sr., P.E., Inc.
Civil & Environmental Engineering

February 27, 2009

Ms. Jaclynne Drummond
Solid Waste Section
Division of Waste Management
North Carolina Department of Environment and Natural Resources
Mail Service Center 1646
Raleigh, NC 27699-1646

RE: STATISTICAL ANALYSIS/EVALUATION: OCTOBER 08
DUNN-ERWIN MUNICIPAL SOLID WASTE LANDFILL, PERMIT 43-02
HARNETT COUNTY, NORTH CAROLINA

Dear Ms. Drummond:

On behalf of Harnett County, C.T. Clayton, Sr., PE, Inc. (CTC) is pleased to herewith submit the results of the statistical analysis for the semi-annual groundwater monitoring event of October 2008 performed at the Dunn-Erwin Municipal Solid Waste Landfill in accordance with North Carolina Solid Waste Management Rules *15A N.C.A.C. 13 B, .1633* and *.1634*. The findings and conclusions of this report will be considered by Harnett County for the assessment of the Harnett County's corrective action program for the groundwater contamination plume, downgradient of the existing landfill in accordance with North Carolina Solid Waste Management Rules *15A N.C.A.C. 13 B, .1635, .1636, and .1637*

The report is organized in sections entitled Executive Summary, Introduction, Methodology, and Results, and it has four appendices inclusive of the statistical model output.

Should you have any questions or comments, please contact me at our address shown above or by e-mail at *tyrus@ctclayton.com*.

Sincerely,

C. T. Clayton, Sr., PE, Inc.

Tyrus Clayton

cc. Jerry Blanchard - Harnett County
C. T. Clayton, Sr., P.E
C. J. poran, PE - ENSOL, Inc.

/attachments

P.O. Box 578
46 W. Washington Street
Coats, NC 27521
Phone: 910-897-7070
Fax: 910-897-6767

Offices located in Coats and New Bern, North Carolina

STATISTICAL ANALYSIS/EVALUATION
OCTOBER 2008
DUNN-ERWIN MUNICIPAL SOLID WASTE LANDFILL
PERMIT #43-02
HARNETT COUNTY, NORTH CAROLINA

Submitted to:
Solid Waste Section
Division of Waste Management
NCDENR
1646 Mail Service Center
Raleigh, NC 27699-1646

Submitted by:
C.T. Clayton, Sr., P.E., Inc.
P. O. Box 12794
New Bern, NC 28561

Submitted on behalf of:
Harnett County General Services
900 South 9th Street
Lillington, NC 27546

February 27, 2008

TABLE OF CONTENTS

EXECUTIVE SUMMARY i

I. INTRODUCTION 1

II. GROUNDWATER LEVELS 1

III. METHODOLOGY 1

IV. RESULTS 4

Set 1 Upgradient Monitoring Wells 5
Downgradient Monitoring Wells 8

Set 2 20
Upgradient Monitoring Wells 20
Downgradient Monitoring Wells 21

Set 3 22
Upgradient Surface Water Point 22
Downgradient Surface Water Points 24

TABLES

1. Groundwater Levels Within Monitoring Wells
2. Groundwater Velocity Data
3. Summary of Results of Various Statistical Analyses for Inorganics
4A. Summary of Appendices I & II Statistical Analysis Results
4B. Notification Table for Values Exceeding 2L NCGS or 13B GPS
5. Analysis of Organic Detections in Downgradient Monitoring Wells
6. Comparison of 2L NCGS, 13B GPS, SWSL, Current and Historic Detection Limits

FIGURES

1. Contaminant Plume Assessment
2. Site Layout and Monitoring Well Locations
3. Top Organic Detections in Downgradient Wells per Sampling Event

APPENDICES

APPENDIX A Data Set 1:
- Individual MW Summary Tables
- Excel Results:
  Test of Proportions
  Predictive Interval Analysis

APPENDIX B Data Set 2:
- Individual MW Summary Tables
- Excel Results:
  Test of Proportions

APPENDIX C Data Set 3:
- Individual SWPT Summary Tables
- Excel Results:
  Test of Proportions

APPENDIX D Laboratory Data and Chain of Custody Forms

EXECUTIVE SUMMARY

The October 2008 groundwater sampling event performed at the Dunn-Erwin Municipal Solid Waste Landfill (MSWLF) fulfilled the County's semi-annual groundwater sampling and analyses requirements in accordance with North Carolina Solid Waste Management Rules *15A N.C.A.C. 13 B, .1633* and *.1634.*

Prior to this report, an extensive study was completed in order to better understand the groundwater contamination plume at the site, as described in the report dated August 25, 2003, including the field investigation performed in October 2002 in conjunction with the scheduled October 2002 semi-annual sampling event. Also, 12 new observation wells were installed in the general area of the groundwater contamination plume during this field investigation. The field investigation was followed by additional laboratory testing, and an extensive analysis and computer modeling. Results from that study have been incorporated in this report also including the October 2002 delineation of the groundwater contaminant plume in the uppermost aquifer, downgradient of the MSWLF.

Several new wells (MW11, MW 12, MW 13, MW 14, and MW15) and piezometers (PZ-50, PZ-51, PZ-52, and PZ-53) have been installed and are associated with the proposed new construction and demolition debris (C&D) landfill in the southwest of the groundwater contaminant plume area.

Data from the October 2008 semi-annual sampling were evaluated in sets. Set 1 consists of wells monitoring the previously closed (December 1998) solid waste landfill portion of the site where active construction and demolition debris (C&D) placement is ongoing, including monitoring wells (MWs) MW1, MW2, MW3R, MW4, MW5, MW6, MW7B, MW8, and MW31. Monitoring well MW3, which was previously damaged during site operations prior to April 2005 sampling event has been replaced by MW3R as of June 2005. Monitoring wells MW9 and MW10 were installed in March 2001 and have been added to Data Set 1 as of April 2001. These wells have been incorporated into the statistical analysis as their background sampling was completed in October 2002.

In 2006, five (5) new MWs (MW11 - MW15) have been installed in conjunction with the proposed C&D landfill. Theoretically, these new wells belong to Set 1 since they are downgradient of the active C&D and closed MSWLF. Four of these wells (MW11 - MW14) have been incorporated into the statistical analysis of Set 1 as Subset 1N as their background sampling was completed in October 2008. MW15 was not sampled in October 2007. Consequently, background sampling for MW15 has not been completed and this well has not been incorporated into Set 1. Background sampling for MW15 is planned to be completed as part of the April 2009 sampling event. MW15 will be incorporated into the statistical analysis at that time.

Within Subset 1N, subject to the final proposed C&D landfill design and groundwater monitoring plan, one of these monitoring wells may be designated as an upgradient well to the new landfill. Additionally, one or more of the related four new piezometers (PZ-50 through PZ-53) could also be converted into monitoring wells for the new landfill, as needed.

Set 2 consists of wells monitoring the older closed portion of the landfill site, including MW16,

MW23B, MW32, MW33, and the newer MW34 and MW35 installed in June 1996. Monitoring well MW23B is statistically compared with Set 1 as it appears to be located downgradient of these wells.

Set 3 consists of surface water monitoring points (SWPTs) along the wetlands between the active and the closed areas, including SWPT1, SWPT2, and SWPT3.

Groundwater levels at all monitoring wells are also recorded, as shown in Table 1. As an overall average, groundwater levels during this latest sampling event were approximately 2.48 feet below the average groundwater level based on all sampling events, for each respective well. This value also includes groundwater levels for the wells MW11 - MW15.

The groundwater elevation map (Figure 1) has been updated with average contours based on data collected from January 2007 to May 2008. This figure now includes MW11 - MW15. In addition, Table 2, Groundwater Velocity Data, has been updated to incorporate values for MW11 - MW15.

The North Carolina Groundwater Standards (NCGS) have been amended as per 15A NCAC 02L.0202. The amendment went into effect as of April 1, 2005. This report incorporates the revised NCGS. Historical data has been comprehensively re-evaluated taking into consideration the revised NCGS.

In addition, this reporting has been revised to comply with the updated reporting requirements of the Solid Waste Section (SWS), per the SWS Memoranda dated October 27, 2006, February 23, 2007, and October 16, 2007. Specifically, the Solid Waste Section Limits (SWSL) and lower Method Detection Limits (MDLs) have been incorporated. Also, the 15A NCAC 13B groundwater protection standards (GPS) are also considered for those constituents that lack a 2L NCGS. The 13B GPS have been incorporated only as of October 2007 and are not compared to historic data.

The new MDLs are significantly less than previous detection limits. The SWSLs are more similar to the previous detection limits but are lower for several constituents. Table 6 of this report provides a comprehensive comparison of 2L NCGS, 13B groundwater protection standards, SWSL, and current and historical (2006) MDLs for constituents commonly included in the statistical analysis at the Dunn-Erwin landfill.

As required, concentrations greater than the MDL but less than the SWSL are reported by the laboratory as *estimated values*. Because historic data, including background sampling, was reported using much higher detection limits, estimated values are not incorporated into the current statistical analysis, except for the prediction interval intra-well comparison as discussed in Section III, Methodology. Only results exceeding SWSLs are included in the statistical analysis and presented in the summary tables found in Appendices A-C, as the SWSLs allow for a more consistent comparison of current and historical data. For a complete listing of estimated concentrations, refer to the laboratory reports.

As required by the new rules, the Environmental Monitoring Reporting Form accompanies this submittal. Table 4B serves as the notification table required with this form and includes results which exceed a 2L NCGS or a 13B GPS. Because some of the SWSLs are greater than the

NCGS or GPS, estimated values which exceed NCGS or GPS are included. GPS have been included with NCGS in the statistical analysis tables in the Appendices for detections above the SWSL. However, these tables do not include the estimated detections below the SWSL and are not intended to be an exhaustive comparison to NCGS and GPS.

When compared to historical detection limits, the use of the generally lower SWSLs has resulted in an increase in the number of reported detections. In addition, the lower SWSLs, which are now used in place of the detection limits in qualitative analyses (refer to Section III, Methodology), have resulted in more constituents being statistically significant over background levels (SSIOBL).

The statistical analysis results indicate that compliance wells MW6, MW7B, MW8, MW9, and MW10 in Set 1 have statistically significant levels of one or more organics over background levels when compared with the background wells. In addition, the October 2008 results show that there were more organics detected in concentrations greater than NCGS or GPS when compared to the number of organics detected above NCGS or GPS in April 2008. The October 2008 above NCGS or GPS organics include: benzene, 1,4-dichlorobenzene, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride in MW6; benzene, 1,4-dichlorobenzene, 1,2-dichloroethane (estimated value), methylene chloride, tetrachloroethylene, trichloroethylene, vinyl chloride, and 1,1,2,2-tetrachloroethane (estimated value) in MW7B; benzene, 1,4-dichlorobenzene, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride in MW8; benzene, 1,4-dichlorobenzene, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride in MW9; and benzene and vinyl chloride in MW10.

As part of this event's statistical analysis, the prediction interval intra-well comparison was incorporated to verify certain Test of Proportions (TOP) results. In select cases the compliance-to-background well analyses are not accurate because natural, statistically significant variations existed prior to the facility operation commencement. If the TOP indicates a result of Statistically Significant Increase Over Background Level (SSIOBL) for such a constituent, the prediction interval intra-well comparison is used to verify the result. If the average post-operational concentrations of the constituent are within the prediction interval analysis calculated based on background concentrations, the result is not considered SSIOBL.

Using this methodology, beryllium is not SSIOBL for MW2, MW3, and MW4, cobalt and lead are not SSIOBL for MW7B, and barium for MW23B, which would have resulted as SSIOBL using just the TOP. Cobalt and mercury in MW6 and mercury in MW7B also show statistically significant levels through the TOP. However, cobalt was not detected during MW6's background sampling, and mercury was not included in either well's background sampling. Consequently, these constituents do not qualify for an intra-well comparison. Beryllium appears as SSIOBL in MW12 when analyzed by using TOP only. However, this result cannot be substantiated at this time by the prediction interval intra-well comparison which requires data beyond the four background events. Since only background has been completed at MW12, the prediction interval intra-well comparison cannot be applied at this time. Furthermore, based on the background sampling at MW12 and compared to similar beryllium results at MW2, MW3, and MW4, the beryllium at MW12 is not considered SSIOBL. This assessment will be confirmed using the prediction interval intra-well comparison with data from the next sampling event.

The following inorganics exceeded NCGS or GPS during this sampling event, representing an increase in the number of inorganics exceeding NCGS or GPS compared to the April 2008 results: vanadium in MW31, MW2, MW3, MW5, and MW6; beryllium in MW4; lead and thallium in MW7B; and mercury in MW19. (The thallium and vanadium exceedances were estimated concentration values, except vanadium at SWPT1.) The beryllium, lead, and vanadium detections appear to be background, as these inorganics were not SSIOBL for any well. The thallium detection is also likely trace background, and its concentration was above the 13B GPS but well below the SWSL. Mercury has previously been identified in the plume area.

In Set 2, no organics or inorganics are statistically significant. No organics were detected in October 2008, consistent with the results from April 2008. For inorganics, barium and cadmium were detected in Set 2. Neither inorganic was detected over the NCGS, representing a decrease compared to the results from April 2008.

In Set 3, arsenic, barium, cobalt, lead, vanadium, zinc, chloromethane, and toluene were detected, representing an increase in detections compared to April 2008. Of the detectections, only toluene at SWPT3 is statistically significant for Set 3. The following inorganic exceeded NCGS or GPS during this sampling event, representing an increase compared to the October 2008 results: vanadium in SWPT1, SWPT2, and SWPT3. (Values were estimated at SWPT2 and SWPT3.)

Details of the statistical procedures employed are discussed in Section III of this report, entitled Methodology. The results of the October 2008 analysis are summarized and discussed for each constituent detected over the SWSL at each monitoring well or surface water monitoring point in Section III, entitled Results. Appendices A, B, C, and D contain tabulated data for the individual wells with computer-generated results of the statistical analyses performed and laboratory results with chain of custody forms, respectively. Based on these statistical analysis results and the August 2003 detailed plume investigation report, the following conclusions regarding groundwater contamination and future monitoring at the Dunn-Erwin MSWLF are presented:

- The previously active portion of the Dunn-Erwin solid waste landfill is now closed with a final cap. C&D waste is being placed on the cap area, as per SWS approval. All parameters that have been detected in concentrations that are statistically significant over background levels (SSIOBL) are being compared with North Carolina Groundwater Standards (NCGS), as appropriate.

- Harnett County has begun the implementation of corrective action program according to North Carolina Solid Waste Management Rules *15A N.C.A.C. 13 B, .1637,* as per SWS review and approval.

- Harnett County continues groundwater Assessment Monitoring in accordance with North Carolina Solid Waste Management Rule *15A N.C.A.C. 13 B, .1634.* The findings and conclusions of this report will be considered by Harnett County for the assessment of corrective action for the groundwater contamination plume, downgradient of the existing landfill implemented by Harnett County in accordance with North Carolina Solid Waste Management Rules *15A N.C.A.C. 13 B, .1635, .1636, and .1637*

- Based on updated groundwater analytical data accumulated since October 1994 from the scheduled semi-annual sampling events, the top four organic contaminants most frequently detected in downgradient monitoring wells at concentrations that consistently have exceeded NCGS include 1,1-dichloroethane, methylene chloride, tetrachloroethylene, and trichloroethylene. Prior to this event and since October 2003, benzene had been detected in the downgradient plume only in MW9 (both results occurring during the 2006 events). However, benzene detections have increased over recent sampling events. The prevalence of benzene detections will be observed in future sampling events.

- Of these four organics 1,1-dichloroethane, methylene chloride and trichloroethylene have been consistently considered as statistically significant in the semi-annual assessments. However, only methylene chloride has been consistently detected in average concentrations that are about one order of magnitude greater than NCGS. Therefore, methylene chloride has remained the key organic constituent in the groundwater contamination plume, downgradient of the MSWLF.

- With 10 detections as of the October 2007 sampling event (including past events), vinyl chloride has qualified for inclusion into the contamination plume review starting October 2007. There were five additional vinyl chloride detections in October 2008. However, vinyl chloride results **are not** as prevalent as the other top organic contaminants, and because it has a **low 2L standard** the results show apparent large average concentration-to-NCGS ratios. It has been included in Figure 3 to observe in future events.

- As of October 1999 only wells MW6, MW7B, and MW8 require annual sampling for Appendix II constituents while in assessment monitoring. All other monitoring wells of Set 1 were excluded from Appendix II sampling requirements based on approval of the North Carolina Solid Waste Section (SWS) from October 1999. However, the SWS requested in March 2007 that MW9 and MW10 also be added to the Appendix II testing since they are within the contaminant plume. Therefore, these five wells are sampled for Appendix II constituents in October annually, as required by the SWS.

- All active monitoring well locations in Set 1 should continue to be sampled and analyzed for Appendix I constituents semi-annually as per North Carolina Solid Waste Management Rules 15A N.C.A.C. 13 B, .1633, with the next Appendix I sampling event scheduled for April 2009. Monitoring well MW3 was replaced by MW3R in June 2005.

- All active monitoring wells in Set 2 should continue to be sampled and analyzed for Appendix I organics and the eight RCRA metals semi-annually while in detection monitoring. The next sampling event should occur in April 2009.

- All active surface water point locations in Set 3 should continue to be sampled and analyzed for Appendix I constituents semi-annually as per North Carolina Solid Waste Management Rules 15A N.C.A.C. 13 B, .1633, with the next Appendix I sampling event scheduled for April 2009.

- Background sampling of new wells MW11 - MW14 has been be completed as of

October 2008. These wells have been incorporated into the statistical analysis of Set 1 as a Subset 1N. MW15 currently has had only three sampling events. This well will be incorporated after background sampling is complete, which should occur in April 2009.

- The new reporting requirements have been incorporated for this sampling event. Reporting will be adjusted if required by the SWS. This submittal under the new SWS reporting requirements includes:
  - (i) Environmental Monitoring Reporting Form (hardcopy)
  - (ii) Summary Table 4B with the parameters that exceed 2L NCGS or 13B GPS in October 2008
  - (iii) A hardcopy of the EXCEL sheets from the E1I lab
  - (iv) A hard copy of the complete assessment report

I. Introduction

This statistical analysis was performed to evaluate whether groundwater and surface water monitoring results from the October 2008 sampling event at the Dunn-Erwin MSWLF in Harnett County demonstrate compliance with North Carolina Groundwater Standards (NCGS) with respect to Appendix I and Appendix II constituents of the North Carolina Solid Waste Management Rules *15A N.C.A.C. 13 B, .1633(a) and .1634(a).* The United States Environmental Protection Agency (EPA) Guidance Document, Statistical Analysis of Ground-Water Monitoring Data at RCRA Facilities, April 1989, was used as the main reference for the statistical procedures followed in this study. Details of the procedures and results obtained from the analysis are described in the following sections.

Conclusions and recommendations regarding subsequent sampling at the Dunn-Erwin MSWLF are presented in the Executive Summary. Based on the groundwater contamination plume assessment report submitted to the NCDENR Solid Waste Section (SWS) on August 25, 2003, Figure 1 shows the downgradient area of the MSWLF with approximate contamination plume boundaries of October 2002. A layout of approximate monitoring wells and surface water sampling locations and the MSWLF facility is shown in Figure 2.

II. Groundwater Levels

Table 1 shows historic groundwater levels within monitoring wells at the Dunn-Erwin landfill. Generally, groundwater levels during the October 2008 sampling event were approximately 2.48 feet below the average groundwater level based on all sampling events, for each respective well. This value includes groundwater levels for recently installed wells MW11 - MW15.

Table 2 shows estimated groundwater velocity data, previously calculated based on groundwater levels recorded in the October 1995 sampling event and updated to include average data from January 2007 to May 2008 for wells MW11 - MW15. This table also incorporates an estimated range of site hydraulic conductivity and effective porosity values.

III. Methodology

An Excel™ adaptation of the EPA software GRITS/STAT (A Ground Water Information Tracking System with Statistical Analysis Capability, Version 4.2) was utilized to perform statistical calculations. Downgradient monitoring wells (MWs) MW2, MW3R, MW4, MW5, MW6, MW7B, MW8, MW9, MW10, MW11, MW12, MW13, MW14, and MW23B were each compared with the upgradient wells MW1 and MW31 (Data Set 1), and downgradient wells MW32, MW33, MW34, and MW35 were each compared to upgradient well MW16 (Data Set 2) to evaluate the existence of statistically significant increases over background levels (SSIOBL) for each detected constituent. Surface Water Monitoring Points (SWPTs) SWPT2 and SWPT3 are compared with upgradient

SWPT1 (Data Set 3) to evaluate the existence of SSIOBL for each Appendix I constituent.

For the reasons discussed in the Executive Summary regarding differences between historic and current method detection limits (MDLs) and the Solid Waste Section Limits (SWSLs), only detections exceeding the SWSLs are included in the statistical analysis. Estimated values (concentrations reported as greater than the MDL but less than the SWSL) are not included in the statistical analysis. When referring to the statistical analysis, a non-detect is a result less than the SWSL and a detection is a result greater than the SWSL. Where necessary, estimated values are compared to NCGS or 13B Groundwater Protection Standards (GPS). A comparison of NCGS and GPS standards, SWSLs, October 2008 MDLs and detection limits from 2006 for selected commonly detected constituents are presented in Table 6.

The one-way analysis of variance test (ANOVA) compares median concentrations of the respective upgradient and downgradient wells between data sets with at least four sampling events each. The Excel™ program was employed to perform the ANOVA for each parameter in a monitoring well group with less than 50% total non-detects in all wells over all sampling events.

All data sets with less than 15% non-detects were also tested for both normal and log-normal data distributions using EPA accepted normality tests. A parametric ANOVA was performed for those data sets meeting the normality and less than 15% non-detect requirements. The parametric ANOVA also tested for residual normality and homogeneity of variances (using Levene's Test) between data sets, both of which are necessary to determine those parameters that are SSIOBL using the parametric ANOVA. For both the parametric ANOVA and Levene's Test, non-detected concentrations were computed as on one-half (1/2) of the method detection limit. If any of the above tests produced a negative result, the parametric ANOVA was disregarded. (No data sets met the criteria for a parametric ANOVA test during the latest event).

All data sets with less than 50% non-detects and not fulfilling the requirements of the parametric ANOVA test received the non-parametric ANOVA test, which utilized the Kruskal-Wallace Test for making comparisons between data sets.

The Test of Proportions, as outlined in Section 8.1.2 of the EPA Guidance document, was utilized for all data sets for constituents with less than or equal to 50% and above 10% detects in all monitoring wells combined. This test was further defined to include only those compliance wells (individually coupled with the background wells) that produced a large enough data set such that the total number of detects for the particular constituent was greater than or equal to five (5).

In select cases the compliance-to-background well analyses are not accurate because natural, statistically significant variations existed prior to the facility operation commencement. If the Test of Proportions indicates a result of SSIOBL for such a constituent, the prediction interval intra-well comparison was used to verify the statistical significance of the concentrations. If the average post-operational concentrations of the constituent are within the prediction interval analysis calculated based on background

concentrations, the result is not considered SSIOBL. Estimated values are used in the prediction interval analysis. Previously, a non-detect value was treated as half the detection limit to calculate the interval. However, use of the estimated values allows for a more accurate prediction than using half the SWSL.

For all other instances that did not qualify for the ANOVA tests or the Test of Proportions, the detections were analyzed qualitatively. The qualitative analysis was conducted for individual constituents at a particular compliance well. Initially, the number of detections for the constituent in the particular compliance well was considered as follows:

- A compliance well with only one detection was not considered SSIOBL.

- For a compliance well with two or more detections and without detections in the background well, the order of magnitude (OOM) above the SWSL was evaluated. The OOM was computed as the logarithm of the actual detected concentration over the SWSL. If the average concentrations had an OOM greater than or equal to 0.67 (five times greater than the SWSL), the constituent was considered SSIOBL for the particular well. Prior to October 2007, the detection limit was used because the SWSLs had not been incorporated. As noted in the Executed Summary, the SWSL is more consistent with historic detection limits, compared to the much lower MDLs (refer to Table 6). As such, use of the SWSL allows for a more uniform comparison to the historic data and is also consistent with the use of SWSL in the other statistical analyses.

- For a compliance well with two or more detections and with detections of the particular constituent also in the compliance well, the compliance well was evaluated depending on the number and magnitude of detections at the compliance well, the background well, and their respective average concentration differences.

Additionally, Table 5 includes the analysis of cumulative results from all sampling events of the ongoing scheduled semi-annual analyses since October 1994, showing the summary of all organic detections in Data Set 1 that includes downgradient (compliance) monitoring wells (MWs) MW2, MW3R, MW4, MW5, MW6, MW7B, MW8, MW9, MW10, MW11, MW12, MW13, MW14, and MW23B.

Page 11 of 12 in Table 5 shows overall average concentration of organics detections with respect to the number of detections, and the average-concentration-to-NCGS ratio (ANR). The criteria selected to identify main organic constituents include these that had 10 or more detections with an ANR that approaches or exceeds 1.0. Vinyl chloride was added to the list of main constituents now that it has had 10 detections.

IV. Results

This section reports results from the statistical tests performed on detected constituents (greater than SWSL as of October 2007). A summary of upgradient wells (background wells) precedes the downgradient wells for each data set. The upgradient well summaries include a complete detection history for all sampling events per upgradient well. Downgradient well summaries include a brief detection history followed by the results of the statistical tests per detected constituent.

Detections noted prior to October 2007 include all results which exceeded the historic detection limits for the respective constituents. Unless otherwise noted, a detection is now defined as a result that exceeds the SWSL as of October 2007. Estimated values (greater than the current MDL but less than the SWSL) are not listed except for some instances to compare to NCGS or GPS.

A summary of the results of the statistical tests for inorganics is shown in Table 3. In addition to the types of statistical tests and inorganic results, Table 3 also shows which inorganics were detected, both above the MDL and also above the SWSL. Table 4A indicates those parameters that have been detected in concentrations that are statistically significant over background levels (SSIOBL). Table 4B lists parameters exceeding NCGS or GPS during the April 2008 sampling event. ***Table 4B is intended to also serve as the notification table that is required with the Environmental Monitoring Reporting Form.*** To allow for a concise and legible summary, only monitoring wells with results that exceeded NCGS or GPS are listed. Results for monitoring wells or parameters not listed did not exceed NCGS or GPS. It should also be noted that Table 4B includes estimated values.

Detailed summary tables of constituent detections over the SWSL per monitoring well, recommended statistical tests per constituent, and results of the respective statistical tests are enclosed in Appendices A, B, and C for Data Sets 1, 2, and 3, respectively. Laboratory analytical data and chain of custody forms are included in Appendix D.

In Table 5, Page 11 of 12, five organic compounds shown in bold face were identified as the top organic constituents in the groundwater contamination plume, including benzene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride. 1,1-dichloroethane has been added to this list due to its NCGS revision from 700 to 70 ug/l. Vinyl chloride has been added after it had 10 detections (as of October 2007). Of these only 1,1-dichloroethane, methylene chloride, and trichloroethylene have consistently been identified as SSIOBL by the statistical analyses of the scheduled semi-annual sampling results.

An analysis to verify that these main organic constituents are consistent within the assumed area of the groundwater contamination plume was performed. The analysis included average concentration of organics detections, number of detections, and ANR values detected only in compliance wells MW6, MW7B, MW8, MW9, and MW10, and averaged only over these five (5) wells for all sampling events since October 1994. The results shown in Table 5, Page 12 of 12 verify that the main organic constituents that

had 10 or more detections with an ANR that exceeds 1.0, shown in bold face, are benzene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride.

To obtain time-line perspective of these organics detections, Figure 3 shows the average ANR values per each scheduled semi-annual sampling event in the five downgradient wells located within the estimated groundwater contamination plume area for these five organic constituents. Of these five, methylene chloride has been detected most consistently with the highest ANR values, with a maximum of 31. The Figure also shows that 1,1-dichloroethane, trichloroethylene, and tetrachloroethylene have been detected with ANR values exceeding 1.0 since the beginning of data collection in October 1994, while benzene has only been detected with ANR values exceeding 1.0 since March 1999. Vinyl chloride shows high ANR values due to a relatively lower NCGS, however, it shows ANR values greater than 1.0 much less frequently than the other constituents. It is likely the vinyl chloride detections are a result of the degradation of the larger chlorinated compounds.

Finally, methylene chloride is the only SSIOBL organic constituent that has consistently been detected in the plume area in concentrations that exceed NCGS by about one order of magnitude. Therefore, methylene chloride is identified as the key organic constituent in this groundwater contamination plume.

SET 1

Upgradient Wells (Background Wells):

MW1: MW1 is an upgradient well for MW2, MW3, MW4, MW5, MW6, MW7B, MW8, and MW23B (which is a Set 2 monitoring well). Historically, this well has shown inorganic concentrations above the detection limit for barium, beryllium, cadmium, chromium, cobalt, copper, lead, nickel, tin, vanadium, and zinc. Of these constituents, cadmium exceeded NCGS in one sampling event with a concentrations of 0.004 mg/l in January 1995. Lead exceeded NCGS in five sampling events with concentrations of 0.104, 0.104, 0.02, 0.028, and 0.018 mg/l in January, March and September 1995, and April and October 1997, respectively. Historically, carbon disulfide and diethylphthalate have been the only organic constituents detected in MW1. No constituents were detected during this latest sampling event.

The following summarizes the history of detected concentrations for each metal constituent:

barium: Barium was detected in six sampling events for MW1 with concentrations of 0.252, 0.024, 1.68, 0.586, 0.083, and 0.1 mg/l in October and November 1994, January and March 1995, October 1997, and October 1998, respectively.

beryllium: Beryllium was detected in nine sampling events for MW1 with concentrations of 0.024, 0.006, 0.002, 0.002, 0.003, 0.006, 0.001, 0.004, 0.003, 0.002, and 0.002 mg/l in January, March, and September 1995,

April and October 1996, April and October 1997, April and October 1998, October 1999, and April 2002, respectively.

cadmium: Cadmium was detected in four sampling events for MW1 with concentrations of 0.0008, 0.001, 0.004, and 0.011 mg/l, in October and November 1994 and January and March 1995, respectively.

chromium: Chromium was detected in five sampling events with concentrations of 0.005, 0.018, 0.011, 0.013, 0.02 mg/l in October 1994, January and March 1995, April 1997, and April and October 1998, respectively.

cobalt: Cobalt was detected in only one sampling event for MW1 with a concentration of 0.016 mg/l in January 1995.

copper: Copper was detected in four sampling events for MW1 with concentrations of 0.017, 0.078, 0.018, and 0.007 mg/l in October 1994, January and March 1995, and October 1997, respectively.

lead: Lead was detected in six sampling events for MW1 with concentrations of 0.005, 0.104, 0.104, 0.02, 0.028, and 0.018 mg/l in October 1994 and January, March, and September 1995, and April and October 1997, respectively.

nickel: Nickel was detected for one sampling event in MW1 with a concentration of 0.03 mg/l in January 1995.

vanadium: Vanadium was detected in two sampling events for MW1 with concentrations of 0.02 and 0.083 mg/l in October 1994, and January 1995, respectively.

zinc: Zinc was detected in eight sampling events in MW1 with concentrations of 0.098, 0.012, 0.237, 0.038, 0.08, 0.065, 0.08, and 0.011 mg/l in October and November 1994 and January , March, and September 1995, April 1997, April 2004, and May 2007, respectively.

The following organics have been detected in MW1:

carbon disulfide: Carbon disulfide was detected in two sampling event in MW1 with concentrations of 20.9 and 7.4 mg/l in November 1994 and October 1999, respectively.

diethylphthalate: Diethylphthalate was detected in three sampling events for MW1 with concentrations of 5.3, 5.3 and 9.8 ug/l in September 1995, April 1996 and April 1997, respectively.

MW31: MW31 is a background well for MW2, MW3, MW4, MW5, MW6, MW7B, MW8 and MW23B. The detected metals in MW31 have been barium, beryllium, cadmium, chromium,

cobalt, copper, lead, vanadium, and zinc. Of these, arsenic exceeded NCGS in one sampling event with a concentrations of 0.055 mg/l in September 1995. Cadmium exceeded NCGS in three events with concentrations of 0.005, 0.003, and 0.003 in January 1995, March 1995, and September 1995, respectively. Chromium exceeded NCGS in five events with concentrations of 0.21, 0.124, 0.06, 0.08, and 0.1 mg/l in September 1995, April and October 1997, October 1998, and March and October 1999, respectively, and was detected at a concentration of 0.01 mg/l in April 2000. Lead exceeded NCGS in nine events with concentrations of 0.0052, 0.033, 0.17, 0.031, 0.088, 0.045, 0.03, 0.05, and 0.06 mg/l in January, March and September 1995, April 1996, April and October 1997, October 1998, and March and October 1999, respectively. Vanadium exceeded the 13B GPS with *estimated* results of 6.6, 20.7, and 19.9 ug/l in October 2007, April 2008, and October 2008. There have been no detected organics in MW31. Lead was the only constituent detected during this latest sampling event.

The following summarizes the history of detected concentrations for each metal constituent in MW31:

arsenic: Arsenic was detected in five sampling events for MW31 with concentrations of 0.005, 0.055, 0.011, 0.032, and 0.005 mg/l in March and September 1995 April 1996, and April and October 1997, respectively.

barium: Barium was detected in four sampling events for MW31 with concentrations of 0.04, 0.157, 0.097, and 0.098 mg/l in October 1994, January and March 1995, and October 1997 respectively.

beryllium: Beryllium was detected in four sampling events for MW31 with concentrations of 0.028, 0.006, 0.003, 0.001 and 0.005 mg/l in November 1994, September 1995, April and October 1997, and October 1999, respectively.

cadmium: Cadmium was detected in four sampling events for MW31 with concentrations of 0.005, 0.003, 0.003, and 0.001 mg/l in January, March, and September 1995, and April 1997, respectively.

chromium: Chromium was detected in nine sampling events for MW31 with concentrations of 0.021, 0.015, 0.021, 0.21, 0.044, 0.124, 0.06, 0.04, 0.01, and 0.01 mg/l in October and November 1994, January and September 1995, April 1996, April and October 1997, October 1998, October 1999, and April 2000, respectively.

cobalt: Cobalt was detected in two sampling events for MW31 with concentrations of 0.007 and 0.02 mg/l in January and September 1995, respectively.

copper: Copper was detected in eight sampling events for MW31 with concentrations of 0.011, 0.006, 0.052, 0.033, 0.017, 0.033, 0.043, and

0.06 mg/l, in October and November 1994, January, March, and September 1995, April 1996, April 1997, and October 1998, respectively.

lead: Lead was detected in ten sampling events for MW31 with concentrations of 0.011, 0.006, 0.052, 0.033, 0.017, 0.031, 0.088, 0.045, 0.03, 0.06, 0.014, and 0.013 mg/l, in October and November 1994, January, March, and September 1995, April 1996, April and October 1997, October 1998, October 1999, April 2008, and October 2008, respectively.

vanadium: Vanadium was detected for nine sampling events for MW31 with concentrations of 0.045, 0.026, 0.032, 0.08, 041, 0.087, 0.235, 0.11, and 0.04 mg/l, in October and November 1994, January, March, and September 1995, April 1996, April and October 1997, and October 1998, respectively.

zinc: Zinc was detected for nine sampling events in MW31 with concentrations of 0.017, 0.01, 0.027, 0.037, 0.07, 0.05, 0.04, 0.01, 0.017, and 0.01 mg/l, in October and November 1994, January, March, and September 1995, April 1996, October 1997, October 1998, October 1999, May 2007, and April 2008, respectively.

Downgradient Wells (Compliance Wells):

MW2: Compliance well MW2 has shown inorganic detections for arsenic, barium, beryllium, cadmium, chromium, cobalt, copper, lead, nickel, vanadium, and zinc. Of these, cadmium exceeded NCGS in two events, with concentrations of 0.003 and 0.004 mg/l in March and September 1995, respectively. Lead exceeded NCGS in four events, with concentrations of 0.025, 0.025, 0.041, and 0.025 mg/l in November 1994 and January, March and September 1995, respectively. Vanadium exceeded the 13B GPS with an *estimated* results of 3.6 ug/l in October 2008. Diethylphthalate, an Appendix II constituent not included in Appendix I, was detected in September 1995 in MW2. This was the only organic constituent detected for all sampling events in MW2. Beryllium was the only constituent detected during this latest sampling event.

The following results were obtained for the detected metals in October 2008:

beryllium: Beryllium resulted as not SSIOBL for MW2 using the Prediction Interval Analysis.

MW3R: Compliance well MW3R has replaced compliance well MW3. Groundwater data from sampling events prior to October 2005 from MW3 have been utilized to compare with the data for MW3R sampled beginning in October 2005.

Compliance well MW3 and/or MW3R previously had metal detections for barium, beryllium, cadmium, chromium, cobalt, copper, lead, vanadium, and zinc. Cadmium, exceeded NCGS in two sampling events with concentrations of 0.002 and 0.011 mg/l in November 1994 and March 1995, respectively. Vanadium exceeded the 13B GPS with an *estimated*

results of 4.3 ug/l in October 2008. Carbon disulfide has been the only organic constituent detected in MW3/3R. Barium, beryllium and zinc were the only constituents detected during this latest sampling event.

The following results were obtained for the detected metals in October 2008:

barium: Barium resulted as not SSIOBL for MW3 using the Test of Proportions.

beryllium: Beryllium resulted as not SSIOBL for MW3 using the Prediction Interval Analysis.

zinc: Zinc resulted as not SSIOBL for MW3 using the Test of Proportions.

MW4: MW4 has had a history of detections of inorganics barium, beryllium, cadmium, chromium, cobalt, copper, lead, nickel, vanadium, and zinc. Beryllium exceeded the 13B GPS with a result of 6.0 ug/l in October 2008. Cadmium has exceeded NCGS in one event with a concentration of 0.004 mg/l in March 1995. Lead has exceeded NCGS in two events: 0.018 mg/l in both November 1994 and October 1996. Carbon disulfide and diethylphthalate have been the only detected organics for MW4, however no organics were detected in this latest sampling. Beryllium and zinc were the only constituents detected during this latest sampling event.

The following results were obtained for the detected metals in October 2008:

beryllium: Beryllium resulted as not SSIOBL for MW4 using the Prediction Interval Analysis.

zinc: Zinc resulted as not SSIOBL for MW4 using the Test of Proportions.

MW5: Compliance well MW5 had shown above the detection limit inorganic concentrations for barium, cadmium, chromium, copper, lead, nickel, vanadium, and zinc. Of these, chromium exceeded NCGS in one sampling event with a concentration of 0.009 mg/l in October 1994. Vanadium exceeded the 13B GPS with an *estimated* results of 4.0 ug/l in October 2008. Carbon disulfide has been the only organic constituent detected with a concentration of 30.5 and 6.4 ug/l in November 1994 and October 1999. Barium, beryllium and zinc were the only constituents detected during this latest sampling event.

The following results were obtained for the detected metals in October 2008:

barium: Barium resulted as not SSIOBL for MW5 using the Test of Proportions.

beryllium: Beryllium resulted as not SSIOBL for MW5 using the Test of Proportions.

zinc: Zinc resulted as not SSIOBL for MW5 using the Test of Proportions.

MW6: Compliance well MW6 has a history of inorganic detections for arsenic, barium, cadmium, chromium, cobalt, copper, lead, mercury, nickel, vanadium, and zinc. Of these, cadmium has exceeded NCGS in three sampling event with concentrations of 0.005,

0.009, and 0.004 mg/l in October and November 1994 and January 1995, respectively. Lead has exceeded NCGS in four sampling events with concentrations of 0.019, 0.033, 0.037, and 0.019 mg/l in November 1994, January and September 1995, and April 1996, respectively. Mercury exceeded NCGS in two sampling events with a concentration of 0.002 mg/l in October 1999. Zinc exceeded NCGS in one sampling event with a concentration of 91.5 mg/l in October 2004. Vanadium exceeded 13B GPS with *estimated* results of 7.3 and 5.5 ug/l in October 2007 and October 2008. Barium and cobalt were the only inorganic constituents detected during this latest sampling event at MW6.

Detected organics for MW6 include acetone, benzene, bis(2-ethylhexyl)phthalate, carbon disulfide, chlorobenzene, 1,4-dichlorobenzene, chloroethane, 1,1-dichloroethane, 1,1-dichloroethene, dichlorodifluoromethane, methylene chloride, 1,1,1-trichlroethane, trichloroethylene, vinyl chloride, and xylenes. Benzene has exceeded NCGS in six sampling events with concentrations of 2.7, 3.4, 9.5, 6.1, 4.2, and 4.9 ug/l in March and October 1999, April 2001, October 2007, and April and October 2008, respectively. Chlorobenzene exceeded NCGS in October 1998 with a concentration of 70 ug/l. Chloromethane exceeded NCGS in one sampling event with a concentration of 46 ug/l in April 2000. 1,4-dichlorobenzene has exceeded NCGS in six sampling events with concentrations of 7.2, 6.9, 3.2, 7.7, 7.4, and 5.0 ug/l in April 2001, October 2005, May 2007, October 2007, and April and October 2008, respectively. 1,1-dichloroethane has exceeded NCGS in seven sampling events with concentrations of 78.9, 105, 87.1, 80, 134, 160, and 88 ug/l in October 1994, January and March 1995, October 1996, April and October 1997, and March 1999, respectively. 1,1-dichloroethene has exceeded NCGS in one sampling event with a concentration of 83.2 ug/l in January 1995. 1,2-dichloroethane has exceeded 13B GPS in two sampling events with estimated concentrations of 0.6 and 0.4 ug/l in October 2007 and April 2008, respectively. Methylene chloride has exceeded NCGS in 13 sampling events with concentrations of 66, 109, 47, 37, 34.8, 28.2, 12.8, 64.5, 20.1, 12.9, 8.8, 33, and 9.0 ug/l in October 2000, April and October 2001, April and October 2002, October 2003, April 2004, October 2005, April and October 2006, May and October 2007, and October 2008, respectively. Tetrachloroethylene has exceeded NCGS in 12 sampling events with concentrations of 5.3, 3.8, 5.6, 1.9, 8.2, 7.1, 6.2, 8.0, 6.9, 9.3, 4.5, and 3.8 ug/l in October 1994, January and March 1995, October 1999, April 2001, October 2005, April and October 2006, May and October 2007, and April and October 2008, respectively. Trichloroethylene has exceeded NCGS in 19 sampling events with concentrations of 8.4, 6.7, 10.6, 8.8, 7.2, 6.8, 11, 9.9, 8.7, 7.0, 17, 5.4, 5.2, 8.8, 7.1, 8.1, 7.7, 9.24, 5.9, and 4.9 ug/l in October and November 1994, January and March 1995, February and October 1996, April and October 1997, October 1999, April 2000, April and October 2001, April 2002, October 2005, April and October 2006, May and October 2007, and April and October 2008, respectively. Vinyl chloride has exceeded NCGS in six sampling events with concentrations of 22, 11.2, 8, 7.2, 6.3, and 10.8 ug/l in April 2001, April 2006, May and October 2007, and April and October 2008, respectively.

Benzene, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride were the detected organics at MW6 during this latest sampling event.

The following results were obtained for the detected metals in MW6 in October 2008:

barium: Barium resulted as not SSIOBL for MW6 using the Test of Proportions.

cobalt: Cobalt resulted as SSIOBL for MW6 using the Test of Proportions.

The following results were obtained for the detected organics in October 2008:

benzene: Benzene resulted as SSIOBL for MW6 using the Qualitative Test.

1,4-dichlorobenzene: 1,4-dichlorobenzene resulted as SSIOBL for MW6 using the Qualitative Test.

cis-1,2-dichloroethene: cis-1,2-Dichloroethene resulted as SSIOBL for MW6 using the Test of Proportions.

1,1-dichloroethane: 1,1-dichloroethane resulted as SSIOBL for MW6 using the Test of Proportions.

methylene chloride: Methylene chloride resulted as SSIOBL for MW6 using the Test of Proportions.

tetrachloroethylene: Tetrachloroethylene resulted as SSIOBL for MW6 using the Qualitative Test.

trichloroethylene: Trichloroethylene resulted as SSIOBL for MW6 using the Test of Proportions.

vinyl chloride: Vinyl chloride resulted as SSIOBL for MW6 using the Qualitative Test.

MW7B: Compliance well MW7B has replaced compliance well MW7. Groundwater data from previous sampling events (October and November 1994, and January and March 1995) from MW7 have been utilized to compare with the data for MW7B sampled since September 1995.

Detected metals in MW7 and/or MW7B include arsenic, barium, beryllium, cadmium, chromium, cobalt, copper, lead, nickel, vanadium, zinc, and mercury. Of these, arsenic exceeded NCGS in one sampling event with a concentration of 0.279 mg/l in October 1997. Cadmium exceeded NCGS in two sampling events with a concentration of 0.004 in both September 1995 and April 1997. Chromium exceeded NCGS in three sampling events with concentrations of 0.04, 0.09, and 0.071 mg/l in March and September 1995, and April 1997, respectively. Lead exceeded NCGS in 20 sampling events with concentrations of 0.519, 0.044, 0.36, 0.196, 0.087, 0.264, 0.062, 0.070, 0.71, 0.05, 0.10, 0.036, 0.017, 0.020, 0.035, 0.018, 0.027, 0.019, 0.031, and 0.019 mg/l in October 1994, March and September 1995, April and October 1996, April and October 1997, April 1998, March and October 1999, April and October 2000, October 2001, April 2002, October 2003, October 2004, and April and October 2005, October 2007, and October 2008 respectively. Mercury exceeded NCGS in six sampling events with concentrations of 0.0027, 0.00142, 0.0011, 0.0015, 0.0046, and 0.0026 mg/l in October 2002, October 2003,

October 2004, October 2005, October 2006, and October 2007, respectively. Thallium exceeded 13B GPS with *estimated* results of 0.5, 0.4, and 2.8 ug/l in October 2007, April 2008, and October 2008, respectively. Vanadium exceeded 13B GPS with an *estimated* result of 14.2 ug/l in October 2007.

Barium, cobalt, lead, and mercury were the detected metals at MW7 during this latest sampling event.

Detected organics have included benzene, chlorobenzene, chloroethane, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,1-dichloroethene, 1,1-dichloroethane, 1,2-dichloroethane, methylene chloride, toluene, 1,1,1-trichloroethane, tetrachloroethylene, trichloroethylene, trichlorofluoromethane, xylenes, dichlorodifluoromethane, diethylphthalate, and bis(2-ethylhexyl)phthalate. Of these, benzene has exceeded NCGS in five sampling events with concentrations of 1.1, 4.7, 4.1, 4.2, and 5.8 ug/l in March 1999, May 2007, October 2007, and April and October 2008, respectively. 1,4-dichlorobenzene has exceeded NCGS in one sampling event with a concentration of 1.7 ug/l in October 2008. Chloromethane has exceeded NCGS in one sampling event with a concentration of 64 ug/l in April 2000. 1,1-dichloroethane has exceeded NCGS in 22 sampling events with concentrations of 262, 100, 92, 77, 100, 99.5, 110, 210, 170, 90, 176, 230, 87.1, 220, 141, 137, 113, 147, 176, 174, 153, and 129 ug/l in October 1994, September 1995, February, April and October 1996, April 1998, March and October 1999, April and October 2000, October 2001, April and October 2002, April and October 2003, April and October 2004, April 2005, April and October 2006, and May and October 2007, respectively. 1,2-dichloroethane has exceeded NCGS in two sampling events with a concentration of 8.7 ug/l in April 2003 and an *estimated* concentration of 0.4 ug/L in October 2008. 1,1-dichloroethene has exceeded NCGS in one sampling event with a concentration of 8.1 ug/l in April 2003. Methylene chloride has exceeded NCGS in 16 sampling events with concentrations of 60, 75, 138, 154, 26.4, 174, 70.3, 93.3, 101, 75.1, 59.6, 79.9, 74.1, 74.5, 45.5, and 69 ug/l in October 2000, April and October 2001, April and October 2002, April and October 2003, April and October 2004, April and October 2005, April and October 2006, May and October 2007, and October 2008, respectively. Tetrachloroethylene exceeded NCGS in four sampling events with concentrations of 9.0, 3.7, 3.2, and 3.7 ug/l in October 2005, October 2007, and April and October 2008, respectively. Trichloroethylene exceeded NCGS in 18 sampling events, with concentrations of 9.9, 10.7, 3.6, 7.8, 6.0, 5.3, 7.3, 8.8, 6.8, 7.6, 7.7, 7.5, 10.5, 9.9, 8.8, 9.2, 9.1, and 8.8 ug/l in October and November 1994, March and October 1999, April 2000, April and October 2001, April 2002, October 2003, April and October 2004, April 2005, April and October 2006, May and October 2007, and April and October 2008, respectively. Vinyl chloride has exceeded NCGS in four sampling events with concentrations of 5, 5, 3.9, and 8.2 ug/l in May and October 2007, and April and October 2008, respectively. 1,1,2,2-tetrachloroethane exceeded 13B GPS with an *estimated* result of 1.0 ug/l in October 2008.

During this latest sampling event, benzene, chlorobenzene, chloroethane, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, trichloroflouromethane, vinyl chloride, xylenes, and dichlorodifluoromethane were detected at MW7B.

The following results were obtained for the detected inorganics in MW7/7B in October 2008:

barium: Barium resulted as not SSIOBL for MW7/7B using the Test of Proportions.

cobalt: Cobalt resulted as not SSIOBL for MW7/7B using the Prediction Interval Analysis.

lead: Lead resulted as not SSIOBL for MW7/7B using the Prediction Interval Analysis.

mercury: Mercury resulted as SSIOBL for MW7/7B using the Test of Proportions.

The following results were obtained for the detected organics in MW7/7B October 2008:

benzene: Benzene resulted as not SSIOBL for MW7/7B using the Qualitative Test.

chlorobenzene: Chlorobenzene resulted as not SSIOBL for MW7/7B using the Qualitative Test.

chloroethane: Chloroethane resulted as SSIOBL for MW7/7B using the Test of Proportions.

1,4-dichlorobenzene: 1,4-dichlorobenzene resulted as not SSIOBL for MW7/7B using the Qualitative Test.

cis-1,2-dichloroethene: cis-1,2-Dichloroethene as not SSIOBL for MW7/7B using the Test of Proportions.

1,1-dichloroethane: 1,1-dichloroethane resulted as SSIOBL for MW7/7B using the Test of Proportions.

methylene chloride: Methylene chloride resulted as SSIOBL for MW7/7B using the Test of Proportions.

tetrachloroethylene: Tetrachloroethylene resulted as SSIOBL for MW7/7B using the Qualitative Test.

trichloroethylene: Trichloroethylene resulted as SSIOBL for MW7/7B using the Test of Proportions.

trichloroflouromethane: Trichloroflouromethane resulted as SSIOBL for MW7/7B using the Qualitative Test.

vinyl chloride: Vinyl chloride resulted as SSIOBL for MW7/7B using the Qualitative Test.

xylenes: Xylenes resulted as SSIOBL for MW7/7B using the Test of Proportions.

dichlorodifluoromethane: Dichlorodifluoromethane resulted as SSIOBL for MW7/7B using the Test of Proportions.

MW8: Compliance well MW8 has shown above detection limit inorganic concentrations for barium, beryllium, cadmium, chromium, copper, lead, vanadium, zinc, cyanide, and mercury. Cadmium exceeded NCGS in two sampling event with a concentration of 0.002 mg/l in both November 1994 and April 1997. Chromium exceeded NCGS in one sampling event with a concentration of 0.111 mg/l in April 1997. Lead exceeded NCGS in one sampling event with a concentration of 0.073 mg/l in April 1997. Cyanide exceeded NCGS in one sampling event with a concentration of 0.127 mg/l in October 1996. Mercury exceeded NCGS in one sampling event with a concentration of 0.002 mg/l in October 1998. Barium and mercury were the only detected metal at MW8 during this latest sampling event.

Detected organics at MW8 have included benzene, cis-1,2-dichloroethene, carbon disulfide, chloroethane, chloromethane, 1,4-dichlorobenzene, 1,1-dichloroethane, methylene chloride, dichlorodifluoromethane, vinyl chloride, and xylenes. Benzene exceeded NCGS in five sampling events, with concentrations of 2.1, 1.6, 2.6, 2.5, and 2.9 ug/l in October 1997, March 1999, October 2007, and April and October 2008, respectively. Chloromethane exceeded NCGS in three sampling events, with concentrations of 6.1, 88, and 25 ug/l in October 1999, April 2000, and October 2001, respectively. 1,4-dichlorobenzene exceeded NCGS in one sampling event with a concentrations of 1.5 ug/l in October 2008. 1,1-dichloroethane exceeded NCGS in five sampling events with concentrations of 92, 135, 80, 76.8, and 71.5 ug/l in April 2000, April 2001, April and October 2002, and April 2003, respectively. 1,1-dichloroethene exceeded NCGS in one sampling event, with a concentration of 81 ug/l in October 2001. Methylene chloride exceeded NCGS in 22 sampling events, with concentrations of 49, 31, 5.2, 25, 30, 74, 140, 92, 90, 80.5, 71.2, 69, 44.5, 39.9, 40.6, 63.3, 64, 67.2, 48.4, 35.9, 31, and 48 ug/l in April and October 1997, April and October 1998, March 1999, October 2000, April and October 2001, April and October 2002, April and October 2003, April and October 2004, April and October 2005, April and October 2006, May and October 2007, and April and October 2008, respectively. Tetrachloroethylene exceeded NCGS in five sampling events, with concentrations of 5.2, 5, 6.5, 5.5, and 4.7 ug/l in October 2006, May and October 2007, and April and October 2008, respectively. Trichloroethylene exceeded NCGS in six sampling events, with concentrations of 6.8, 5.3, 4, 4.4, 4.8, and 4.8 ug/l in April and October 2001, May and October 2007, and April and October 2008, respectively. Vinyl chloride exceeded NCGS with an *estimated* result of 0.9 ug/l in October 2007 and results of 1.0 and 1.5 ug/L in April and October 2008, respectively.

During this latest sampling event, benzene, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride were detected at MW8.

The following result was obtained for the detected inorganic in MW8 in October 2008:

barium: Barium resulted as not SSIOBL for MW8 using the Test of Proportions.

mercury: Mercury resulted as not SSIOBL for MW8 using the Test of Proportions.

The following results were obtained for the detected organics in MW8 in October 2008:

benzene: Benzene resulted as not SSIOBL for MW8 using the Qualitative Test.

1,4-dichlorobenzene: 1,4-Dichlorobenzene resulted as not SSIOBL for MW8 using the Qualitative Test.

cis-1,2-dichloroethene: cis-1,2-Dichloroethene resulted as not SSIOBL for MW8 using the Test of Proportions.

1,1-dichloroethane: 1,1-Dichloroethane resulted as SSIOBL for MW8 using the Test of Proportions.

methylene chloride: Methylene chloride resulted as SSIOBL for MW8 using the Test of Proportions.

tetrachloroethylene: Tetrachloroethylene resulted as SSIOBL for MW8 using the Qualitative Test.

trichloroethylene: Trichloroethylene resulted as SSIOBL for MW8 using the Test of Proportions.

vinyl chloride: Vinyl chloride resulted as not SSIOBL for MW8 using the Qualitative Test.

MW9: Compliance well MW9 was installed in March 2001 and was sampled for the first time in April 2001. The data are now included in the statistical analysis.

Detected metals in MW9 include barium, chromium, copper, lead, mercury, and vanadium. Chromium exceeded NCGS in one sampling event with a concentration of 0.082 mg/l in October 2002. Mercury exceeded NCGS in two sampling events with concentrations of 0.005 and 0.0015 mg/l in October 2007. Barium and mercury were the only detected inorganics during this latest sampling event.

Detected organics at MW9 have included benzene, chlorobenzene, chloroethane, chloromethane, 1,2-dibromoethane, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,1-dichloroethane, 1,2-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, vinyl chloride, and xylenes. Of these, benzene exceeded NCGS in 12 sampling events, with concentrations of 8.6, 11, 7.8, 8.2, 8.1, 6.4, 5.6, 5.2, 5, 5.4, 11.5, and 8 ug/l in April and October 2001, April and October 2002, April and October 2003, April and October 2006, May and October 2007, and April and October 2008, respectively. Chloromethane exceeded NCGS in one sampling event, with a concentration of 189 ug/l in

April 2001. 1,2-dibromoethane exceeded NCGS in one sampling event, with a concentration of 14 ug/l in October 2001. 1,4-dichlorobenzene exceeded NCGS in three sampling events, with concentrations of 2.5, 6.6, and 2.1 ug/l in October 2007, and April and October 2008, respectively. 1,1-dichloroethane exceeded NCGS in 12 sampling events, with concentrations of 126, 219, 170, 202, 135, 122, 75.2, 81.9, 110, 103, 87, and 74.7 ug/l in October 2001, April and October 2002, April and October 2003, April and October 2004, April and October 2005, April and October 2006, and May 2007, respectively. 1,2-dichloroethane exceeded NCGS in two sampling event, with concentrations of 11.8 and 0.8 (estimated) ug/l in April 2003 and April 2008, respectively. Methylene chloride exceeded NCGS in 14 sampling events, with concentrations of 195, 231, 272, 197, 166, 127, 67.9, 56.7, 75.7, 122, 96.4, 64.2, 49.6, and 64.6 ug/l in October 2001, April and October 2002, April and October 2003, April and October 2004, April and October 2005, April and October 2006, May and October 2007, and October 2008, respectively. Tetrachloroethylene exceeded NCGS in six sampling events, with concentrations of 5.3, 5.3, 5.1, 2.9, 4.4, 2.4 ug/l in October 2001, October 2002, April 2003, October 2007, and April and October 2008, respectively. Trichloroethylene exceeded NCGS in 15 sampling events, with concentrations of 11, 15, 9.8, 10, 9.5, 8.2, 5.8, 7.0, 6.5, 6.2, 5.0, 4.7, 3.9, 5.9, and 4.2 ug/l in April and October 2001, April and October 2002, October 2003, April and October 2004, April and October 2005, April and October 2006, May and October 2007, and April and October 2008, respectively. Vinyl chloride exceeded NCGS in four sampling events, with concentrations of 9.1, 5.9, 6.5, and 8.7 ug/l in May and October 2007, and April and October 2008, respectively.

Benzene, chlorobenzene, chloroethane, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, and vinyl chloride were detected at MW9 during this latest sampling event.

The following result was obtained for the detected inorganic in MW9 in October 2008:

barium: Barium resulted as not SSIOBL for MW9 using the Test of Proportions.

mercury: Mercury resulted as not SSIOBL for MW9 using the Test of Proportions.

The following results were obtained for the detected organics in MW9 in October 2008:

benzene: Benzene resulted as SSIOBL for MW9 using the Qualitative Test.

chlorobenzene: Chlorobenzene resulted as not SSIOBL for MW9 using the Qualitative Test.

chloroethane: Chloroethane resulted as SSIOBL for MW9 using the Test of Proportions.

1,4-dichlorobenzene: 1,4-dichlorobenzene resulted as not SSIOBL for MW9 using the Qualitative Test.

cis-1,2-dichloroethene: cis-1,2-Dichloroethene resulted as SSIOBL for MW9 using the Test of Proportions.

1,1-dichloroethane: 1,1-dichloroethane resulted as SSIOBL for MW9 using the Test of Proportions.

methylene chloride: Methylene chloride resulted as SSIOBL for MW9 using the Test of Proportions.

tetrachloroethylene: Tetrachloroethylene resulted as not SSIOBL for MW9 using the Qualitative Test.

trichloroethylene: Trichloroethylene resulted as SSIOBL for MW9 using the Test of Proportions.

vinyl chloride: Vinyl chloride resulted as SSIOBL for MW9 using the Qualitative Test.

MW10: Compliance well MW10 was installed in March 2001 and was sampled for the first time in April 2001. The data are now included in the statistical analysis.

Detected metals in MW10 include chromium, copper, lead, vanadium and zinc. Chromium exceeded NCGS in one sampling event with a concentration of 0.118 mg/l in October 2002. Vanadium exceeded 13B GPS with *estimated* results of 12.2 and 3.7 ug/l in October 2007 and April 2008. No inorganics were detected during this latest sampling event.

Detected organics at MW10 have included acetone, benzene, chlorobenzene, chloroethane, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,2-dibromoethane, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, toluene, trichloroethylene, vinyl chloride, and xylenes. Of these, benzene exceeded NCGS in seven sampling events, with concentrations of 6.9, 7.3, 6.2, 4.6, 2.0, 4.5, and 3.9 ug/l in April and October 2001, April 2002, May and October 2007, and April and October 2008, respectively. 1,1-dichloroethane exceeded NCGS in three sampling events, with concentrations of 266, 109, and 606 ug/l, in Oct. 2001, April 2002, and April 2004, respectively. Methylene chloride exceeded NCGS in 11 sampling events, with concentrations of 120, 310, 132, 59.3, 19.7, 48.7, 48, 67.7, 51.6, 27.1, 14.4, and 4.1 ug/l in April and October 2001, April and October 2002, April and October 2003, April and October 2004, April 2005, April 2006, and April 2008, respectively. Tetrachloroethylene exceeded NCGS in six sampling events, with concentrations of 12, 11, 13, 6.8, 7.1, and 7.3 ug/l in April and October 2001, April and October 2002, and April and October 2003, respectively. Trichloroethylene exceeded NCGS in four sampling events, with a concentrations of 11, 11, 9.1, and 5.7 ug/l in April and October 2001, April 2002, and October 2003, respectively. Vinyl chloride exceeded NCGS in four sampling events, with concentrations of 10, 1.4, 2, and 3.3 ug/l in April 2001, October 2007, and April and October 2008, respectively.

Benzene, 1,4-dichlorobenzene, cis-1,2-dichloroethene, 1,1-dichloroethane, toluene and vinyl chloride were the detected organics at MW10 during this latest sampling event.

The following results were obtained for the detected organics in MW10 in October 2008:

benzene: Benzene resulted as not SSIOBL for MW10 using the Qualitative Test.

1,4-dichlorobenzene: 1,4-Dichlorobenzene resulted as not SSIOBL for MW10 using the Qualitative Test.

cis-1,2-dichloroethene: cis-1,2-dichloroethene resulted as SSIOBL for MW10 using the Test of Proportions.

1,1-dichloroethane: 1,1-Dichloroethane resulted as SSIOBL for MW10 using the Test of Proportions.

toluene: Toluene resulted as not SSIOBL for MW10 using the Qualitative Test.

vinyl chloride: Vinyl chloride resulted as not SSIOBL for MW10 using the Qualitative Test.

MW11: Compliance well MW11 was installed in 2006 and was sampled for the first time in May 2007. The data are now included in the statistical analysis. Detected metals in MW11 include zinc. Vanadium exceeded 13B GPS with an *estimated* concentration of 6.2 ug/l in October 2008. No organics have been detected in MW11. No inorganics were detected during this latest sampling event.

MW12: Compliance well MW12 was installed in 2006 and was sampled for the first time in May 2007. The data are now included in the statistical analysis. Detected metals in MW12 include beryllium and zinc. Vanadium exceeded 13B GPS with an *estimated* concentration of 6.4 ug/l in October 2007. No inorganics have exceeded NCGS or 13B GPS. No organics have been detected in MW12. Beryllium and zinc were detected during this latest sampling event.

The following results was obtained for the detected inorganics in MW12 in October 2008:

beryllium: Based on the Test of Proportions beryllium appears as SSIOBL for MW12. Because only background data is available, this well does not yet qualify for the Prediction Interval Analysis. However, because beryllium was detected in each background event and based on similar results at wells MW2, MW3, and MW4, beryllium appears to be background at MW12 and is not considered SSIOBL.

zinc: Zinc resulted as not SSIOBL for MW12 using the Test of Proportions.

MW13: Compliance well MW13 was installed in 2006 and was sampled for the first time in May 2007. The data are now included in the statistical analysis. Detected metals in MW13 include zinc. No inorganics have exceeded NCGS or 13B GPS. No organics have been detected in MW13. No inorganics were detected during this latest sampling event.

MW14: Compliance well MW14 was installed in 2006 and was sampled for the first time in May 2007. The data are now included in the statistical analysis. Detected metals in MW14 include zinc. No inorganics have exceeded NCGS or 13B GPS. No organics have been detected in MW14. Zinc was the only detection during this latest sampling event.

The following result was obtained for the detected inorganic in MW14 in October 2008:

zinc: Zinc resulted as not SSIOBL for MW14 using the Test of Proportions.

MW23B: MW23B is a Set 2 well. It does not follow the Set 1 analysis schedule since it is too remote to be a monitoring point for the active portion of the landfill. It is analyzed for Appendix I organics plus the eight RCRA metals as a part of Set 2. However, it is statistically compared with Set 1 because it appears to be located downgradient of the active landfill.

Compliance well MW23B had shown above the detection limit inorganic concentrations for barium, beryllium, cadmium, chromium, copper, lead, selenium, silver, zinc, and mercury. Of these, lead exceeded NCGS in March and September 1995, February 1996, March and October 1999 with concentrations of 0.018, 0.027, 0.0157, 0.049, and 0.089 mg/l, respectively. Arsenic exceeded NCGS in one sampling event with a concentration of 0.064 in October 1997. Silver exceeded NCGS in one sampling event with a concentration of 0.105 in January 1995. Mercury also exceeded NCGS in one sampling event with a concentration of 0.0017 mg/l in March 1999. No organics have been detected in MW23B. Barium was the only detected during the latest sampling event.

The following result was obtained for the detected inorganic in MW23B in October 2008:

barium: Barium resulted as not SSIOBL for MW23B using the Prediction Interval Analysis.

DATA SET 2

In October 2008, Set 2 monitoring wells were sampled, analyzed, and statistically evaluated for Appendix I organics and eight RCRA metals only as they monitor the older, closed-out portion of the landfill. Prior to September 1995, there are data for all Appendix I constituents. These data are reported, however analyses are performed for only the eight RCRA metals.

Upgradient Well (Background Well):

MW16: MW16 is a background well for MW32, MW33, MW34, and MW35 in this analysis. The detected inorganics in MW16 include barium, cadmium, chromium, cobalt, copper, lead, mercury, vanadium, and zinc. Of these, cadmium exceeded NCGS in six sampling events with concentrations of 0.0018, 0.006, 0.007, 0.002, 0.0075, and 0.0049 mg/l in October 1994, January, March, and September 1995, October 1996, and April 1997, respectively. Lead exceeded NCGS in two sampling events with a concentration of 0.02 and 0.039 ug/l in April 1997 and March 1999, respectively. Chromium exceeded NCGS in one sampling event with a concentration of 0.062 ug/l in March 1999. The only detected

organic in MW16 was methylene chloride in January 1995, which exceeded NCGS with a concentration of 29.4 ug/l. No constituents were detected during the latest sampling event.

The following summarizes the history of detected concentrations for each metal constituent in MW16:

barium: Barium was detected in ten sampling events for MW16 with concentrations of 0.112, 0.194, 0.114, 0.147, 0.014, 0.099, 0.1, 0.281, 0.162, and 0.06 mg/l in October and November 1994, January and March 1995, October 1997, April and October 1998, March and October 1999, and April 2000, respectively.

cadmium: Cadmium was detected in eight sampling events for MW16 with concentrations of 0.0018, 0.001, 0.006, 0.007, 0.002, 0.0075, 0.0049, and 0.001 mg/l in October and November 1994, January, March, and September 1995, October 1996, April 1997, and March 1999, respectively.

chromium: Chromium was detected in eight sampling events for MW16 with concentrations of 0.004, 0.007, 0.005, 0.01, 0.019, 0.006, 0.008, 0.062 and 0.019 mg/l in October and November 1994, March, and September 1995, April 1997, April and October 1998, and March and October 1999, respectively.

copper: Copper was detected in four sampling events for MW16 with concentrations of 0.008, 0.009, 0.018, and 0.014 mg/l in October and November 1994 and January and March 1995, respectively.

lead: Lead was detected in ten sampling events for MW16 with concentrations of 0.002, 0.003, 0.004, 0.013, 0.012, 0.020, 0.002, 0.005, 0.039, 0.011, and 0.002 mg/l in October and November 1994, March and September 1995, October 1996, April and October 1997, October 1998, March and October 1999, and April 2000, respectively.

mercury: Mercury was detected in only one sampling event for MW16 with a concentration of 0.0002 mg/l in October 1998.

vanadium: Vanadium was detected in two sampling events for MW16 with concentrations of 0.005 and 0.012 mg/l in October and November 1994.

zinc: Zinc was detected in five sampling events for MW16 with concentrations of 0.012, 0.014, 0.015, 0.027, and 0.07 mg/l in October and November 1994, January and March 1995, and October 1996, respectively.

Downgradient Wells (Compliance Wells):

MW32: Compliance well MW32 has had detections for antimony, arsenic, barium, beryllium, cadmium, chromium, cobalt, copper, lead, nickel, selenium, vanadium, and zinc.

Of these, cadmium exceeded NCGS in two sampling event with concentrations of 0.004 and 0.025 mg/l in November 1994 and October 1998. Chromium exceeded NCGS in two sampling events with concentrations of 0.133 mg/l and 0.094 mg/l in November 1994 and April 2003, respectively. Lead exceeded NCGS in eight sampling events with concentrations of 0.09, 0.02, 0.064, 0.033, 0.063, 0.029, 0.021, and 0.024 mg/l in November 1994, March 1995, March and October 1999, April 2003, April 2005, April 2006, and April 2008, respectively. The only detected organic constituent for MW32 was MEK (2-butanone) with a concentration of 471 ug/l in January 1995. No constituents were detected during the latest sampling event.

MW33: Compliance well MW33 has had detections for barium, beryllium, cadmium, chromium, cobalt, copper, lead, mercury, vanadium, zinc. Of these, cadmium exceeded NCGS in three sampling events with concentrations of 0.0021, 0.003, and 0.005 mg/l in October and November 1994 and January 1995, respectively. Lead exceeded NCGS in two sampling events with concentrations of 0.014 and 0.016 mg/l in January 1995 and October 1998, respectively. Chromium exceeded NCGS in October 1998 with a concentration of 0.016 mg/l. The only detected organic was cis-1,2-dichloroethene, detected in October 1998 with a concentration of 1.8 ug/l. No constituents were detected in MW33 during the latest sampling event.

MW34: This compliance well, installed in June 1996, was sampled for Appendix I organics and the eight RCRA metals in April 1998. Inorganics barium, chromium, lead, and mercury have been detected in MW34. No organics have been detected at this monitoring well. Detections above NCGS include one detect of chromium with a concentration of 0.017 in October 1998 and three detects of lead with concentrations of 0.02, 0.025 and 0.02 mg/l in October 1998, and March and October 1999, respectively. Cadmium was the only detection in MW34 during the latest sampling event.

The following result was obtained for the detected inorganic in MW34 in October 2008:

cadmium: Cadmium resulted as not SSIOBL for MW34 using the Test of Proportions.

MW35: This compliance well, installed in June 1996, was analyzed for Appendix I organics and the eight RCRA metals in April 1998. Inorganics arsenic, barium, cadmium, chromium, lead, mercury and selenium have been detected at MW35. Of these arsenic exceeded NCGS in one sampling event with a concentration of 0.0681 in April 1997. Barium has exceeded NCGS in one sampling event with a concentration of 2.06 mg/l in April 1997. Cadmium has exceeded NCGS in two sampling events with concentrations of 0.0119 and 0.208 mg/l in April and October 1997. Chromium has exceeded NCGS in three sampling events with concentrations of 0.0119, 0.208, and 0.148 mg/l in April and October 1997, and March 1999. Lead has exceeded NCGS in five sampling events with concentrations of 0.355, 0.105, 0.055, 0.110 and 0.043 mg/l in April and October 1997, October 1998, and March and October 1999, respectively. Mercury exceeded NCGS in one sampling event with a concentration of 2.06 mg/l in 0.002 mg/l in April 1997. No organics have been detected in MW35. Barium was the only constituent detected during the latest sampling event.

The following result was obtained for the detected inorganic in MW35 in October 2008:

barium: Barium resulted as not SSIOBL for MW35 using the Test of Proportions.

SET 3: SURFACE WATER MONITORING POINTS

Set 3 surface water monitoring points were sampled, analyzed, and statistically evaluated for Appendix I parameters only.

Upgradient Surface Water Monitoring Point (Background):

SWPT1: SWPT1 is an upgradient surface water monitoring point for SWPT2 and SWPT3. SWPT1 has had detected metal concentrations for arsenic, barium, cadmium, chromium, copper, and zinc. Vanadium exceeded 13B GPS with a concentration of 40 ug/l in October 2008. The only organics detected at SWPT1 were toluene in October 1999 and chloromethane in October 2008. Arsenic, barium, cobalt, lead, vanadium, lead, and chloromethane were detected at SWPT1 during this sampling event.

The following summarizes the detection history at SWPT1:

arsenic: Arsenic was detected in three sampling events for SWPT1 with concentrations of 0.007, 0.013, and 0.047 mg/l in October 1994, September 1995, and October 2008, respectively.

barium: Barium was detected in five sampling events for SWPT1 with concentrations of 0.045, 0.033, 0.03, 0.029, and 0.183 mg/l in October and November 1994, January and March 1995, and October 2008, respectively.

cadmium: Cadmium was detected in two sampling events for SWPT1 with concentrations of 0.001 mg/l in September 1995 and October 2003.

chromium: Chromium was detected in one sampling event for SWPT1 with a concentration of 0.002 mg/l in October 1994.

cobalt: Cobalt was detected in two sampling events for SWPT1 with a concentration of 0.010 and 0.031 mg/l in October 1999 and October 2008, respectively.

copper: Copper was detected in two sampling events for SWPT1 with concentrations of 0.006 and 0.006 mg/l in October 1994 and March 1995, respectively.

lead: Lead was detected in one sampling event for SWPT1 with a concentration of 0.01 mg/l in October 2008.

vanadium: Vanadium was detected in one sampling event for SWPT1 with a concentration of 0.04 mg/l in October 2008.

zinc: Zinc was detected in nine sampling events for SWPT1 with concentrations of 0.011, 0.016, 0.021, 0.013, 0.22, 0.04, 0.011, 0.022, and 0.033 mg/l in October and November 1994, January and March 1995, October 1997, October 1998, May 2007, and April and October 2008, respectively.

chloromethane: Chloromethane was detected in one sampling event for SWPT1 with a concentration of 1.3 ug/l in October 2008.

toluene: Toluene was detected in one sampling event for SWPT1 with a concentration of 1.3 ug/l in October 1999.

Downgradient Surface Water Monitoring Points (Compliance):

SWPT2: SWPT2 is a compliance surface water monitoring point with previously detected metal concentrations for arsenic, barium, cadmium, chromium, copper, lead and zinc. Vanadium detected 13B GPS with a *estimated* concentration of 23.1 ug/l in October 2008. Detected organics include toluene. Arsenic and zinc were the only detected inorganics and toluene was the only detected organic at SWPT2 during this sampling event.

The following result was obtained for the detected inorganic in SWPT2 in October 2008:

arsenic: Arsenic resulted as not SSIOBL for SWPT2 using the Qualitative Test.

zinc: Zinc resulted as not SSIOBL for SWPT2 using the Test of Proportions.

The following result was obtained for the detected organic in SWPT2 in October 2008:

toluene: Toluene resulted as not SSIOBL for SWPT2 using the Qualitative Test.

SWPT3: SWPT3 is a compliance surface water monitoring point with previously detected metal concentrations for arsenic, barium, cadmium, chromium, cobalt, copper, lead and zinc. Of these, cadmium exceeded NCGS in two sampling events with concentrations of 0.0045 and 0.006 mg/l in October 1994 and September 1995. Lead exceeded NCGS in one sampling event with a concentration of 0.02 mg/l in October 1998. Vanadium exceeded 13B GPS with *estimated* values of 3.9 and 13.7 ug/l in April and October 2008, respectively. The previously detected organics for SWPT3 include benzene, cis-1,2-dichloroethene, ethylbenzene, toluene, vinyl chloride, and xylenes. Of these, benzene and vinyl chloride exceeded groundwater standards for the September 1995 sampling event with concentrations of 9.1 and 15 ug/l, respectively. Arsenic, barium and zinc were the only inorganic detections and toluene was the only detected organic at SWPT3 during this sampling event.

The following result was obtained for the detected inorganics in SWPT3 in October 2008:

arsenic: Arsenic resulted as not SSIOBL for SWPT3 using the Qualitative Test.

barium: Barium resulted as not SSIOBL for SWPT3 using the Test of Proportions.

zinc: Zinc resulted as not SSIOBL for SWPT3 using the Test of Proportions.

The following result was obtained for the detected organic in SWPT3 in October 2008:

toluene: Toluene resulted as SSIOBL for SWPT3 using the Qualitative Test.

TABLES

Table 1
Static Water Elevations for
Dunn/Erwin Landfill

Monitor Well	TOC Elevation	Ground Elevation	Screen Elevations		Static Water Elevations							
			Upper	Lower	9/-/86	23-Oct-94	16-Nov-94	10-Jan-95	17-Mar-95	28-Mar-95	27-Apr-95	03-Jun-95
MW1	235.67	234.27	no schematic		-	210.37	211.17	211.97	212.07	210.77	210.67	210.67
MW2	198.01	196.01	181.01	166.01	-	182.01	182.21	182.09	183.67	182.85	181.89	182.01
MW3	182.16	180.16	171.16	161.16	-	175.66	176.36	176.76	176.66	175.91	175.49	176.56
MW3R	181.52	179.44	168.52	158.52	-	-	-	-	-	-	-	-
MW4	178.72	176.12	167.12	157.12	-	173.72	174.12	173.02	175.22	173.82	173.89	175.02
MW5	188.75	186.75	167.75	152.75	-	173.45	173.15	172.75	172.75	172.08	172.25	173.75
MW6	208.60	205.60	no schematic		-	192.20	192.10	192.25	194.65	193.70	193.60	192.60
MW7	218.52	216.12	202.12	192.12	-	193.52	193.22	193.06	195.24	193.27	193.02	-
MW7B	219.33	216.10	204.10	189.10	-	-	-	-	-	-	-	-
MW8	218.71	216.01	207.01	192.01	-	201.01	200.71	200.51	202.56	201.21	201.70	-
MW9	219.43	217.17	202.17	187.17	-	-	-	-	-	-	-	-
MW10	214.54	211.57	203.57	188.57	-	-	-	-	-	-	-	-
MW11	203.41	200.88	188.41	178.41	-	-	-	-	-	-	-	-
MW12	172.48	169.95	162.48	152.48	-	-	-	-	-	-	-	-
MW13	187.39	184.80	154.39	139.39	-	-	-	-	-	-	-	-
MW14	170.91	168.59	162.91	142.91	-	-	-	-	-	-	-	-
MW15	190.18	187.80	183.18	178.18	-	-	-	-	-	-	-	-
MW16	195.61	194.20	188.54	170.54	188.20	192.81	191.91	190.47	189.81	190.61	190.61	191.11
MW23B	169.98	168.37	154.97	144.97	163.00	163.98	164.38	164.77	164.83	164.73	164.73	-
MW31	233.30	231.90	203.20	193.20	212.00	210.80	211.60	211.30	212.80	212.22	210.97	-
MW32	183.84	182.20	148.81	138.81	175.60	174.34	175.64	175.24	176.71	174.34	174.67	-
MW33	173.88	170.90	156.90	146.90	164.20	163.88	163.98	164.65	167.53	-	-	-
MW34**	194.06	191.12	no schematic		-	-	-	-	-	-	-	-
MW35**	181.77	179.31	no schematic		-	-	-	-	-	-	-	-
Averages						185.21	185.43	185.30	186.50	187.13	186.96	185.96

NOTES:

** MW34 and MW35 Ground Elevation and TOC elevation are estimated from the contour map (Fig. 1).

denotes day of highest groundwater level (of total days sampled) for the particular MW

denotes day of lowest groundwater level (of total days sampled) for the particular MW

Well 7B Installed Sept. 1995

MW3R replaced MW3 as of Oct. 2005.

Table 1
Static Water Elevations for
Dunn/Erwin Landfill

Monitor Well	Static Water Elevations											
	07-Jul-95	21-Aug-95	9/13/95**	20-Sep-95	18-Oct-95	09-Feb-96	03-Apr-96	07-Oct-96	15-Apr-97	29-Sep-97	07-Oct-98	23-Mar-99
MW1	215.67	209.92	211.07	209.87	211.37	213.25	212.10	211.10	210.12	210.42	210.56	212.21
MW2	184.01	181.81	181.82	181.91	181.51	183.89	183.07	182.52	182.01	183.71	182.36	183.91
MW3	178.16	175.96	176.05	176.16	175.96	177.25	177.22	177.80	176.03	176.77	176.62	176.91
MW3R	-	-	-	-	-	-	-	-	-	-	-	-
MW4	174.72	173.72	173.70	173.82	173.92	174.81	174.61	174.97	172.91	175.04	174.09	175.47
MW5	173.75	173.15	173.47	173.45	173.55	172.76	172.62	173.85	172.50	173.76	173.55	173.88
MW6	194.60	194.00	193.48	193.30	193.50	193.11	193.21	193.77	193.09	192.45	192.08	192.64
MW7	-	195.42	-	194.62	194.22	-	-	-	-	-	-	-
MW7B	-	-	197.08	194.93	194.53	194.71	195.25	195.64	195.11	193.55	193.78	192.86
MW8	201.31	201.91	201.46	201.36	201.11	201.39	201.68	201.36	201.31	200.97	201.67	202.79
MW9	-	-	-	-	-	-	-	-	-	-	-	-
MW10	-	-	-	-	-	-	-	-	-	-	-	-
MW11	-	-	-	-	-	-	-	-	-	-	-	-
MW12	-	-	-	-	-	-	-	-	-	-	-	-
MW13	-	-	-	-	-	-	-	-	-	-	-	-
MW14	-	-	-	-	-	-	-	-	-	-	-	-
MW15	-	-	-	-	-	-	-	-	-	-	-	-
MW16	191.31	193.01	193.26	183.51	191.61	-	189.96	193.29	190.70	192.79	192.96	190.01
MW23B	165.28	164.48	164.85	164.88	164.60	-	165.40	166.80	164.99	164.92	164.33	164.61
MW31	212.30	210.90	210.59	210.90	211.00	212.51	210.40	213.94	212.84	209.93	210.48	211.00
MW32	176.34	-	175.79	-	176.14	-	176.09	176.46	175.48	176.15	176.09	175.25
MW33	-	-	163.96	163.88	163.68	-	165.63	166.04	164.74	165.62	163.95	165.71
MW34**	-	-	-	-	-	-	-	190.88	188.76	190.93	190.90	189.20
MW35**	-	-	-	-	-	-	-	176.56	176.04	176.58	175.99	172.72
Averages	187.95	188.57	185.89	186.35	186.19	191.52	185.94	186.33	185.11	185.57	185.29	185.28

NOTES:

** MW34 and MW35 Ground Elevation and TOC elevation are estimated from the contour map (Fig. 1).

denotes day of highest groundwater level (of total days sampled) for the particular MW

denotes day of lowest groundwater level (of total days sampled) for the particular MW

Well 7B Installed Sept. 1995

MW3R replaced MW3 as of Oct. 2005.

Table 1
Static Water Elevations for
Dunn/Erwin Landfill

Monitor Well	Static Water Elevations											
	13-Oct-99	20-Apr-00	11-Oct-00	19-Apr-01	15-16-Oct-01	03-Apr-02	15-Oct-02	30-Apr-03	29-Oct-03	21-Apr-04	28-Oct-04	26-Apr-05
MW1	210.50	211.70	210.43	210.41	210.92	211.41	210.83	211.57	211.22	210.99	211.53	211.42
MW2	184.02	183.67	183.69	183.49	183.34	183.62	183.46	183.01	183.25	182.82	183.14	183.52
MW3	177.37	176.85	176.70	176.70	176.95	177.21	177.28	177.84	177.77	177.66	177.88	-
MW3R	-	-	-	-	-	-	-	-	-	-	-	-
MW4	175.78	174.67	174.66	174.54	174.73	175.19	175.57	175.68	175.78	176.98	176.58	174.35
MW5	174.40	172.67	173.90	172.66	174.10	173.14	174.40	173.55	175.15	175.61	176.26	173.18
MW6	193.21	193.05	192.74	192.62	192.70	192.68	192.15	194.11	192.75	192.81	192.95	193.12
MW7	-	-	-	-	-	-	-	-	-	-	-	-
MW7B	193.02	191.46	193.38	192.96	193.87	193.46	192.67	195.73	194.22	194.32	194.44	194.32
MW8	202.77	203.01	209.31	203.09	209.72	203.06	202.65	203.98	203.00	202.96	202.53	202.95
MW9	-	-	-	192.81	193.60	193.21	192.23	195.59	193.78	194.01	194.12	194.09
MW10	-	-	-	193.16	193.28	192.98	192.04	195.54	192.90	193.53	193.65	194.06
MW11	-	-	-	-	-	-	-	-	-	-	-	-
MW12	-	-	-	-	-	-	-	-	-	-	-	-
MW13	-	-	-	-	-	-	-	-	-	-	-	-
MW14	-	-	-	-	-	-	-	-	-	-	-	-
MW15	-	-	-	-	-	-	-	-	-	-	-	-
MW16	192.91	190.49	188.19	186.60	188.28	186.74	188.05	187.78	188.61	187.06	189.07	187.37
MW23B	164.84	164.14	164.67	164.06	164.39	164.46	164.58	164.35	164.18	164.23	163.67	163.94
MW31	211.60	209.98	210.96	210.27	211.21	210.12	210.40	211.03	210.55	209.86	211.30	211.02
MW32	176.75	175.63	181.16	178.28	181.16	178.21	181.12	178.80	181.02	178.31	181.06	180.40
MW33	167.33	165.59	165.59	165.63	164.43	165.20	164.68	166.21	164.08	164.53	164.45	165.65
MW34**	191.34	189.21	191.09	189.03	191.01	189.38	191.41	189.38	190.85	188.92	190.89	189.14
MW35**	176.67	175.84	176.47	175.35	176.35	175.46	176.81	175.67	176.36	176.16	176.42	175.49
Averages	186.17	185.20	186.20	185.98	187.06	186.21	186.49	187.05	186.79	186.52	187.06	187.13

NOTES:

** MW34 and MW35 Ground Elevation and TOC elevation are estimated from the contour map (Fig. 1).

denotes day of highest groundwater level (of total days sampled) for the particular MW

denotes day of lowest groundwater level (of total days sampled) for the particular MW

Well 7B Installed Sept. 1995

MW3R replaced MW3 as of Oct. 2005.

Table 1
Static Water Elevations for Dunn/Erwin Landfill

Monitor Well	Static Water Elevations											
	18-Oct-05	19-Apr-06	10/23-24/06	02-May-07	24-Oct-07	23-Apr-08	######## 5	Min	Max	Ave	Range	Std Dev
MW1	208.53	209.70	209.41	209.64	208.61	209.79	209.76	208.53	215.67	210.89	7.14	1.3
MW2	181.59	182.07	181.99	182.33	179.47	183.19	182.31	179.47	184.02	182.72	4.55	1.0
MW3	-	-	-	-	-	-	-	175.49	178.16	176.82	2.67	0.7
MW3R	177.12	175.64	176.43	175.72	171.57	176.30	176.78	171.57	177.12	175.65	5.55	1.9
MW4	174.45	174.33	174.88	174.39	171.22	174.97	176.16	171.22	176.98	174.62	5.76	1.1
MW5	174.19	172.64	173.98	172.81	171.05	173.29	176.16	171.05	176.26	173.52	5.21	1.1
MW6	191.99	192.50	192.17	191.75	191.84	193.61	192.48	191.75	194.65	192.94	2.90	0.7
MW7	-	-	-	-	-	-	-	193.02	195.42	193.95	2.40	0.9
MW7B	193.02	193.29	193.23	194.32	192.73	193.19	193.45	191.46	197.08	193.95	5.62	1.2
MW8	201.41	202.18	201.95	202.15	201.13	203.23	202.68	200.51	209.72	202.43	9.21	1.9
MW9	192.51	192.89	192.73	194.02	192.21	193.01	193.09	192.21	195.59	193.37	3.38	0.9
MW10	191.95	192.66	191.46	193.70	191.86	194.30	193.08	191.46	195.54	193.13	4.08	1.0
MW11	-	185.43	184.74	184.36	183.89	185.99	184.89	183.89	185.99	184.88		
MW12	-	166.16	165.65	166.23	163.37	166.25	166.59	163.37	166.59	165.71		
MW13	-	162.71	163.71	162.48	162.48	162.60	164.06	162.48	164.06	163.01		
MW14	-	161.61	164.44	163.61	160.85	163.61	164.77	160.85	164.77	163.15		
MW15	-	182.45	178.36	180.58	-	182.70	180.04	178.36	182.70	180.83		
MW16	186.87	186.75	188.36	187.21	187.62	188.23	188.67	183.51	193.29	189.55	9.78	2.4
MW23B	163.67	163.96	163.87	163.70	160.58	163.99	164.29	160.58	166.80	164.35	6.22	0.9
MW31	209.58	209.72	210.45	210.74	208.96	210.35	210.99	208.96	213.94	210.99	4.98	1.0
MW32	180.81	178.01	180.64	178.74	180.63	178.68	180.94	174.34	181.16	177.73	6.82	2.3
MW33	163.66	164.44	163.92	164.98	162.86	167.04	164.55	162.86	167.53	164.92	4.67	1.1
MW34**	190.85	189.13	190.96	189.29	190.97	189.81	191.55	188.76	191.55	190.20	2.79	1.0
MW35**	176.05	175.47	176.40	175.76	175.22	175.96	176.57	172.72	176.81	175.93	4.09	0.8
Averages	185.78	182.44	182.72	182.66	181.39	183.19	183.36	180.77	185.48	183.13	5.15	1.22

Range and Std Dev for wells MW11 - MW15 will be added after more data is available.

Table 1B
Piezometer Static Water Elevations for
Dunn/Erwin Landfill

			Screen Elev.		Average	Date Sampled							
Piez. No.	TOC El.	Grnd. El.	Upper	Lower	Water Level	3/19/1991	3/26/1991	4/12/1991	6/27/1991	3/28/1995	4/27/1995	7/7/1995	8/21/1995
40S	176.17	174.20	163.70	158.80	*168.12*	171.68	171.44	171.38	170.61	ND	ND	ND	168.77
41S	208.58	205.90	192.40	187.40	*192.68*	192.83	192.85	192.89	192.21	194.33	193.48	194.58	192.68
42S	168.05	166.00	152.40	142.50	*162.02*	163.03	162.81	162.32	162.63	163.15	163.30	163.55	164.25
44S	184.20	182.41	172.40	167.10	*179.54*	180.86	180.79	179.20	180.46	179.83	179.70	ND	180.90
45S	202.71	200.10	183.90	178.90	*180.74*	181.26	181.16	181.82	180.54	ND	181.51	ND	180.91
46S	220.77	218.20	197.70	187.70	*194.19*	193.17	194.14	193.23	193.76	195.87	195.27	196.77	195.17
47S	189.89	188.21	178.60	168.60	*181.77*	184.25	183.81	183.46	181.83	184.82	184.39	185.39	180.89
48S	208.27	207.20	195.10	185.10	*195.01*	197.22	197.01	196.85	196.41	197.52	196.52	198.57	196.37
GP-24-W	198.27	193.94	189.94	184.94	*190.36*	ND	ND	ND	ND	ND	ND	ND	ND
GP-25-W	200.69	196.45	191.45	186.45	*191.58*	ND	ND	ND	ND	ND	ND	ND	ND
GP-27-W	207.41	203.01	195.01	185.01	*190.81*	ND	ND	ND	ND	ND	ND	ND	ND
GP-28-W	204.26	199.79	194.79	184.79	*191.88*	ND	ND	ND	ND	ND	ND	ND	ND
GP-30-W	208.76	204.44	198.44	188.44	*192.71*	ND	ND	ND	ND	ND	ND	ND	ND
GP-31-W	199.44	195.24	190.24	185.24	*190.68*	ND	ND	ND	ND	ND	ND	ND	ND
GP-33-W	212.15	207.94	195.94	185.94	*191.92*	ND	ND	ND	ND	ND	ND	ND	ND
GP-34-W	210.15	205.77	197.77	187.77	*192.44*	ND	ND	ND	ND	ND	ND	ND	ND
GP-35-W	193.87	189.65	187.65	182.65	*189.53*	ND	ND	ND	ND	ND	ND	ND	ND
GP-36-W	211.71	207.34	195.34	185.34	*192.18*	ND	ND	ND	ND	ND	ND	ND	ND
GP-37-W	197.28	193.08	188.08	183.08	*188.17*	ND	ND	ND	ND	ND	ND	ND	ND
GP-38-W	215.79	211.09	206.09	196.09	*199.67*	ND	ND	ND	ND	ND	ND	ND	ND
PZ-50	205.53	204.00	195.53	185.53	*190.08*	ND	ND	ND	ND	ND	ND	ND	ND
PZ-51	179.75	177.24	168.75	153.75	*169.14*	ND	ND	ND	ND	ND	ND	ND	ND
PZ-52	198.49	197.00	185.49	175.49	*178.60*	ND	ND	ND	ND	ND	ND	ND	ND
PZ-53	201.27	198.96	186.27	181.27	*183.65*	ND	ND	ND	ND	ND	ND	ND	ND
Average Surficial	*NA*	*NA*	*NA*	*NA*	*185.65*	*183.04*	*183.00*	*182.64*	*182.31*	*185.92*	*184.88*	*187.77*	*182.49*
42D	167.96	165.80	126.60	116.70	*152.77*	148.23	148.08	148.07	147.68	ND	147.96	ND	147.06
44D	184.28	182.61	143.40	133.50	*173.12*	173.13	171.86	171.17	170.30	170.16	170.18	ND	170.48
46D	221.38	218.20	179.20	169.20	*193.09*	ND	ND	ND	ND	193.71	192.88	195.88	194.78
47D	190.10	189.16	145.20	135.20	*162.76*	163.39	161.38	161.13	161.03	ND	165.30	165.50	160.8
Average Deep	*NA*	*NA*	*NA*	*NA*	*173.16*	*161.58*	*160.44*	*160.12*	*159.67*	*181.93*	*169.08*	*180.69*	*168.28*
PB9	211.24		203.60	183.60	*190.31*	190.82	190.40	190.07	189.93	---	---	---	---

NOTE:
- Indicates LOW Water
- Indicates HIGH Water
- ND= No Data
- Range is the difference in high and low water levels for piezometer

Table 1B
Piezometer Static Water Elevations for Dunn/Erwin Landfill

	Date Sampled										
Piez. No.	9/20/1995	10/19/1995	10/5/1998	3/23/1999	10/14/1999	4/20/2000	10/11/2000	4/17/2001	9/13/2001	10/15/2001	4/3/2002
40S	167.57	167.77	156.72	Dry	Dry	Dry	167.11	ND	ND	ND	ND
41S	192.18	194.28	191.13	192.22	193.93	192.76	192.58	ND	ND	ND	ND
42S	164.65	163.85	ND	ND	ND	ND	168.05	154.20	160.44	154.91	157.11
44S	180.3	180.4	172.88	180.95	181.85	181.18	180.01	180.91	181.31	180.67	181.06
45S	179.81	180.01	179.11	180.76	182.63	181.22	179.91	181.03	181.22	180.41	180.82
46S	194.47	193.97	192.15	192.37	196.41	ND	196.09	ND	ND	193.39	192.98
47S	179.49	179.89	180.42	184.53	ND	184.93	182.67	178.85	183.14	182.07	183.84
48S	196.27	196.07	ND	ND	ND	ND	ND	192.63	195.87	195.77	193.55
GP-24-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190.09
GP-25-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190.95
GP-27-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190.10
GP-28-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190.79
GP-30-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	191.61
GP-31-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190.34
GP-33-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190.74
GP-34-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	191.52
GP-35-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	189.35
GP-36-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190.84
GP-37-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	187.98
GP-38-W	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	196.89
PZ-50	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
PZ-51	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
PZ-52	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
PZ-53	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Average Surficial	*181.84*	*182.03*	*178.74*	*186.17*	*188.71*	*185.02*	*180.92*	*177.52*	*180.40*	*181.20*	*187.81*
42D	147.36	147.26	ND	ND	ND	ND	167.96	157.87	160.39	158.37	159.98
44D	171.18	171.28	179.57	173.11	174.02	172.59	174.03	172.17	173.61	174.32	173.55
46D	194.28	194.08	193.4	191.98	192.65	193.33	192.53	191.65	192.83	195.13	192.38
47D	161.10	160.60	162.22	161.64	ND	161.91	162.52	162.19	162.9	163.21	163.13
Average Deep	*168.48*	*168.31*	*178.40*	*175.58*	*183.34*	*175.94*	*174.26*	*170.97*	*172.43*	*172.76*	*172.26*
PB9	---	---	---	---	---	---	---	---	---	---	---

NOTE: Indicates LOW Water
Indicates HIGH Water
ND= No Data
Range is the difference in high and low water levels for piezometer

Table 1B
Piezometer Static Water Elevations for Dunn/Erwin Landfill

	Date Sampled											
Piez. No.	10/15/2002	4/30/2003	10/28/2003	4/21/2004	10/27/2004	4/25/2005	10/17/2005	4/18/2006	10/23/2006	10/23/2006	10/23/2007	4/22/2008
40S	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
41S	ND	194.23	191.58	192.27	192.35	193.22	190.71	191.80	191.58	192.58	190.37	194.38
42S	164.06	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
44S	179.82	ND	179.8	171.66	181.07	181.44	171.66	180.16	179.88	180.91	175.03	181.33
45S	179.11	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
46S	192.00	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
47S	180.63	ND	182.31	178.88	182.44	179.08	176.58	182.58	179.18	183.18	174.92	184.86
48S	195.52	193.46	195.75	185.53	196.17	193.49	194.46	193.06	195.33	193.24	193.72	193.59
GP-24-W	ND	ND	191.11	189.76	191.59	190.04	189.72	190.78	190.57	191.51	189.47	189.73
GP-25-W	ND	192.89	191.81	192.04	192.07	192.33	190.55	191.31	190.95	191.94	189.63	192.84
GP-27-W	ND	ND	190.17	190.89	191.02	192.04	189.33	190.57	190.38	191.38	189.15	193.59
GP-28-W	ND	ND	192.29	192.65	192.58	192.97	190.85	191.76	191.23	192.63	190.17	193.00
GP-30-W	ND	195.21	192.19	192.84	192.95	193.76	190.98	192.16	191.92	193.24	190.84	194.76
GP-31-W	ND	ND	191.33	191.06	191.66	190.32	190.24	191.00	190.60	191.73	189.09	190.21
GP-33-W	ND	194.45	191.75	192.16	192.39	192.81	190.45	191.54	191.18	192.54	190.15	193.15
GP-34-W	ND	ND	192.38	193.04	193.19	193.75	191.11	192.22	191.96	192.33	190.82	194.21
GP-35-W	ND	ND	189.91	189.84	189.90	189.87	189.28	189.65	189.48	189.83	188.17	189.66
GP-36-W	ND	ND	192.25	192.80	192.91	193.35	191.00	191.95	191.70	193.04	190.58	193.52
GP-37-W	ND	188.73	188.17	188.79	188.23	188.66	187.62	188.50	188.01	188.52	185.58	189.09
GP-38-W	ND	200.37	200.19	199.75	199.98	199.79	199.90	199.67	199.91	199.78	199.84	199.73
PZ-50	ND	ND	ND	ND	ND	ND	ND	190.22	189.24	ND	ND	190.77
PZ-51	ND	ND	ND	ND	ND	ND	ND	168.96	169.52	168.33	168.43	169.22
PZ-52	ND	ND	ND	ND	ND	ND	ND	179.22	177.92	178.77	177.47	180.08
PZ-53	ND	ND	ND	ND	ND	ND	ND	183.71	183.28	183.61	182.36	185.02
Average Surficial	*181.86*	*194.19*	*190.81*	*189.62*	*191.28*	*191.06*	*189.03*	*188.54*	*188.19*	*188.90*	*186.62*	*189.64*
42D	152.48	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
44D	174.63	ND	174.82	172.87	175.47	173.57	173.75	173.05	174.63	173.21	172.90	173.19
46D	192.16	ND	193.54	192.82	193.72	192.95	192.19	192.03	192.45	193.07	192.05	192.16
47D	163.45	ND	163.65	163.06	164.16	163.49	163.15	163.22	163.80	163.25	162.13	162.99
Average Deep	*170.68*	*ND*	*177.34*	*176.25*	*177.78*	*176.67*	*176.36*	*176.10*	*176.96*	*176.51*	*175.69*	*176.11*
PB9	---	---	---	---	---	---	---	---	---	---	---	---

NOTE: Indicates LOW Water
Indicates HIGH Water
ND= No Data
Range is the difference in high and low water levels for piezometer

Table 1B
Piezometer Static Water Elevations for Dunn/Erwin Landfill

Piez. No.	4/22/2008	RANGE	MIN	MAX
40S	ND	14.96	156.72	171.68
41S	192.46	4.21	190.37	194.58
42S	ND	13.85	154.20	168.05
44S	180.26	10.19	171.66	181.85
45S	ND	3.52	179.11	182.63
46S	ND	4.77	192.00	196.77
47S	179.75	10.47	174.92	185.39
48S	195.35	13.04	185.53	198.57
GP-24-W	189.91	2.12	189.47	191.59
GP-25-W	191.24	3.26	189.63	192.89
GP-27-W	191.11	4.44	189.15	193.59
GP-28-W	191.63	2.83	190.17	193.00
GP-30-W	192.79	4.37	190.84	195.21
GP-31-W	190.62	2.64	189.09	191.73
GP-33-W	191.69	4.30	190.15	194.45
GP-34-W	192.72	3.39	190.82	194.21
GP-35-W	189.43	1.74	188.17	189.91
GP-36-W	192.24	2.94	190.58	193.52
GP-37-W	188.29	3.51	185.58	189.09
GP-38-W	199.96	3.48	196.89	200.37
PZ-50	ND	1.53	189.24	190.77
PZ-51	170.40	2.07	168.33	170.40
PZ-52	178.12	2.61	177.47	180.08
PZ-53	183.94	2.66	182.36	185.02
Average Surficial	*188.52*			
42D	ND	20.90	147.06	167.96
44D	174.67	9.41	170.16	179.57
46D	192.77	4.23	191.65	195.88
47D	163.64	4.90	160.60	165.50
Average Deep	*177.03*			
PB9	---	0.89	189.93	190.82

NOTE:

Table 1C
Turbidity and Specific Conductivity Measurements
Dunn-Erwin MSW Landfill
Harnett County, North Carolina

	Oct-08			
	Turbidity	Temp.	pH	Conductivity
	NTU	*° C*	*pH*	*uMhos*
MW1	17	18	5.5	58
MW2	11	19	4.5	92
MW3R	90	18	5.5	141
MW4	180	19	4.5	68
MW5	240	18	6.2	175
MW6	170	22	4.5	162
MW7	29.0	20	5.2	234
MW8	<1	21	4.1	122
MW9	16	19	4.6	154
MW10	120	20	5.7	315
MW11	190	20	5.2	33
MW12	100	20	5.1	65
MW13	16	17	6.2	124
MW14	19	19	5.5	119
MW15	26	20	5.5	125
MW16	9.2	20	5.9	170
MW23B	125	20	5.4	48
MW31	380	19	5.4	25
MW32	450	18	5.8	50
MW33	25.0	20	4.8	75
MW34	9.7	20	5.3	79
MW35	29	19	5.4	438
SWPT1	950	19	5.6	109
SWPT2	310	18	6.0	131
SWPT3	320	19	6.1	190

Table 2
Harnett County Dunn-Erwin Landfill
Groundwater Velocity Data

	Shallow Wells							Estimated Velocities* (cm/s)			
	K (cm/sec)*		n values*				i*, Oct. 95	=(1)*i/(3)	=(1)*i/(4)	=(2)*i/(5)	=(2)*i/(6)
MW	Note Ref. (1)	(2)	(3)	(4)	(5)	(6)	(7)	(a)	(b)	(c)	(d)
MW1	7.9E-07	1.0E-03	0.1	0.2	0.3	0.4	3.3E-02	2.6E-07	1.3E-07	1.1E-04	8.3E-05
MW2	3.5E-05	1.0E-03	0.1	0.2	0.3	0.4	4.0E-02	1.4E-05	7.0E-06	1.3E-04	1.0E-04
MW3	1.2E-05	1.0E-03	0.1	0.2	0.3	0.4	8.0E-02	9.2E-06	4.6E-06	2.7E-04	2.0E-04
MW4	1.2E-05	1.0E-03	0.1	0.2	0.3	0.4	8.0E-02	9.9E-06	5.0E-06	2.7E-04	2.0E-04
MW5	4.0E-05	1.0E-03	0.1	0.2	0.3	0.4	1.0E-01	4.0E-05	2.0E-05	3.3E-04	2.5E-04
MW6	3.5E-05	1.0E-03	0.1	0.2	0.3	0.4	8.0E-02	2.8E-05	1.4E-05	2.7E-04	2.0E-04
MW7B	NA	1.0E-03	0.1	0.2	0.3	0.4	1.0E-02	NA	NA	3.3E-05	2.5E-05
MW8	2.0E-06	1.0E-03	0.1	0.2	0.3	0.4	1.3E-02	2.5E-07	1.3E-07	4.2E-05	3.1E-05
MW9	8.6E-04		0.25				1.5E-02	5.2E-05			
MW10	3.0E-06		0.25				1.7E-02	2.0E-07			
MW11	2.5E-05		0.25				4.8E-02	4.8E-06			
MW12	2.3E-05		0.25				4.4E-02	4.0E-06			
MW13	5.5E-06		0.25				6.1E-02	1.3E-06			
MW14	7.4E-07		0.25				6.5E-02	1.9E-07			
MW15	2.2E-05		0.25				2.6E-02	2.3E-06			
MW16	7.3E-08	1.0E-03	0.1	0.2	0.3	0.4	NA	NA	NA	NA	NA
MW23B	2.8E-04	1.0E-03	0.1	0.2	0.3	0.4	2.0E-02	5.6E-05	2.8E-05	6.7E-05	5.0E-05
MW31	3.2E-06	1.0E-03	0.1	0.2	0.3	0.4	2.5E-02	8.0E-07	4.0E-07	8.3E-05	6.3E-05
MW32	2.9E-06	1.0E-03	0.1	0.2	0.3	0.4	NA	NA	NA	NA	NA
MW33	4.1E-06	1.0E-03	0.1	0.2	0.3	0.4	NA	NA	NA	NA	NA
MW34	NA	NA	0.1	0.2	0.3	0.4	NA	NA	NA	NA	NA
MW35	NA	NA	0.1	0.2	0.3	0.4	NA	NA	NA	NA	NA

*** Equation** **V=Ki/n (cm/sec)**

Where V = Mean groundwater velocity as calculated by the above equation
i= Hydraulic gradient (unitless), see note (7)
n = Effective porosity (unitless), see notes (3) through (6)
k = hydraulic conductivity, see notes (1) and (2)

Notes:

NA refers to wells where data is unavailable
(1) In situ hydraulic conductivity as estimated by Withers and Ravenel, "Evaluation of Groundwater Flow and Direction", November 1994
(2) In situ site hydraulic conductivity as estimated for "Field Investigation of Contaminant Plume", October 1996, except
MW9 and MW10 installed in March 2001, for which values are obtained from the Titan report.
MW11 - MW15 calculated by ENSOL, Inc., August 2006 (based on slug tests).
(3) Estimated as the lower limit for effective porosity, n, by Withers and Ravenel, Evaluation of Groundwater Flow and Direction, November 1994
(4) Estimated as the upper limit for effective porosity, n, by Withers and Ravenel, Evaluation of Groundwater Flow and Direction, November 1994
(5) Lower limit of effective porosity estimation in "Field Investigation of Contaminant Plume", October 1996.
(6) Upper limit of effective porosity estimation in "Field Investigation of Contaminant Plume", October 1996.
n=0.25 used for MW11 - MW15, which is average of other values.
(7) Hydraulic gradient as estimated from groundwater contours based on groundwater data sampled in October 1995, except for wells MW11 - MW15, which were estimated from contours based on groundwater data from Jan 2007 - May 2008.

(a) Velocity as estimated using Withers and Ravenel estimated hydraulic conductivity (1), the lower limit for effective porosity (3), and the corresponding hydraulic gradient estimated from Figure 1.

(b) Velocity as estimated using Withers and Ravenel estimated hydraulic conductivity (1), the upper limit for effective porosity (4), and the corresponding hydraulic gradient estimated from Figure 1.

(c) Velocity as estimated using estimated hydraulic conductivity (2), the effective porosity (5), and the corresponding hydraulic gradient estimated from Figure 1.

(d) Velocity as estimated using estimated hydraulic conductivity (2), the effective porosity (6), and the corresponding hydraulic gradient estimated from Figure 1.

(e) For MW9 and MW10 installed in March 2001, velocity was computed for values obtained from the Titan report.

Table 3
Summary of Results of Various Statistical Analyses Detected Inorganics
October 2008

Constituent	Test Set 1[1]	Test Set 2[1]	Test Set 3	Monitoring Wells Indicating SSIOBL	Detected > MDL	Detected > SWSL
Arsenic	Qualitative	Qualitative	Qualitative	None	Yes	Yes
Barium	TOP[2], PIA[5]	TOP[2]	TOP[2]	None	Yes	Yes
Beryllium	TOP[2], PIA[5]	NA[3]	Qualitative	None	Yes	Yes
Cadmium	Qualitative	TOP[2]	Qualitative	None	Yes	Yes
Chromium	TOP[2]	TOP[2]	Qualitative	None	Yes	No
Cobalt	TOP[2], PIA[5]	NA[3]	Qualitative	MW6	Yes	Yes
Copper	TOP[2]	NA[3]	TOP[2]	None	Yes	No
Lead	TOP[2], PIA[5]	TOP[2]	Qualitative	None	Yes	Yes
Mercury	NA[4]	Qualitative	NA[4]	MW6, MW7	Yes	Yes
Nickel	Qualitative	NA[3]	Qualitative	None	Yes	No
Selenium	Qualitative	Qualitative	Qualitative	None	Yes	No
Silver	Qualitative	Qualitative	Qualitative	None	Yes	No
Thallium	NA[7]	NA[7]	NA[7]	NA[7]	Yes	No
Tin	Qualitative	NA[6]	NA[6]	None	Yes	No
Vanadium	TOP[2]	NA[3]	Qualitative	None	Yes	Yes
Zinc	TOP[2]	NA[3]	TOP[2]	None	Yes	Yes

Notes to Table 1:
1 MW23B, a Set 2 well, is statistically compared with Set 1 since it is located downgradient of the Set 1 wells.
2 Those constituents which were tested using the test of proportions were also reviewed qualitatively.
3 These constituents are not included in the 8 RCRA metals sampled for in data Set 2.
4 Mercury is included only in Data Set 2 and only annually in monitoring wells MW6, MW7,7B, and MW8 in Data Set 1.
5 The Prediction Interval Analysis is used when the TOP results are not accurate due to natural, statistically significant variations in concentrations which existed prior to the facility operation commencement.
6 Tin was not included in this sampling event.
7 Thallium was only detected at estimated values below SWSL; estimated values not included in statistical analysis.

Abbreviations
NP ANOVA = Non-Parametric ANOVA
TOP = Test of Proportions
PIA = Prediction Interval Analysis
NA = Not applicable
MDL = Method Detection Limit
SWSL = Solid Waste Section Limit

Table 4A
Summary of Appendices I & II Statistical Analysis Results
October 2008

Monitoring Well	Parameters Indicating SSIOBL	
	Inorganics	Organics
Set 1		
MW1 [1]	NA [1]	NA [1]
MW31 [1]	NA [1]	NA [1]
MW2	none	none
MW3	none	none
MW4	none	none
MW5	none	none
MW6	cobalt, mercury	benzene, chlorobenzene, chloroethane, cis-1,2-Dichloroethylene, 1,4-dichlorobenzene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, 1,1,1-trichloroethane, trichloroethylene, vinyl chloride, xylenes, dichlorodifluoromethane
MW7B	mercury	chloroethane, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, toluene, 1,1,1-trichloroethane, trichloroethylene, trichlorofluoromethane, vinyl chloride, xylenes, dichlorodifluoromethane
MW8	none	chloroethane, chloromethane, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene
MW9	none	benzene, chloroethane, cis-1,2-Dichloroethylene, 1,1-dichloroethane, methylene chloride, trichloroethylene, vinyl chloride, xylenes
MW10	none	chloroethane, cis-1,2-Dichloroethylene, 1,1-dichloroethane, methylene chloride, tetrachloroethylene, trichloroethylene, xylenes
MW23B [2]	none	none
Set 2 [3]		
MW16 [1]	NA [1]	NA [1]
MW32	none	none
MW33	none	none
MW34	none	none
MW35	none	none
Set 3 [3]		
SWPT1 [1]	NA [1]	NA [1]
SWPT2	none	none
SWPT3	none	toluene

1. NA indicates Not Applicable. These are upgradient wells or surface water points.
2. MW23B, a set 2 well, is statistically compared with Set 1 as it is located downgradient of the active landfill.
3. Set 2 was sampled, analyzed, and evaluated for Appendix I organics plus the eight (8) RCRA metals only. Set 3 was sampled, analyzed, and evaluated for Appendix I parameters only.

Table 4B
Notification Table
NC Groundwater Exceedances
Dunn-Erwin Landfill
Harnett County, North Carolina
October 2008

Constituent	2L STD	13B STD	SWSL	MW31	MW2	MW3	MW4	MW5	MW6	MW7B	MW8	MW9	MW10	MW11	SWPT1	SWPT2	SWPT3	Notes
Inorganics																		
Beryllium	NE	4	1				6											Not SSIOBL, background
Lead	15	--	10							19								Not SSIOBL, background
Thallium	NE	0.28	5.5							*2.8*								Probable trace background
Vanadium	NE	3.5	25	*19.9*	*3.6*	*4.3*		*4.0*	*5.5*					*6.2*	40	*23.1*	*13.7*	Not SSIOBL, background
Mercury	1.05	--	0.2									1.5						Previously found in plume area
Organics																		
Benzene	1	--	1						4.9	5.8	2.9	8	3.9					MW6 - MW10 are located within previously identified contaminant plume. This area is included in pending corrective action.
1,4-Dichlorobenzene	1.4	--	1						5	1.7	1.5	2.1						
1,2-Dichloroethane	0.38	--	1							*0.4*								
Methylene chloride	4.6	--	1						9	69	48	64.6						
Tetrachloroethylene	0.7	--	1						3.8	3.7	4.7	2.4						
Trichloroethylene	2.8	--	1						4.9	8.8	4.8	4.2						
Vinyl chloride	0.015	--	1						10.8	8.2	1.5	8.7	3.3					
1,1,2,2-Tetrachloroethane	NE	0.18	3							*1*								

NE = Not Established
All units are in (ug/L) unless noted.
Values in italics are estimated.
Only wells with exceedances shown.
Only values > 2L or 13B STD shown.

Table 6
Comparison of Standards, SWSL, Current and Historic Detection Limits
For selected Constituents
Dunn-Erwin Landfill
Harnett County, North Carolina
Oct-08

Constituent	2L STD	13B STD	SWSL	2008 MDL	2006 DL
Inorganics					
Antimony	NE	1.4	6	0.08	30
Arsenic	50	--	10	0.07	10
Barium	2000	--	100	0.11	500
Beryllium	NE	4	1	0.06	2
Cadmium	1.75	--	1	0.04	1
Chromium	50	--	10	0.11	10
Cobalt	NE	70	10	0.03	10
Copper	1000	--	10	0.05	200
Lead	15	--	10	0.04	10
Nickel	100	--	50	0.06	50
Selenium	50	--	10	0.14	20
Silver	17.5	--	10	0.04	10
Thallium	NE	0.28	5.5	0.04	10
Vanadium	NE	3.5	25	0.07	40
Zinc	1050	--	10	0.04	50
Cyanide	70	--	10	NA	50
Mercury	1.05	--	0.2	NA	1
Tin	NE	NE	100	NA	100
Organics					
Acetone	700	--	100	1.21	100
Benzene	1	--	1	0.16	5
Carbon disulfide	700	--	100	0.14	100
Chlorobenzene	50	--	3	0.13	5
Chloroethane	2800	--	10	0.29	10
Methyl chloride	2.6	--	1	0.18	10
1,2-Dibromoethane	0.0004	--	1	0.13	5
1,4-Dichlorobenzene	1.4	--	1	0.21	5
cis-1,2-Dichloroethene	70	--	5	0.14	5
1,1-Dichloroethane	70	--	5	0.16	5
1,2-Dichloroethane	0.38	--	1	0.12	5
1,1-Dichloroethene	7	--	5	0.14	5
Methylene chloride	4.6	--	1	0.14	10
Tetrachloroethylene	0.7	--	1	0.16	5
Toluene	1000	--	1	0.13	5
1,1,1-Trichloroethane	200	--	1	0.11	5
Trichloroethylene	2.8	--	1	0.13	5
Trichlorofluoromethane	2100	--	1	0.13	5
Vinyl chloride	0.015	--	1	0.34	10
Xylenes (total)	530	--	5	0.48	5

NE = Not Established
All units are in (ug/L) unless noted.

FIGURES

LEGEND

- 210 — EXISTING CONTOURS
- 190 — AVERAGE GRONDWATER CONTOURS
- LIMITS OF WASTE
- GP 21 — GEOPROBE BORING (NO WELL INSTALLED)
- GP 30W — GEOPROBE WELL
- PZ 46S — EXISTING PIEZOMETER
- MW 9 — EXISTING MONITORING WELL



NOTE

AVERAGE GROUNDWATER CONTOURS GENERATED FROM DATA COLLECTED FROM JAN. 07 – MAY 08

GRAPHIC SCALE

200 100 0 200 400

(IN FEET)

Clayton, Sr., P.E., Inc.
CIVIL & ENVIRONMENTAL ENGINEERING
POST OFFICE BOX 579
COATS, NORTH CAROLINA 27521
PHONE 910-897-7070 FAX: 910-897-5757
MOBILE: 919 795-6302 (Tyron) Email: tyron@clayton.com

DUNN-ERWIN LANDFILL CORRECTIVE ACTION PLAN

HARNETT COUNTY, NC.

Date: 12/09/2008	Sheet Title: TREATMENT BARRIER EXHIBIT MAP
Project #: 03002B	
Drawn By: SBK	Scale: 1" = 200'
Designed By: CTC JR.	Proj. Eng.: RS
Checked By: RS	File Name: 03002BMAS081202
Sheet: 1	

SURFACE WATER SAMPLING LOCATION #1
MW-2
MW-3R
MW-4
MW-5
MW-1
CLOSED MSW ACTIVE C&D
MW-31
GP 30-V
MW 8
MW 73
MW-6
MW-16
SURFACE WATER SAMPLING LOCATION #2
PZ 46S
PZ 46D
MW 9
PZT 9-1
PZT 9-2
MW 10
PZT 10-1
PZT 10-2
GP 34-V
PZ 41S
PZ-50
GP 30-V
GP 29-V
GP 25-V
GP 36-V
GP 27-V
PZ 40S ESTIMATED
PZ-51
GP 33-V
GP 31-V
GP 35-V
GP 24-V
GP 37-V
PZ 48S
PZ 47S
PZ 47D
MW-11
PROPOSED C&D LANDFILL
PZ-53
MW-12
MW 35
MW-15
PZ 44S
PZ 44D
PZ 43 ESTIMATED
MW-13
PZ-52
MW-14
MW 23
PZ 42S
MATCH LINE
SURFACE WATER SAMPLING LOCATION #3
LEGEND
GP 23-W GEOPROBE WELL
PZ 46S EXISTING PIEZOMETER
MW 9 EXISTING MONITORING WELL
SURFACE WATER SAMPLING LOCATION
Clayton, Sr., P.E., Inc.
C.T. Clayton, Sr., Professional Engineer
PO BOX 12794
NEW BERN, NC 28561
Phone: 252 672-0304
Home Fax: 910 687-0860
Mobile: 252 671-6079
Fax: 252 672-0577
LAYOUT of DUNN-ERWIN LANDFILL FIGURE 2A
HARNETT COUNTY NORTH CAROLINA
PROJECT # : 0003002
PROJ. ENG. : CTC
DRAWN BY : CTC Jr.
FIELD FILE : CJP
CAD FILE : DELF Plume 2004.dwg
SCALE : 1" = 300'
DATE : APRIL 4, 2006
SHEET # : 1 OF 1
DATE
P:\03 Harnett County\03002 Dunn Erwin\CAD\03002\kwp\03002MAS.dwg, Nov 03, 2006, 5:34pm

PROJECT # : 003002
PROJ. ENG. : CTC
DRAWN BY : CTC Jr.
FIELD FILE : CJP
CAD FILE : DELF Plume 2004.dwg

SCALE : 1" = 300'
DATE : APRIL 4, 2006

SHEET # : FIGURE 2B

LAYOUT
of
DUNN-ERWIN LANDFILL
FIGURE 2B

HARNETT COUNTY NORTH CAROLINA

Clayton, Sr., P.E., Inc.
C.T. Clayton, Sr., Professional Engineer
PO BOX 12794
NEW BERN, NC 28561
Phone: 252 672-0304
Home Fax: 910 897-0060
Mobile: 252 671-6979
Fax: 252 672-8577

DATE

\\FileServer\Projects\003 Harnett County\003002 Dunn Erwin\CAD\003002\dwg\003002MAS.dwg Oct 31, 2006 4:33pm

Figure 3

Top Six, NCGS-Normalized Average Organics Concentrations per Sampling Event
Averages for Select Downgradient Wells (Contaminant Plume Area)
MW6, MW7B, MW8, MW9, MW10
Dunn-Erwin Landfill, Harnett County



APPENDIX A

DATA SET 1

Recommended Test Per Constituent
Total Detects and Percentages
Set 1 Data
Dunn-Erwin MSW Landfill
Harnett County, NC

CONSTITUENT	SET 1 DATA		RECOMMENDED TEST
	Detect #	Detect %	
INORGANICS (mg/l)			
Antimony	0	0%	QUALITATIVE
Arsenic	18	5%	QUALITATIVE
Barium	87	25%	TEST OF PROPORTIONS*
Beryllium	106	32%	TEST OF PROPORTIONS*
Cadmium	31	9%	QUALATATIVE
Chromium	69	19%	TEST OF PROPORTIONS*
Cobalt	53	16%	TEST OF PROPORTIONS*
Copper	49	15%	TEST OF PROPORTIONS*
Lead	91	26%	TEST OF PROPORTIONS*
Nickel	8	2%	QUALITATIVE
Selenium	1	0%	QUALITATIVE
Silver	1	0%	QUALITATIVE
Vanadium	42	13%	TEST OF PROPORTIONS*
Zinc	93	28%	TEST OF PROPORTIONS*
t-Cyanide**	1	1%	QUALITATIVE
Mercury**	24	22%	TEST OF PROPORTIONS*
Tin**	4	5%	QUALITATIVE
ORGANICS (ug/l)			
Acetone	5	1%	QUALITATIVE
Benzene	35	10%	QUALITATIVE
Carbon Disulfide	9	3%	QUALITATIVE
Chlorobenzene	33	9%	QUALITATIVE
Chloroethane	82	23%	TEST OF PROPORTIONS*
Chloromethane	6	2%	QUALITATIVE
1,2-Dibromoethane	1	0%	QUALITATIVE
1,4-Dichlorobenzene	16	4%	QUALITATIVE
cis-1,2-Dichloroethene	39	11%	TEST OF PROPORTIONS*
1,1-Dichloroethane	112	31%	TEST OF PROPORTIONS*
1,2-Dichloroethane	2	1%	QUALITATIVE
1,1-Dichloroethene	23	6%	QUALITATIVE
Methylene Chloride	96	27%	TEST OF PROPORTIONS*
Tetrachloroethylene	34	10%	QUALITATIVE
Toluene	8	2%	QUALITATIVE
1,1,1-Trichloroethane	26	7%	QUALITATIVE
Trichloroethylene	69	19%	TEST OF PROPORTIONS*
Trichlorofluoromethane	15	4%	QUALITATIVE
Vinyl Chloride	20	6%	QUALITATIVE
Xylenes	42	12%	TEST OF PROPORTIONS*
Dichlorodifluoromethane**	28	23%	TEST OF PROPORTIONS*
Diethyphthalate**	7	6%	QUALITATIVE
bis(2-ethylhexyl)phthalate**	2	2%	QUALITATIVE

NOTES:

* The Test of Proportions may be performed jointly with a qualitative test to ensure more accurate results.

** These constituents are Appendix II constituents which were analyzed for the first time in September 1995.

Groundwater Monitoring Well Data
Monitoring Well 1 (MW1)
Upgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW1																		
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																			
Antimony						NA	NA		NA										
Arsenic						NA	NA		NA										
Barium	0.252	0.024	1.68	0.586		NA	NA		NA			0.083		0.1					
Beryllium			0.024	0.006	0.002	NA	NA	0.002	NA	0.003	0.006	0.001	0.004	0.003		0.002			
Cadmium	0.0008	0.001	0.004	0.001		NA	NA		NA										
Chromium	0.005		0.018	0.011		NA	NA		NA		0.013		0.02						
Cobalt			0.016			NA	NA		NA										
Copper	0.017		0.078	0.018		NA	NA		NA			0.007							
Lead	0.005		0.104	0.104	0.02	NA	NA		NA		0.028	0.018							
Nickel			0.03			NA	NA		NA										
Selenium						NA	NA		NA										
Silver						NA	NA		NA										
Vanadium	0.02		0.083			NA	NA		NA										
Zinc	0.098	0.012	0.237	0.038	0.08	NA	NA		NA		0.0647								
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Tin*	NA	NA	NA	NA		NA	NA		NA		NA	0.1	NA		NA		NA	NA	NA
ORGANICS (ug/l)																			
Acetone						NA	NA		NA										
Benzene						NA	NA		NA										
Carbon Disulfide		20.9				NA	NA		NA							7.4			
Chlorobenzene						NA	NA		NA										
Chloroethane						NA	NA		NA										
Chloromethane						NA	NA		NA										
1,2-Dibromoethane						NA	NA		NA										
1,4-Dichlorobenzene						NA	NA		NA										
cis-1,2-Dichloroethene						NA	NA		NA										
1,1-Dichloroethane						NA	NA		NA										
1,2-Dichloroethane						NA	NA		NA										
1,1-Dichloroethene						NA	NA		NA										
Methylene Chloride						NA	NA		NA										
Tetrachloroethylene						NA	NA		NA										
Toluene						NA	NA		NA										
1,1,1-Trichloroethane						NA	NA		NA										
Trichloroethylene						NA	NA		NA										
Trichloroflouromethane						NA	NA		NA										
Vinyl Chloride						NA	NA		NA										
Xylenes						NA	NA		NA										
Dichlorodifluoromethane*	NA	NA	NA	NA									NA		NA		NA	NA	NA
Diethyphthalate*	NA	NA	NA	NA	5.3			5.3			9.8		NA		NA		NA	NA	NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA
		- indicates concentrations exceeding NCGS																	
	"NE"	- not established																	
	"NA"	- not applicable																	
	*	-denotes an Appendix II constituent not included in Appendix I																	

Groundwater Monitoring Well Data
Monitoring Well 1 (MW1)
Upgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT																MW1 detects		NCGS
SAMPLING DATES	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony																0	0%	0.0014**
Arsenic																0	0%	0.05
Barium																6	19%	2
Beryllium		0.002														11	35%	0.004**
Cadmium																4	13%	0.00175
Chromium																5	16%	0.05
Cobalt																1	3%	0.07**
Copper																4	13%	1
Lead																6	19%	0.015
Nickel																1	3%	0.1
Selenium																0	0%	0.05
Silver																0	0%	0.0175
Vanadium																2	6%	0.0035**
Zinc						0.08						0.011				8	26%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.07
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1	17%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone																0	0%	700
Benzene																0	0%	1
Carbon Disulfide																2	6%	700
Chlorobenzene																0	0%	50
Chloroethane																0	0%	2800
Chloromethane																0	0%	2.6
1,2-Dibromoethane																0	0%	0.0004
1,4-Dichlorobenzene																0	0%	1.4
cis-1,2-Dichloroethene																0	0%	70
1,1-Dichloroethane																0	0%	70
1,2-Dichloroethane																0	0%	0.38
1,1-Dichloroethene																0	0%	7
Methylene Chloride																0	0%	4.6
Tetrachloroethylene																0	0%	0.7
Toluene																0	0%	1000
1,1,1-Trichloroethane																0	0%	200
Trichloroethylene																0	0%	2.8
Trichloroflouromethane																0	0%	2100
Vinyl Chloride																0	0%	0.015
Xylenes																0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	3	30%	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE

NCGS = 2L STD or

** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 31 (MW31)
Upgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW31																		
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																			
Antimony						NA	NA		NA										
Arsenic				0.005	0.055	NA	NA	0.011	NA		0.032	0.005							
Barium	0.04		0.157	0.097		NA	NA		NA			0.098			0.1				
Beryllium		0.028			0.006	NA	NA		NA		0.003	0.001			0.002	0.005			
Cadmium			0.005	0.003	0.003	NA	NA		NA		0.0013								
Chromium	0.021	0.015	0.021		0.21	NA	NA	0.044	NA		0.124	0.060		0.04	0.08	0.1	0.01		
Cobalt			0.007		0.02	NA	NA		NA										
Copper	0.017	0.012	0.095	0.04	0.22	NA	NA	0.033	NA			0.043		0.06	0.07				
Lead	0.011	0.006	0.052	0.033	0.17	NA	NA	0.031	NA		0.088	0.045		0.03	0.05	0.06			
Nickel						NA	NA		NA										
Selenium						NA	NA		NA										
Silver						NA	NA		NA										
Vanadium	0.045	0.026	0.032	0.08	0.41	NA	NA	0.087	NA		0.235	0.11		0.04	0.13				
Zinc	0.017	0.01	0.027	0.037	0.07	NA	NA		NA			0.05		0.04	0.04	0.1			
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Tin*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
ORGANICS (ug/l)																			
Acetone						NA	NA		NA										
Benzene						NA	NA		NA										
Carbon Disulfide						NA	NA		NA										
Chlorobenzene						NA	NA		NA										
Chloroethane						NA	NA		NA										
Chloromethane						NA	NA		NA										
1,2-Dibromoethane						NA	NA		NA										
1,4-Dichlorobenzene						NA	NA		NA										
cis-1,2-Dichloroethene						NA	NA		NA										
1,1-Dichloroethane						NA	NA		NA										
1,2-Dichloroethane						NA	NA		NA										
1,1-Dichloroethene						NA	NA		NA										
Methylene Chloride						NA	NA		NA										
Tetrachloroethylene						NA	NA		NA										
Toluene						NA	NA		NA										
1,1,1-Trichloroethane						NA	NA		NA										
Trichloroethylene						NA	NA		NA										
Trichloroflouromethane						NA	NA		NA										
Vinyl Chloride						NA	NA		NA										
Xylenes						NA	NA		NA										
Dichlorodifluoromethane*	NA	NA	NA	NA									NA		NA		NA	NA	NA
Diethyphthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 31 (MW31)
Upgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT																MW31 Detects		NCGS
SAMPLING DATES	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony																0	0%	0.0014**
Arsenic																5	16%	0.05
Barium																5	16%	2
Beryllium																6	19%	0.004**
Cadmium																4	13%	0.00175
Chromium																11	35%	0.05
Cobalt																2	6%	0.07**
Copper																9	29%	1
Lead														0.014	0.013	13	42%	0.015
Nickel																0	0%	0.1
Selenium																0	0%	0.05
Silver																0	0%	0.0175
Vanadium																10	32%	0.0035**
Zinc												0.017		0.01		11	35%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.07
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone																0	0%	700
Benzene																0	0%	1
Carbon Disulfide																0	0%	700
Chlorobenzene																0	0%	50
Chloroethane																0	0%	2800
Chloromethane																0	0%	2.6
1,2-Dibromoethane																0	0%	0.0004
1,4-Dichlorobenzene																0	0%	1.4
cis-1,2-Dichloroethene																0	0%	70
1,1-Dichloroethane																0	0%	70
1,2-Dichloroethane																0	0%	0.38
1,1-Dichloroethene																0	0%	7
Methylene Chloride																0	0%	4.6
Tetrachloroethylene																0	0%	0.7
Toluene																0	0%	1000
1,1,1-Trichloroethane																0	0%	200
Trichloroethylene																0	0%	2.8
Trichloroflouromethane																0	0%	2100
Vinyl Chloride																0	0%	0.015
Xylenes																0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 2 (MW2)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW2																		
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																			
Antimony						NA	NA		NA										
Arsenic				0.005	0.033	NA	NA		NA										
Barium	0.143	0.404	0.489	0.469	0.82	NA	NA		NA			0.05		0.1					
Beryllium			0.012	0.035		NA	NA	0.004	NA	0.005	0.005	0.002	0.004	0.003		0.008	0.002		0.002
Cadmium		0.001	0.001	0.003	0.004	NA	NA		NA										
Chromium	0.006	0.033		0.02	0.02	NA	NA		NA		0.0117					0.01			
Cobalt		0.009		0.01	0.07	NA	NA		NA										
Copper	0.027	0.046	0.037	0.041		NA	NA		NA			0.008							
Lead	0.006	0.025	0.025	0.041	0.025	NA	NA		NA		0.0148	0.004				0.01			
Nickel		0.02		0.01		NA	NA		NA										
Selenium						NA	NA		NA										
Silver						NA	NA		NA										
Vanadium	0.24		0.022	0.07	0.05	NA	NA		NA										
Zinc	0.037	0.026	0.096	0.104	0.05	NA	NA		NA	0.102		0.023				0.06			
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA	0.0008	NA		NA		NA	NA	NA
Tin*	NA	NA	NA	NA		NA	NA		NA		NA	0.1	NA		NA		NA	NA	NA
ORGANICS (ug/l)																			
Acetone						NA	NA		NA										
Benzene						NA	NA		NA										
Carbon Disulfide						NA	NA		NA										
Chlorobenzene						NA	NA		NA										
Chloroethane						NA	NA		NA										
Chloromethane						NA	NA		NA										
1,2-Dibromoethane						NA	NA		NA										
1,4-Dichlorobenzene						NA	NA		NA										
cis-1,2-Dichloroethene						NA	NA		NA										
1,1-Dichloroethane						NA	NA		NA										
1,2-Dichloroethane						NA	NA		NA										
1,1-Dichloroethene						NA	NA		NA										
Methylene Chloride						NA	NA		NA										
Tetrachloroethylene						NA	NA		NA										
Toluene						NA	NA		NA										
1,1,1-Trichloroethane						NA	NA		NA										
Trichloroethylene						NA	NA		NA										
Trichloroflouromethane						NA	NA		NA										
Vinyl Chloride						NA	NA		NA										
Xylenes						NA	NA		NA										
Dichlorodifluoromethane*	NA	NA	NA	NA									NA		NA		NA	NA	NA
Diethyphthalate*	NA	NA	NA	NA	13								NA		NA		NA	NA	NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA
		- indicates concentrations exceeding NCGS																	
	"NE"	- not established																	
	"NA"	- not applicable																	
	*	-denotes an Appendix II constituent not included in Appendix I																	

Groundwater Monitoring Well Data
Monitoring Well 2 (MW2)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT																MW2 Detects		NCGS
SAMPLING DATES	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony																0	0%	0.0014**
Arsenic																2	6%	0.05
Barium																7	23%	2
Beryllium	0.002	0.002		0.004		0.002	0.003					0.002	0.0015	0.002	0.002	20	65%	0.004**
Cadmium																4	13%	0.00175
Chromium																6	19%	0.05
Cobalt																3	10%	0.07**
Copper																5	16%	1
Lead																8	26%	0.015
Nickel																2	6%	0.1
Selenium																0	0%	0.05
Silver																0	0%	0.0175
Vanadium																4	13%	0.0035**
Zinc												0.013		0.012		10	32%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.07
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1	17%	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1	17%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone																0	0%	700
Benzene																0	0%	1
Carbon Disulfide																0	0%	700
Chlorobenzene																0	0%	50
Chloroethane																0	0%	2800
Chloromethane																0	0%	2.6
1,2-Dibromoethane																0	0%	0.0004
1,4-Dichlorobenzene																0	0%	1.4
cis-1,2-Dichloroethene																0	0%	70
1,1-Dichloroethane																0	0%	70
1,2-Dichloroethane																0	0%	0.38
1,1-Dichloroethene																0	0%	7
Methylene Chloride																0	0%	4.6
Tetrachloroethylene																0	0%	0.7
Toluene																0	0%	1000
1,1,1-Trichloroethane																0	0%	200
Trichloroethylene																0	0%	2.8
Trichloroflouromethane																0	0%	2100
Vinyl Chloride																0	0%	0.015
Xylenes																0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1	10%	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 3 (MW3)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW3																		
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																			
Antimony						NA	NA		NA										
Arsenic						NA	NA		NA										
Barium	0.095	0.174	0.083	0.061		NA	NA		NA			0.062			0.1				
Beryllium		0.004	0.08	0.007	0.007	NA	NA	0.007	NA	0.011	0.009	0.004	0.005	0.005	0.011	0.008	0.004	0.005	0.006
Cadmium		0.002	0.001	0.011		NA	NA		NA										
Chromium	0.005			0.003		NA	NA		NA							0.01			
Cobalt		0.005	0.012			NA	NA		NA										
Copper				0.006		NA	NA		NA			0.006							
Lead	0.006					NA	NA		NA			0.003				0.01			
Nickel						NA	NA		NA										
Selenium						NA	NA		NA										
Silver						NA	NA		NA										
Vanadium	0.009			0.07		NA	NA		NA										
Zinc	0.023	0.039	0.018	0.018	0.06	NA	NA		NA			0.03				0.05			
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Tin*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
ORGANICS (ug/l)																			
Acetone						NA	NA		NA										
Benzene						NA	NA		NA										
Carbon Disulfide		64.4				NA	NA		NA										
Chlorobenzene						NA	NA		NA										
Chloroethane						NA	NA		NA										
Chloromethane						NA	NA		NA										
1,2-Dibromoethane						NA	NA		NA										
1,4-Dichlorobenzene						NA	NA		NA										
cis-1,2-Dichloroethene						NA	NA		NA										
1,1-Dichloroethane						NA	NA		NA										
1,2-Dichloroethane						NA	NA		NA										
1,1-Dichloroethene						NA	NA		NA										
Methylene Chloride						NA	NA		NA										
Tetrachloroethylene						NA	NA		NA										
Toluene						NA	NA		NA										
1,1,1-Trichloroethane						NA	NA		NA										
Trichloroethylene						NA	NA		NA										
Trichloroflouromethane						NA	NA		NA										
Vinyl Chloride						NA	NA		NA										
Xylenes						NA	NA		NA										
Dichlorodifluoromethane*	NA	NA	NA	NA									NA		NA		NA	NA	NA
Diethyphthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA
		- indicates concentrations exceeding NCGS																	
	"NE"	- not established																	
	"NA"	- not applicable																	
	*	-denotes an Appendix II constituent not included in Appendix I																	

Groundwater Monitoring Well Data
Monitoring Well 3 (MW3)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT									MW3R							MW3 Detects		NCGS
SAMPLING DATES	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony								NA								0	0%	0.0014**
Arsenic								NA								0	0%	0.05
Barium								NA							0.124	7	23%	2
Beryllium	0.005	0.005	0.005	0.005	0.005	0.005	0.006	NA						0.001	0.002	24	80%	0.004**
Cadmium								NA								3	10%	0.00175
Chromium		0.014						NA								4	13%	0.05
Cobalt								NA								2	7%	0.07**
Copper								NA								2	7%	1
Lead								NA								3	10%	0.015
Nickel								NA								0	0%	0.1
Selenium								NA								0	0%	0.05
Silver								NA								0	0%	0.0175
Vanadium								NA								2	7%	0.0035**
Zinc								NA				0.015		0.014	0.022	10	33%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.07
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone								NA								0	0%	700
Benzene								NA								0	0%	1
Carbon Disulfide								NA								1	3%	700
Chlorobenzene								NA								0	0%	50
Chloroethane								NA								0	0%	2800
Chloromethane								NA								0	0%	2.6
1,2-Dibromoethane								NA								0	0%	0.0004
1,4-Dichlorobenzene								NA								0	0%	1.4
cis-1,2-Dichloroethene								NA								0	0%	70
1,1-Dichloroethane								NA								0	0%	70
1,2-Dichloroethane								NA								0	0%	0.38
1,1-Dichloroethene								NA								0	0%	7
Methylene Chloride								NA								0	0%	4.6
Tetrachloroethylene								NA								0	0%	0.7
Toluene								NA								0	0%	1000
1,1,1-Trichloroethane								NA								0	0%	200
Trichloroethylene								NA								0	0%	2.8
Trichloroflouromethane								NA								0	0%	2100
Vinyl Chloride								NA								0	0%	0.015
Xylenes								NA								0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 5 (MW5)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW5																		
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																			
Antimony						NA	NA		NA										
Arsenic						NA	NA		NA								0.02		
Barium	0.208	0.142	0.243	0.104		NA	NA		NA			0.127	0.1	0.2	0.2				
Beryllium						NA	NA		NA	0.002				0.002	0.003	0.006			
Cadmium			0.001			NA	NA	0.001	NA										
Chromium	0.009					NA	NA		NA										
Cobalt						NA	NA		NA										
Copper	0.017	0.006	0.007	0.006		NA	NA		NA										
Lead	0.008	0.002	0.008			NA	NA		NA			0.002							
Nickel				0.08		NA	NA		NA										
Selenium						NA	NA		NA										
Silver						NA	NA		NA										
Vanadium	0.006					NA	NA		NA										
Zinc	0.027	0.019	0.026	0.01		NA	NA		NA			0.019							
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
Tin*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA	NA	NA
ORGANICS (ug/l)																			
Acetone						NA	NA		NA										
Benzene						NA	NA		NA										
Carbon Disulfide		30.5				NA	NA		NA							6.8			
Chlorobenzene						NA	NA		NA										
Chloroethane						NA	NA		NA										
Chloromethane						NA	NA		NA										
1,2-Dibromoethane						NA	NA		NA										
1,4-Dichlorobenzene						NA	NA		NA										
cis-1,2-Dichloroethene						NA	NA		NA										
1,1-Dichloroethane						NA	NA		NA										
1,2-Dichloroethane						NA	NA		NA										
1,1-Dichloroethene						NA	NA		NA										
Methylene Chloride						NA	NA		NA										
Tetrachloroethylene						NA	NA		NA										
Toluene						NA	NA		NA										
1,1,1-Trichloroethane						NA	NA		NA										
Trichloroethylene						NA	NA		NA										
Trichloroflouromethane						NA	NA		NA										
Vinyl Chloride						NA	NA		NA										
Xylenes						NA	NA		NA										
Dichlorodifluoromethane*	NA	NA	NA	NA									NA		NA		NA	NA	NA
Diethyphthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA									NA		NA		NA	NA	NA
		- indicates concentrations exceeding NCGS																	
	"NE"	- not established																	
	"NA"	- not applicable																	
	*	-denotes an Appendix II constituent not included in Appendix I																	

Groundwater Monitoring Well Data
Monitoring Well 5 (MW5)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT																MW5 Detects		NCGS
SAMPLING DATES	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony																0	0%	0.0014**
Arsenic																1	3%	0.05
Barium												0.112	0.103		0.197	11	35%	2
Beryllium															0.003	5	16%	0.004**
Cadmium																2	6%	0.00175
Chromium																1	3%	0.05
Cobalt																0	0%	0.07**
Copper																4	13%	1
Lead																4	13%	0.015
Nickel																1	3%	0.1
Selenium																0	0%	0.05
Silver																0	0%	0.0175
Vanadium																1	3%	0.0035**
Zinc															0.014	6	19%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.07
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone																0	0%	700
Benzene																0	0%	1
Carbon Disulfide																2	6%	700
Chlorobenzene																0	0%	50
Chloroethane																0	0%	2800
Chloromethane																0	0%	2.6
1,2-Dibromoethane																0	0%	0.0004
1,4-Dichlorobenzene																0	0%	1.4
cis-1,2-Dichloroethene																0	0%	70
1,1-Dichloroethane																0	0%	70
1,2-Dichloroethane																0	0%	0.38
1,1-Dichloroethene																0	0%	7
Methylene Chloride																0	0%	4.6
Tetrachloroethylene																0	0%	0.7
Toluene																0	0%	1000
1,1,1-Trichloroethane																0	0%	200
Trichloroethylene																0	0%	2.8
Trichloroflouromethane																0	0%	2100
Vinyl Chloride																0	0%	0.015
Xylenes																0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 6 (MW6)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW6																			
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																				
Antimony						NA	NA		NA											
Arsenic				0.005		NA	NA		NA											
Barium	0.068	0.096	0.141	0.062		NA	NA		NA			0.084	0.1	0.1						
Beryllium						NA	NA		NA											
Cadmium	0.005	0.009	0.004			NA	NA		NA											
Chromium	0.003	0.033		0.005		NA	NA	0.020	NA		0.012									
Cobalt						NA	NA		NA		0.011	0.009			0.01		0.01		0.011	
Copper		0.019	0.01	0.008		NA	NA		NA			0.020								
Lead	0.009	0.019	0.033	0.007	0.037	NA	NA	0.019	NA		0.011	0.007								
Nickel	0.005					NA	NA		NA											
Selenium						NA	NA		NA											
Silver						NA	NA		NA											
Vanadium	0.008	0.074	0.026			NA	NA	0.055	NA											
Zinc	0.038	0.047	0.029	0.018		NA	NA		NA			0.017								
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA		NA				NA		NA		NA	
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA	0.0004	0.0004	0.0004	NA	0.002	NA		NA	
Tin*	NA	NA	NA	NA		NA	NA		NA		NA	0.1			NA		NA		NA	
ORGANICS (ug/l)																				
Acetone						NA			NA								170			
Benzene						NA			NA						2.7	3.4			9.50	
Carbon Disulfide		7.9				NA			NA											
Chlorobenzene		4	8.5			NA			NA		13	24		70	11	5.1				
Chloroethane					38	NA	40	40	NA	64	91	46	28.6	190	44	53	53	21	78	
Chloromethane						NA			NA								46			
1,2-Dibromoethane						NA			NA											
1,4-Dichlorobenzene						NA			NA										7.20	
cis-1,2-Dichloroethene						NA			NA						1.9	2.6			13	
1,1-Dichloroethane	78.9	51.7	105	87.1	67	NA	66	61	NA	80	134	160	30.1		88	64	41	37		
1,2-Dichloroethane						NA			NA											
1,1-Dichloroethene			83.2			NA			NA						1.4					
Methylene Chloride	27.5	31.4		23.2	58	NA	7.2	7.2	NA	46	158	160	10.2	240	96			66	109	
Tetrachloroethylene	5.3		3.8	5.6		NA			NA						2.4	1.9			8.20	
Toluene						NA			NA											
1,1,1-Trichloroethane	15.4	16	15.1	8.3	10	NA	13	7.1	NA		7.2				2.4					
Trichloroethylene	8.4	6.7	10.6	8.8		NA	7.2		NA	6.8	11	9.9			7.9	8.7	7		17	
Trichloroflouromethane						NA			NA											
Vinyl Chloride						NA			NA										22	
Xylenes	46.7	83.8	68.9	74.8	24	NA	22	23	NA	24	32				11		6		11	
Dichlorodifluoromethane*	NA	NA	NA	NA	6.4		5	6.8	10.9		7.9		NA		2.4	2.7	NA		NA	
Diethyphthalate*	NA	NA	NA	NA									NA				NA		NA	
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA					6.8				NA				NA		NA	

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 6 (MW6)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT																MW6 Detects		NCGS
SAMPLING DATES	Oct .01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony																0	0%	0.0014**
Arsenic																1	3%	0.05
Barium												0.148	0.103	0.14	0.136	11	35%	2
Beryllium																0	0%	0.004**
Cadmium																3	10%	0.00175
Chromium		0.017														6	19%	0.05
Cobalt	0.012	0.013		0.019	0.015	0.015	0.019	0.017	0.013	0.017	0.016	0.028	0.017	0.03	0.027	19	61%	0.07**
Copper																4	13%	1
Lead																8	26%	0.015
Nickel																1	3%	0.1
Selenium																0	0%	0.05
Silver																0	0%	0.0175
Vanadium																4	13%	0.0035**
Zinc							91.5						0.015	0.016		8	26%	1.05
t-Cyanide*		NA		NA		NA		NA		NA		NA		NA		0	0%	0.07
Mercury*		NA	0.0006	NA	0.0008	NA		NA		NA		NA	0.0004	NA		7	44%	0.00105
Tin*		NA		NA		NA		NA		NA		NA		NA		1	6%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone																1	3%	700
Benzene													6.1	4.2	4.9	6	19%	1
Carbon Disulfide																1	3%	700
Chlorobenzene																7	22%	50
Chloroethane	17	19				15.9			12.3							17	53%	2800
Chloromethane																1	3%	2.6
1,2-Dibromoethane																0	0%	0.0004
1,4-Dichlorobenzene									6.9			3.2	7.7	7.4	5	6	19%	1.4
cis-1,2-Dichloroethene		5.8							17.3	11.9	12.8	12.6	23.1	31.4	41.2	11	34%	70
1,1-Dichloroethane	27	28	27.7	6.6	18.4	13.1	7.4	8.9	33.2	18.6	18.4	13.9	22.7	9.2	8.4	30	94%	70
1,2-Dichloroethane																0	0%	0.38
1,1-Dichloroethene																2	6%	7
Methylene Chloride	47	37	34.8		28.2	12.8			64.5	20.1	12.9	8.8	33	4.1	9	26	81%	4.6
Tetrachloroethylene									7.1	6.2	8	6.9	9.3	4.5	3.8	13	41%	0.7
Toluene																0	0%	1000
1,1,1-Trichloroethane																9	28%	200
Trichloroethylene	5.4	5.2							8.8	7.1	8.1	7.7	9.24	5.9	4.9	21	66%	2.8
Trichloroflouromethane																0	0%	2100
Vinyl Chloride										11.2		8	7.2	6.3	10.8	6	19%	0.015
Xylenes									9.8							13	41%	530
Dichlorodifluoromethane*		NA		NA		NA		NA		NA		NA		NA		7	35%	1400
Diethyphthalate*		NA		NA		NA		NA		NA		NA		NA		0	0%	5000
bis(2-ethylhexyl)phthalate*		NA		NA		NA		NA		NA		NA		NA		1	5%	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 7,7B (MW7,7B)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW7				MW7B														
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct.00	Apr. 01
INORGANICS (mg/l)																			
Antimony		NA	NA			NA	NA		NA					NT					
Arsenic		NA	NA		0.033	NA	NA	0.010	NA	0.01	0.032	0.279		NT					
Barium	0.892	NA	NA	0.2	0.55	NA	NA		NA				0.3	NT	0.9		0.5		
Beryllium		NA	NA	0.001	0.003	NA	NA		NA		0.003			NT	0.004				
Cadmium	0.0013	NA	NA	0.001	0.004	NA	NA		NA		0.004			NT					
Chromium	0.03	NA	NA	0.040	0.09	NA	NA	0.020	NA	0.021	0.071	0.011	0.010	NT	0.09	0.01		0.014	
Cobalt	0.146	NA	NA	0.013	0.04	NA	NA	0.012	NA		0.018	0.011		NT	0.07	0.02		0.019	0.020
Copper	0.034	NA	NA	0.036		NA	NA		NA			0.013		NT	0.08				
Lead	0.519	NA	NA	0.044	0.36	NA	NA	0.196	NA	0.087	0.264	0.062	0.070	NT	0.71	0.05	0.1	0.036	
Nickel	0.02	NA	NA			NA	NA		NA					NT					
Selenium		NA	NA			NA	NA		NA					NT					
Silver		NA	NA			NA	NA		NA					NT					
Vanadium	0.197	NA	NA	0.06	0.23	NA	NA	0.064	NA	0.054	0.169			NT	0.21				
Zinc	0.051	NA	NA	0.065	0.06	NA	NA		NA			0.026		NT	0.15	0.05			
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA		NA		NA	NT	NA		NA		NA
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA	0.0006	NA	NT	NA	0.001	NA		NA
Tin*	NA	NA	NA	NA		NA	NA		NA		NA		NA	NT	NA		NA		NA
ORGANICS (ug/l)																			
Acetone			NA			NA			NA										
Benzene			NA			NA			NA					NT	1.1				
Carbon Disulfide			NA			NA			NA					NT					
Chlorobenzene			NA			NA			NA					NT					
Chloroethane			NA	29.3	30	NA	13	14	NA	37		4.8	177	NT	31	68	44	21	31
Chloromethane			NA			NA			NA					NT			64		
1,2-Dibromoethane			NA			NA			NA					NT					
1,4-Dichlorobenzene			NA			NA			NA					NT					
cis-1,2-Dichloroethene			NA			NA			NA					NT					
1,1-Dichloroethane	262	69.7	NA	52.4	100	NA	92	77	NA	100	56	30	99.5	NT	110	210	170	90	
1,2-Dichloroethane			NA			NA			NA					NT					
1,1-Dichloroethene	8.6	8.1	NA	6.2	17	NA	15	8.8	NA	15	14	12	14.7	NT	7.2	7.4			10
Methylene Chloride		11.2	NA			NA			NA	13	28	2.2	14.6	NT	53			60	75
Tetrachloroethylene			NA			NA			NA					NT					
Toluene	31.4	13.2	NA	3.8	11	NA	9		NA					NT	3.4		5		
1,1,1-Trichloroethane	59.1	59.3	NA	29.1	78	NA	65	75	NA	65	49	27	33.4	NT	11	12	12		8.20
Trichloroethylene	9.9	10.7	NA			NA			NA			1		NT	3.6	7.8	6		5.30
Trichloroflouromethane			NA	11.7	14	NA	8.7	11	NA	22	11	13	9.4	NT	8.3				9.10
Vinyl Chloride			NA			NA			NA					NT					
Xylenes	6.5	5.4	NA			NA			NA					NT	4.8		12		
Dichlorodifluoromethane*	NA	NA	NA	NA	56	155	34	53	69.2	110	94		33.2	NT	31	41	NA		NA
Diethyphthalate*	NA	NA	NA	NA	13									NT			NA		NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	24									NT			NA		NA

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 7,7B (MW7,7B)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT																MW7,7B Detects		NCGS
SAMPLING DATES	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony																0	0%	0.0014**
Arsenic																5	18%	0.05
Barium												0.341	0.345	0.268	0.64	10	36%	2
Beryllium																4	14%	0.004**
Cadmium																4	14%	0.00175
Chromium		0.013														12	43%	0.05
Cobalt	0.014		0.024	0.017	0.025	0.022	0.019	0.015	0.022	0.032	0.031	0.025	0.026	0.031	0.036	24	86%	0.07**
Copper																4	14%	1
Lead	0.017	0.020			0.035		0.018	0.027	0.019	0.010	0.015	0.014	0.031		0.019	23	82%	0.015
Nickel																1	4%	0.1
Selenium																0	0%	0.05
Silver																0	0%	0.0175
Vanadium																7	25%	0.0035**
Zinc																6	21%	1.05
t-Cyanide*		NA		NA		NA		NA		NA		NA		NA		0	0%	0.07
Mercury*	0.001	NA	0.0027	NA	0.0014	NA	0.0011	NA	0.0015	NA	0.0046	NA	0.0026	NA	0.00038	10	71%	0.00105
Tin*		NA	0.179	NA		NA		NA		NA		NA		NA		1	7%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone																0	0%	700
Benzene												4.7	4.1	4.2	5.8	5	17%	1
Carbon Disulfide																0	0%	700
Chlorobenzene				6			5.3							3	3.9	4	13%	50
Chloroethane	22	34	14.9	19.9	30.7	28.5	22.6	13.6	21.9	24.9	16.1	10.5	12.4		11.1	26	87%	2800
Chloromethane																1	3%	2.6
1,2-Dibromoethane																0	0%	0.0004
1,4-Dichlorobenzene															1.7	1	3%	1.4
cis-1,2-Dichloroethene												6			16	2	7%	70
1,1-Dichloroethane	176	230	87.1	220	141	137	113	147	22.5	176	174	153	129		15.1	28	93%	70
1,2-Dichloroethane				8.7												1	3%	0.38
1,1-Dichloroethene	5.3	7.4	6.5	8.1	6	5.9		5.4								20	69%	7
Methylene Chloride	138	154	26.4	174	70.3	93.3	101	75.1	59.6	79.9	74.1	74.5	45.5		69	22	73%	4.6
Tetrachloroethylene									9				3.7	3.2	3.7	4	13%	0.7
Toluene																7	23%	1000
1,1,1-Trichloroethane	5.6	6.9		5.1												17	57%	200
Trichloroethylene	7.3	8.8			6.8	7.6	7.7	7.5		10.5	9.9	8.8	9.2	9.1	8.8	19	63%	2.8
Trichloroflouromethane		7	5.1										1.5	2.2	1	15	50%	2100
Vinyl Chloride												5	5	3.9	8.2	4	13%	0.015
Xylenes		9.3		6.3			5.6					4.8			9.2	9	30%	530
Dichlorodifluoromethane*		NA	24.7	NA	20.6	NA	10.7	NA	12.6	NA	9.5	NA	7	NA	5.7	17	85%	1400
Diethyphthalate*		NA		NA		NA		NA		NA		NA		NA		1	5%	5000
bis(2-ethylhexyl)phthalate*		NA		NA		NA		NA		NA		NA		NA		1	5%	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 8 (MW8)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW8																		
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																			
Antimony						NA	NA		NA										
Arsenic						NA	NA		NA		0.015								
Barium	0.043	0.05	0.025	0.032		NA	NA		NA			0.037					0.08		
Beryllium						NA	NA		NA		0.004					0.007			
Cadmium		0.002	0.001			NA	NA		NA		0.002								
Chromium		0.013				NA	NA		NA		0.111	0.009							
Cobalt						NA	NA		NA										
Copper	0.005	0.015	0.09	0.005		NA	NA		NA			0.007							
Lead		0.008			0.011	NA	NA		NA		0.073	0.008							
Nickel						NA	NA		NA										
Selenium						NA	NA		NA										
Silver						NA	NA		NA										
Vanadium		0.045				NA	NA		NA		0.410								
Zinc	0.02	0.035	0.019	0.009		NA	NA		NA		0.056	0.020		0.040					
t-Cyanide*	NA	NA	NA	NA		NA	NA		NA	0.127	NA		NA		NA		NA		NA
Mercury*	NA	NA	NA	NA		NA	NA		NA		NA		NA	0.002	NA		NA		NA
Tin*	NA	NA	NA	NA		NA	NA		NA		NA		NA		NA		NA		NA
ORGANICS (ug/l)																			
Acetone						NA			NA										
Benzene						NA			NA			2.1			1.6				
Carbon Disulfide						NA			NA										
Chlorobenzene						NA			NA										
Chloroethane					16	NA	7.2		NA		31	22	12.2		14	21	41	16	19
Chloromethane						NA			NA							6.1	88		
1,2-Dibromoethane						NA			NA										
1,4-Dichlorobenzene						NA			NA										
cis-1,2-Dichloroethene						NA			NA										
1,1-Dichloroethane					6.4	NA	11	7.8	NA		45	47	10.2	39	37	59	92	44	135
1,2-Dichloroethane						NA			NA										
1,1-Dichloroethene						NA			NA										
Methylene Chloride						NA			NA		49	31	5.2	25	30			74	140
Tetrachloroethylene						NA			NA										
Toluene						NA			NA										
1,1,1-Trichloroethane						NA			NA										
Trichloroethylene						NA			NA			2.2			1.8	2.8			6.80
Trichloroflouromethane						NA			NA										
Vinyl Chloride						NA			NA										
Xylenes						NA			NA										5.00
Dichlorodifluoromethane*	NA	NA	NA	NA	7	6.8							NA		2.3	4.3	NA		NA
Diethyphthalate*	NA	NA	NA	NA									NA				NA		NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA									NA				NA		NA
		- indicates concentrations exceeding NCGS																	
	"NE"	- not established																	
	"NA"	- not applicable																	
	*	-denotes an Appendix II constituent not included in Appendix I																	

Groundwater Monitoring Well Data
Monitoring Well 8 (MW8)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT																MW8 Detects		NCGS
SAMPLING DATES	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																		(mg/l)
Antimony																0	0%	0.0014**
Arsenic																1	3%	0.05
Barium														0.115	0.108	8	26%	2
Beryllium																2	6%	0.004**
Cadmium																3	10%	0.00175
Chromium	0.022															4	13%	0.05
Cobalt																0	0%	0.07**
Copper																5	16%	1
Lead																4	13%	0.015
Nickel			0.053													1	3%	0.1
Selenium																0	0%	0.05
Silver																0	0%	0.0175
Vanadium	0.063															3	10%	0.0035**
Zinc																7	23%	1.05
t-Cyanide*		NA		NA		NA		NA		NA		NA		NA		1	7%	0.07
Mercury*		NA		NA		NA		NA		NA		NA		NA	0.0002	2	13%	0.00105
Tin*		NA		NA		NA		NA		NA		NA		NA		0	0%	NE
ORGANICS (ug/l)																		(ug/l)
Acetone																0	0%	700
Benzene													2.6	2.5	2.9	5	16%	1
Carbon Disulfide																0	0%	700
Chlorobenzene																0	0%	50
Chloroethane		28	15.3	12.7	13.2											14	44%	2800
Chloromethane	25															3	9%	2.6
1,2-Dibromoethane																0	0%	0.0004
1,4-Dichlorobenzene													1.3	1.2	1.5	3	9%	1.4
cis-1,2-Dichloroethene												7	5.4	10.2	13.2	4	13%	70
1,1-Dichloroethane		80	76.8	71.5	59.2	42.7	31	38.9	59	58.6	63	49.1	54.3		61.8	25	78%	70
1,2-Dichloroethane																0	0%	0.38
1,1-Dichloroethene	81															1	3%	7
Methylene Chloride	92	90	80.5	71.2	69	44.5	39.9	40.6	63.3	64	67.2	48.4	35.9	31	48	22	69%	4.6
Tetrachloroethylene											5.2	5	6.5	5.5	4.7	5	16%	0.7
Toluene																0	0%	1000
1,1,1-Trichloroethane																0	0%	200
Trichloroethylene	5.3											4	4.4	4.8	4.8	9	28%	2.8
Trichloroflouromethane																0	0%	2100
Vinyl Chloride														1	1.5	2	6%	0.015
Xylenes																1	3%	530
Dichlorodifluoromethane*		NA		NA		NA		NA		NA		NA		NA		4	20%	1400
Diethyphthalate*		NA		NA		NA		NA		NA		NA		NA		0	0%	5000
bis(2-ethylhexyl)phthalate*		NA		NA		NA		NA		NA		NA		NA		0	0%	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 9 (MW9)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW9																MW9 Detects		NCGS
SAMPLING DATES	Apr. 01	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																			(mg/l)
Antimony																	0	0%	0.0014**
Arsenic																	0	0%	0.05
Barium													0.103	0.123	0.129	0.140	4	25%	2
Beryllium																	0	0%	0.004**
Cadmium																	0	0%	0.00175
Chromium		0.038	0.015	0.082													3	19%	0.05
Cobalt																	0	0%	0.07**
Copper														0.013			1	6%	1
Lead				0.014													1	6%	0.015
Nickel																	0	0%	0.1
Selenium																	0	0%	0.05
Silver																	0	0%	0.0175
Vanadium		0.078		0.189													2	13%	0.0035**
Zinc																	0	0%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	0.07
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.005	NA	0.0015	2	NA	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	NE
ORGANICS (ug/l)																			(ug/l)
Acetone																	0	0%	700
Benzene	8.6	11	7.8	8.2	8.1	6.4					5.6	5.2	5	5.4	11.5	8	12	75%	1
Carbon Disulfide																	0	0%	700
Chlorobenzene			18	23.6	19.8	18	16.2	10.3	10.1	12.1	18.2	11.7	11.1	11.8	8.1	9.6	14	88%	50
Chloroethane	65	51	39	35.7	27.4	36	21.4	16.5	15.7	22.4	23.5	20.3	13	12.4	11.6	12.3	16	100%	2800
Chloromethane	189																1	6%	2.6
1,2-Dibromoethane		14															1	6%	0.0004
1,4-Dichlorobenzene														2.5	6.6	2.1	3	19%	1.4
cis-1,2-Dichloroethene				6							6.5	7.9	5.7	8	25	13.1	7	44%	70
1,1-Dichloroethane		126	219	170	202	135	122	75.2	81.9	110	103	87	74.7	58.1		68.1	14	88%	70
1,2-Dichloroethane					11.8												1	6%	0.38
1,1-Dichloroethene																	0	0%	7
Methylene Chloride		195	231	272	197	166	127	67.9	56.7	75.7	122	96.4	64.2	49.6		64.6	14	88%	4.6
Tetrachloroethylene		5.3		5.3	5.1									2.9	4.4	2.4	6	38%	0.7
Toluene																	0	0%	1000
1,1,1-Trichloroethane																	0	0%	200
Trichloroethylene	11	15	9.8	10		9.5	8.2	5.8	7	6.5	6.2	5	4.7	3.9	5.9	4.2	15	94%	2.8
Trichloroflouromethane																	0	0%	2100
Vinyl Chloride													9.1	5.9	6.5	8.7	4	25%	0.015
Xylenes	26	39	25	24.5	19.6	15.6	7.3				7.1	5.6			5.1		10	63%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	NE

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 10 (MW10)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW10																MW10 Detects		NCGS
SAMPLING DATES	Apr. 01	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																			(mg/l)
Antimony																	0	0%	0.0014**
Arsenic																	0	0%	0.05
Barium																	0	0%	2
Beryllium																	0	0%	0.004**
Cadmium																	0	0%	0.00175
Chromium	0.014		0.013	0.118						0.012							4	25%	0.05
Cobalt																	0	0%	0.07**
Copper														0.018	0.021		2	13%	1
Lead				0.012													1	6%	0.015
Nickel																	0	0%	0.1
Selenium																	0	0%	0.05
Silver																	0	0%	0.0175
Vanadium				0.246													1	6%	0.0035**
Zinc	0.052												0.019		0.013		3	19%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	0.07
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	NE
ORGANICS (ug/l)																			(ug/l)
Acetone					156				130	419	234						4	25%	700
Benzene	6.9	7.3	6.2										4.6	2	4.5	3.9	7	44%	1
Carbon Disulfide																	0	0%	700
Chlorobenzene	25	33	21	9.2		6.8	5.7	6.7					3.4				8	50%	50
Chloroethane	72	47	51	16.7	11.6	18.8	19.1	19.8	12.2								9	56%	2800
Chloromethane																	0	0%	2.6
1,2-Dibromoethane																	0	0%	0.0004
1,4-Dichlorobenzene														1.3	1.3	1.4	3	19%	1.4
cis-1,2-Dichloroethene	17	17	20	6.9		6.8	11.7	12.6	10.7	6.5	15.8	7.9	16.9	6.9	9	13	15	94%	70
1,1-Dichloroethane		266	109	59.3	42.6	69.1	606	53.3	34.9	25.2	19.1	9.4	10.9	9.2	7.5	7.7	15	94%	70
1,2-Dichloroethane																	0	0%	0.38
1,1-Dichloroethene																	0	0%	7
Methylene Chloride	120	310	132	59.3	19.7	48.7	48	67.7	51.6		27.1		14.4		4.9		12	75%	4.6
Tetrachloroethylene	12	11	13	6.8	7.1	7.3											6	38%	0.7
Toluene																13.1	1	6%	1000
1,1,1-Trichloroethane																	0	0%	200
Trichloroethylene	11	11	9.1			5.7									1.3		5	31%	2.8
Trichloroflouromethane																	0	0%	2100
Vinyl Chloride	10													1.4	2	3.3	4	25%	0.015
Xylenes	35	39	30	7.4	5	6.4		12.3	5.5		5.3						9	56%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		0	NA	NE

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 11 (MW11)
Downgradient Well - Set 1 (Subset 1N)
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW11				MW11 Detects		NCGS
SAMPLING DATES	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)							(mg/l)
Antimony					0	0%	0.0014**
Arsenic					0	0%	0.05
Barium					0	0%	2
Beryllium					0	0%	0.004**
Cadmium					0	0%	0.00175
Chromium					0	0%	0.05
Cobalt					0	0%	0.07**
Copper					0	0%	1
Lead					0	0%	0.015
Nickel					0	0%	0.1
Selenium					0	0%	0.05
Silver					0	0%	0.0175
Vanadium					0	0%	0.0035**
Zinc		0.013			1	25%	1.05
t-Cyanide*	NA	NA	NA	NA	0	NA	0.07
Mercury*	NA	NA	NA	NA	0	NA	0.00105
Tin*	NA	NA	NA	NA	0	NA	NE
ORGANICS (ug/l)							(ug/l)
Acetone					0	0%	700
Benzene					0	0%	1
Carbon Disulfide					0	0%	700
Chlorobenzene					0	0%	50
Chloroethane					0	0%	2800
Chloromethane					0	0%	2.6
1,2-Dibromoethane					0	0%	0.0004
1,4-Dichlorobenzene					0	0%	1.4
cis-1,2-Dichloroethene					0	0%	70
1,1-Dichloroethane					0	0%	70
1,2-Dichloroethane					0	0%	0.38
1,1-Dichloroethene					0	0%	7
Methylene Chloride					0	0%	4.6
Tetrachloroethylene					0	0%	0.7
Toluene					0	0%	1000
1,1,1-Trichloroethane					0	0%	200
Trichloroethylene					0	0%	2.8
Trichloroflouromethane					0	0%	2100
Vinyl Chloride					0	0%	0.015
Xylenes					0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	0	NA	1400
Diethyphthalate*	NA	NA	NA	NA	0	NA	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	0	NA	NE

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 12 (MW12)
Downgradient Well - Set 1 (Subset 1N)
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW12				MW12 Detects		NCGS
SAMPLING DATES	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)							(mg/l)
Antimony					0	0%	0.0014**
Arsenic					0	0%	0.05
Barium					0	0%	2
Beryllium	0.001	0.0019	0.0015	0.002	4	100%	0.004**
Cadmium					0	0%	0.00175
Chromium					0	0%	0.05
Cobalt					0	0%	0.07**
Copper					0	0%	1
Lead					0	0%	0.015
Nickel					0	0%	0.1
Selenium					0	0%	0.05
Silver					0	0%	0.0175
Vanadium					0	0%	0.0035**
Zinc	0.013	0.017		0.012	3	75%	1.05
t-Cyanide*	NA	NA	NA	NA	0	NA	0.07
Mercury*	NA	NA	NA	NA	0	NA	0.00105
Tin*	NA	NA	NA	NA	0	NA	NE
ORGANICS (ug/l)							(ug/l)
Acetone					0	0%	700
Benzene					0	0%	1
Carbon Disulfide					0	0%	700
Chlorobenzene					0	0%	50
Chloroethane					0	0%	2800
Chloromethane					0	0%	2.6
1,2-Dibromoethane					0	0%	0.0004
1,4-Dichlorobenzene					0	0%	1.4
cis-1,2-Dichloroethene					0	0%	70
1,1-Dichloroethane					0	0%	70
1,2-Dichloroethane					0	0%	0.38
1,1-Dichloroethene					0	0%	7
Methylene Chloride					0	0%	4.6
Tetrachloroethylene					0	0%	0.7
Toluene					0	0%	1000
1,1,1-Trichloroethane					0	0%	200
Trichloroethylene					0	0%	2.8
Trichloroflouromethane					0	0%	2100
Vinyl Chloride					0	0%	0.015
Xylenes					0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	0	NA	1400
Diethyphthalate*	NA	NA	NA	NA	0	NA	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	0	NA	NE

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 13 (MW13)
Downgradient Well - Set 1 (Subset 1N)
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW13				MW13 Detects		NCGS
SAMPLING DATES	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)							(mg/l)
Antimony					0	0%	0.0014**
Arsenic					0	0%	0.05
Barium					0	0%	2
Beryllium					0	0%	0.004**
Cadmium					0	0%	0.00175
Chromium					0	0%	0.05
Cobalt					0	0%	0.07**
Copper					0	0%	1
Lead					0	0%	0.015
Nickel					0	0%	0.1
Selenium					0	0%	0.05
Silver					0	0%	0.0175
Vanadium					0	0%	0.0035**
Zinc	0.012				1	25%	1.05
t-Cyanide*	NA	NA	NA	NA	0	NA	0.07
Mercury*	NA	NA	NA	NA	0	NA	0.00105
Tin*	NA	NA	NA	NA	0	NA	NE
ORGANICS (ug/l)							(ug/l)
Acetone					0	0%	700
Benzene					0	0%	1
Carbon Disulfide					0	0%	700
Chlorobenzene					0	0%	50
Chloroethane					0	0%	2800
Chloromethane					0	0%	2.6
1,2-Dibromoethane					0	0%	0.0004
1,4-Dichlorobenzene					0	0%	1.4
cis-1,2-Dichloroethene					0	0%	70
1,1-Dichloroethane					0	0%	70
1,2-Dichloroethane					0	0%	0.38
1,1-Dichloroethene					0	0%	7
Methylene Chloride					0	0%	4.6
Tetrachloroethylene					0	0%	0.7
Toluene					0	0%	1000
1,1,1-Trichloroethane					0	0%	200
Trichloroethylene					0	0%	2.8
Trichloroflouromethane					0	0%	2100
Vinyl Chloride					0	0%	0.015
Xylenes					0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	0	NA	1400
Diethyphthalate*	NA	NA	NA	NA	0	NA	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	0	NA	NE

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 14 (MW14)
Downgradient Well - Set 1 (Subset 1N)
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW14				MW14 Detects		NCGS
SAMPLING DATES	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)							(mg/l)
Antimony					0	0%	0.0014**
Arsenic					0	0%	0.05
Barium					0	0%	2
Beryllium					0	0%	0.004**
Cadmium					0	0%	0.00175
Chromium					0	0%	0.05
Cobalt					0	0%	0.07**
Copper					0	0%	1
Lead					0	0%	0.015
Nickel					0	0%	0.1
Selenium					0	0%	0.05
Silver					0	0%	0.0175
Vanadium					0	0%	0.0035**
Zinc	0.012	0.018		0.012	3	75%	1.05
t-Cyanide*	NA	NA	NA	NA	0	NA	0.07
Mercury*	NA	NA	NA	NA	0	NA	0.00105
Tin*	NA	NA	NA	NA	0	NA	NE
ORGANICS (ug/l)							(ug/l)
Acetone					0	0%	700
Benzene					0	0%	1
Carbon Disulfide					0	0%	700
Chlorobenzene					0	0%	50
Chloroethane					0	0%	2800
Chloromethane					0	0%	2.6
1,2-Dibromoethane					0	0%	0.0004
1,4-Dichlorobenzene					0	0%	1.4
cis-1,2-Dichloroethene					0	0%	70
1,1-Dichloroethane					0	0%	70
1,2-Dichloroethane					0	0%	0.38
1,1-Dichloroethene					0	0%	7
Methylene Chloride					0	0%	4.6
Tetrachloroethylene					0	0%	0.7
Toluene					0	0%	1000
1,1,1-Trichloroethane					0	0%	200
Trichloroethylene					0	0%	2.8
Trichloroflouromethane					0	0%	2100
Vinyl Chloride					0	0%	0.015
Xylenes					0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	0	NA	1400
Diethyphthalate*	NA	NA	NA	NA	0	NA	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	0	NA	NE

		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 23B (MW23B)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW23B																			
SAMPLING DATES	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Mar. 96	July 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01	Oct. 01
INORGANICS (mg/l)																				
Antimony						NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		NA	NA
Arsenic						NA			NA	NA		0.064			0.006	0.015				
Barium	0.071	0.17	0.109	0.228		NA	0.076		NA	NA			0.029	0.077	0.26	1.64	0.084			
Beryllium		0.002		0.02	0.019	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		NA	NA
Cadmium	0.0008	0.001				NA			NA	NA										
Chromium	0.009	0.025		0.012	0.01	NA	0.0105		NA	NA					0.025	0.104				
Cobalt						NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		NA	NA
Copper	0.015	0.034	0.02	0.037		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		NA	NA
Lead	0.005	0.015	0.006	0.018	0.027	NA	0.0157		NA	NA		0.005	0.002	0.009	0.049	0.089				
Nickel						NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		NA	NA
Selenium						NA			NA	NA						0.002				
Silver			0.105			NA			NA	NA										
Vanadium	0.013	0.05	0.006	0.04		NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		NA	NA
Zinc	0.043	0.035	0.021	0.047	0.06	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA		NA	NA
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA	NA	NA	NA
Mercury*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA					0.0017	0.0003				
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA		NA	NA	NA	NA
ORGANICS (ug/l)																				
Acetone						NA			NA	NA	NA									
Benzene						NA			NA	NA	NA									
Carbon Disulfide						NA			NA	NA	NA									
Chlorobenzene						NA			NA	NA	NA									
Chloroethane						NA			NA	NA	NA									
Chloromethane						NA			NA	NA	NA									
1,2-Dibromoethane						NA			NA	NA	NA									
1,4-Dichlorobenzene						NA			NA	NA	NA									
cis-1,2-Dichloroethene						NA			NA	NA	NA									
1,1-Dichloroethane						NA			NA	NA	NA									
1,2-Dichloroethane						NA			NA	NA	NA									
1,1-Dichloroethene						NA			NA	NA	NA									
Methylene Chloride						NA			NA	NA	NA									
Tetrachloroethylene						NA			NA	NA	NA									
Toluene						NA			NA	NA	NA									
1,1,1-Trichloroethane						NA			NA	NA	NA									
Trichloroethylene						NA			NA	NA	NA									
Trichloroflouromethane						NA			NA	NA	NA									
Vinyl Chloride						NA			NA	NA	NA									
Xylenes						NA			NA	NA	NA									
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

MW23B, a Set 2 well, is statistically compared with Set 1 since it is downgradient of Set 1 wells.

- indicates concentrations exceeding NCGS

"NE" - not established

"NA" - not applicable

* -denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 23B (MW23B)
Downgradient Well - Set 1
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT															MW23B Detects		NCGS
SAMPLING DATES	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 04	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																	(mg/l)
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.0014**
Arsenic															3	10%	0.05
Barium													0.101	0.101	12	39%	2
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	3	43%	0.004**
Cadmium															2	6%	0.00175
Chromium															7	23%	0.05
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.07**
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	4	57%	1
Lead															11	35%	0.015
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.1
Selenium															1	3%	0.05
Silver															1	3%	0.0175
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	4	57%	0.0035**
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	5	71%	1.05
t-Cyanide*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.07
Mercury*															2	8%	0.00105
Tin*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	NE
ORGANICS (ug/l)																	(ug/l)
Acetone															0	0%	700
Benzene															0	0%	1
Carbon Disulfide															0	0%	700
Chlorobenzene															0	0%	50
Chloroethane															0	0%	2800
Chloromethane															0	0%	2.6
1,2-Dibromoethane															0	0%	0.0004
1,4-Dichlorobenzene															0	0%	1.4
cis-1,2-Dichloroethene															0	0%	70
1,1-Dichloroethane															0	0%	70
1,2-Dichloroethane															0	0%	0.38
1,1-Dichloroethene															0	0%	7
Methylene Chloride															0	0%	4.6
Tetrachloroethylene															0	0%	0.7
Toluene															0	0%	1000
1,1,1-Trichloroethane															0	0%	200
Trichloroethylene															0	0%	2.8
Trichloroflouromethane															0	0%	2100
Vinyl Chloride															0	0%	0.015
Xylenes															0	0%	530
Dichlorodifluoromethane*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	NA	1400
Diethyphthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	NA	5000
bis(2-ethylhexyl)phthalate*	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	NA	NE

NCGS = 2L STD or ** 13B GWPS as of Oct 07

APPENDIX B

DATA SET 2

Recommended Test Per Constituent
Total Detects and Percentages
Set 2 Data
Dunn-Erwin MSW Landfill
Harnett County, NC

CONSTITUENT	SET 2 DATA		RECOMMENDED TEST
	Detect #	Detect %	
INORGANICS (mg/l)			
Arsenic	9	6%	QUALITATIVE
Barium	43	30%	TEST OF PROPORTIONS*
Cadmium	20	14%	TEST OF PROPORTIONS*
Chromium	31	22%	TEST OF PROPORTIONS*
Lead	46	32%	TEST OF PROPORTIONS*
Mercury	8	6%	QUALITATIVE
Selenium	2	1%	QUALITATIVE
Silver	0	0%	QUALITATIVE
ORGANICS (ug/l)			
cis-1,2-dichloroethene	3	2%	QUALITATIVE
methylene chloride	1	1%	QUALITATIVE
mek; 2-butanone	1	1%	QUALITATIVE
NOTES:			
* The Test of Proportions may be performed jointly with a qualitative test to ensure more accurate results.			

Test of Proportions
Data Set 2
Dunn-Erwin MSW Landfill
Harnett County, North Carolina

Parameter	Nt	PDt	B*C	B*(1-C)	n	Pu	m	Pd	SD	Z	notes
DATA SET 2											
MW32											
Barium	62	0.323	20	42	31	0.323	31	0.323	0.119	0.000	not SSIOBL
Cadmium	62	0.226	14	48	31	0.258	31	0.194	0.106	0.607	not SSIOBL
Chromium	62	0.274	17	45	31	0.290	31	0.258	0.113	0.285	not SSIOBL
Lead	62	0.419	26	36	31	0.355	31	0.484	0.125	-1.029	not SSIOBL
MW33											
Barium	62	0.323	20	42	31	0.323	31	0.323	0.119	0.000	not SSIOBL
Cadmium	62	0.177	11	51	31	0.258	31	0.097	0.097	1.662	not SSIOBL
Chromium	62	0.242	15	47	31	0.290	31	0.194	0.109	0.890	not SSIOBL
Lead	62	0.306	19	43	31	0.355	31	0.258	0.117	0.826	not SSIOBL
MW34											
Barium	56	0.286	16	40	31	0.323	25	0.240	0.121	0.680	not SSIOBL
Cadmium	56	0.143	8	48	31	0.258	25	0.080	0.094	1.893	not SSIOBL
Chromium	56	0.214	12	44	31	0.290	25	0.158	0.110	1.201	not SSIOBL
Lead	56	0.286	16	40	31	0.355	25	0.263	0.121	0.755	not SSIOBL
MW35											
Barium	56	0.304	17	39	31	0.323	25	0.440	0.124	-0.950	not SSIOBL
Cadmium	56	0.196	11	45	31	0.258	25	0.120	0.107	1.293	not SSIOBL
Chromium	56	0.250	14	42	31	0.290	25	0.263	0.116	0.233	not SSIOBL
Lead	56	0.321	18	38	31	0.35	25	0.368	0.126	-0.108	not SSIOBL

NOTES:
Nt = total number of well samples analyzed (upgradient + particular downgradient analyzed) = m + n
PDt = total proportion of detects for Nt for parameter analyzed
m = total number of compliance well samples analyzed = # of sampling events for particular well analyzed
n = total number of upgradient well samples analyzed = # of sampling events X # of upgradient wells
Pu = proportion of upgradient detects for parameter analyzed
Pd = proportion of downgradient detects for parameter and individual well analyzed
Sd = standard error of the difference in proportions (8-4, Interim Final Guidance Doc.)
Z = If the absolute value of Z is greater than 1.96, then there is a statistically significant difference between the upgradient well detection for the given parameter and the particular dowgradient well analyzed.
* = Columns headed with B*C and B*(1-C) require values greater than or equal to 5 in order to perform the test of proportions. An asterisk denotes that the constituent did not qualify for the test of proportions for that particular well.
NA = Not Applicable. There are no detects of the particular constituent in the particular well analyzed.

Groundwater Monitoring Well Data
Monitoring Well 16 (MW16)
Upgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT		MW16 Detects		NCGS
SAMPLE DATE	Oct. 08	detect#	detect%	
INORGANICS (mg/l)				(mg/l)
Antimony	NA	0	0%	0.0014**
Arsenic		0	0%	0.05
Barium		10	32%	2
Beryllium	NA	0	0%	0.004**
Cadmium		8	26%	0.00175
Chromium		9	29%	0.05
Cobalt	NA	1	14%	0.07**
Copper	NA	4	57%	1
Lead		11	35%	0.015
Mercury		1	3%	0.00105
Nickel	NA	0	0%	0.1
Selenium		0	0%	0.05
Silver		0	0%	0.0175
Vanadium	NA	2	29%	0.0035**
Zinc	NA	5	71%	1.05
ORGANICS (ug/l)				(ug/l)
cis-1,2-dichloroethene		0	0%	70
methylene chloride		1	3%	4.6
mek; 2-butanone		0	0%	4200
NOTES				
				NCGS =
				2L STD or
		** 13B GWPS as of Oct 07		

Groundwater Monitoring Well Data
Monitoring Well 16 (MW16)
Upgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW16																	
SAMPLE DATE	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01
INORGANICS (mg/l)																		
Antimony						NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA
Arsenic						NA	NA											
Barium	0.112	0.194	0.114	0.147		NA	NA				0.104	0.099	0.1	0.281	0.162	0.06		
Beryllium						NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium	0.0018	0.001	0.006	0.007	0.002	NA	NA		0.0075	0.0049				0.001				
Chromium	0.004	0.007		0.005	0.01	NA	NA			0.019		0.006	0.008	0.062	0.019			
Cobalt						NA	NA		0.011	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	0.008	0.009	0.018	0.014		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA
Lead	0.002	0.003		0.004	0.013	NA	NA		0.012	0.020	0.002		0.005	0.039	0.011	0.002		
Mercury						NA	NA						0.0002					
Nickel						NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA
Selenium						NA	NA											
Silver						NA	NA											
Vanadium	0.005	0.012				NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA
Zinc	0.012	0.014	0.015	0.027		NA	NA		0.070	NA	NA	NA	NA	NA	NA	NA	NA	NA
ORGANICS (ug/l)																		
cis-1,2-dichloroethene						NA	NA											
methylene chloride			29.4			NA	NA											
mek; 2-butanone						NA	NA											

NOTES		
		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NT"	- not tested
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 16 (MW16)
Upgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT														
SAMPLE DATE	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08
INORGANICS (mg/l)														
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Arsenic														
Barium														
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium														
Chromium														
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Lead														
Mercury														
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Selenium														
Silver														
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
ORGANICS (ug/l)														
cis-1,2-dichloroethene														
methylene chloride														
mek; 2-butanone														
NOTES														

Groundwater Monitoring Well Data
Monitoring Well 32 (MW32)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW32																		
SAMPLE DATE	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01	Oct. 01
INORGANICS (mg/l)																			
Antimony		0.004				NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Arsenic		0.015		0.007		NA	NA							0.006	0.005				
Barium	0.097	0.646	0.145	0.251		NA	NA					0.043	0.249	0.352	0.303	0.067			
Beryllium				0.004		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium	0.0013	0.004				NA	NA						0.025	0.001	0.001				
Chromium	0.004	0.133	0.015	0.022		NA	NA							0.038	0.041				
Cobalt		0.039	0.013	0.009		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	0.006	0.094	0.017	0.026		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Lead	0.002	0.09	0.01	0.02		NA	NA				0.004	0.002	0.012	0.064	0.033				
Mercury						NA	NA												
Nickel		0.05				NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Selenium		0.002				NA	NA												
Silver						NA	NA												
Vanadium	0.005	0.41	0.045	0.09		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Zinc	0.008	0.189	0.029	0.051		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
ORGANICS (ug/l)																			
cis-1,2-dichloroethene						NA	NA												
methylene chloride						NA	NA												
mek; 2-butanone			471			NA	NA												

NOTES		
		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NT"	- not tested
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 32 (MW32)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT															MW32 Detects		NCGS
SAMPLE DATE	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																	(mg/l)
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1	14%	0.0014**
Arsenic															4	13%	0.05
Barium													0.105		10	32%	2
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1	14%	0.004**
Cadmium													0.001		6	19%	0.00175
Chromium			0.094	0.012											8	26%	0.05
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	3	43%	0.07**
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	4	57%	1
Lead			0.063				0.029		0.021		0.011	0.011	0.024		15	48%	0.015
Mercury															0	0%	0.00105
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	1	14%	0.1
Selenium															1	3%	0.05
Silver															0	0%	0.0175
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	4	57%	0.0035**
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	4	57%	1.05
ORGANICS (ug/l)																	(ug/l)
cis-1,2-dichloroethene															0	0%	70
methylene chloride															0	0%	4.6
mek; 2-butanone															1	3%	4200

NOTES

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 33 (MW33)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW33																		
SAMPLE DATE	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Apr. 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01	Oct. 01
INORGANICS (mg/l)																			
Antimony						NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Arsenic						NA	NA												
Barium	0.1	0.332	0.184	0.12		NA	NA				0.135	0.005	0.185	0.107	0.121	0.06			
Beryllium				0.008	0.007	NA	NA		0.004	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium	0.0021	0.003	0.005			NA	NA												
Chromium	0.005	0.012	0.014	0.006		NA	NA						0.012	0.007					
Cobalt		0.006	0.006			NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	0.013	0.02	0.028	0.015		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Lead	0.004	0.012	0.014	0.006		NA	NA				0.004		0.016	0.01	0.011				
Mercury						NA	NA				0.0004							0.0005	
Nickel						NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Selenium						NA	NA												
Silver						NA	NA												
Vanadium	0.008	0.02	0.02			NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Zinc	0.011	0.026	0.42	0.023		NA	NA			NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
ORGANICS (ug/l)																			
cis-1,2-dichloroethene						NA	NA						1.8	1.2	1.8				
methylene chloride						NA	NA												
mek; 2-butanone						NA	NA												

NOTES		
		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NT"	- not tested
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 33 (MW33)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT															MW33 Detects		NCGS
SAMPLE DATE	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																	(mg/l)
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.0014**
Arsenic															0	0%	0.05
Barium															10	32%	2
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	3	43%	0.004**
Cadmium															3	10%	0.00175
Chromium															6	19%	0.05
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	2	29%	0.07**
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	4	57%	1
Lead															8	26%	0.015
Mercury															2	6%	0.00105
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0	0%	0.1
Selenium															0	0%	0.05
Silver															0	0%	0.0175
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	3	43%	0.0035**
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	4	57%	1.05
ORGANICS (ug/l)																	(ug/l)
cis-1,2-dichloroethene															3	10%	70
methylene chloride															0	0%	4.6
mek; 2-butanone															0	0%	4200

NOTES

NCGS = 2L STD or ** 13B GWPS as of Oct 07

Groundwater Monitoring Well Data
Monitoring Well 34 (MW34)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW34																	
SAMPLE DATE	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05
INORGANICS (mg/l)																		
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Arsenic																		
Barium			0.112	0.005	0.201	0.246	0.221	0.062										
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium																		
Chromium					0.017	0.031	0.012											
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Lead			0.003	0.002	0.02	0.025	0.02											
Mercury					0.0003	0.0003												
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Selenium																		
Silver																		
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
ORGANICS (ug/l)																		
cis-1,2-dichloroethene																		
methylene chloride																		
mek; 2-butanone																		

NOTES

MW34 was installed in June 1996 therefore no data prior to this date are available.

	- indicates concentrations exceeding NCGS
"NE"	- not established
"NT"	- not tested
"NA"	- not applicable
*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 34 (MW34)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT								MW34 Detects		NCGS
SAMPLE DATE	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)										(mg/l)
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.0014**
Arsenic								0	0%	0.05
Barium								6	24%	2
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.004**
Cadmium						0.001	0.001	0	8%	0.00175
Chromium								3	16%	0.05
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.07**
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	1
Lead								5	26%	0.015
Mercury								2	11%	0.00105
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.1
Selenium								0	0%	0.05
Silver								0	0%	0.0175
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.0035**
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.05
ORGANICS (ug/l)										(ug/l)
cis-1,2-dichloroethene								0	0%	70
methylene chloride								0	0%	4.6
mek; 2-butanone								0	0%	4200
NOTES										
MW34 was installed in Ju										NCGS =
										2L STD or
"NE"								** 13B GWPS as of Oct 07		
"NT"										
"NA"										
*										

Groundwater Monitoring Well Data
Monitoring Well 35 (MW35)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	MW35																	
SAMPLE DATE	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01	Oct. 01	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05
INORGANICS (mg/l)																		
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Arsenic		0.0681	0.021		0.016	0.008	0.010											
Barium		2.06	0.877	0.005	0.489	0.848	0.512	0.132										
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Cadmium		0.0119	0.208			0.001												
Chromium		0.406			0.077	0.148	0.035	0.006										
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Lead		0.355	0.105	0.002	0.055	0.110	0.043	0.003										
Mercury		0.002			0.0002	0.0004												
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Selenium			0.004															
Silver																		
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
ORGANICS (ug/l)																		
cis-1,2-dichloroethene																		
methylene chloride																		
mek; 2-butanone																		

NOTES

MW35 was installed in June 1996 therefore no data prior to this date are available.

	- indicates concentrations exceeding NCGS
"NE"	- not established
"NT"	- not tested
"NA"	- not applicable
*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Well Data
Monitoring Well 35 (MW35)
Downgradient Well - Set2
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT								MW35 Detects		NCGS
SAMPLE DATE	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)										(mg/l)
Antimony	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.0014**
Arsenic								5	20%	0.05
Barium				0.132	0.318	0.225	0.25	7	44%	2
Beryllium	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.004**
Cadmium								3	12%	0.00175
Chromium								5	26%	0.05
Cobalt	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.07**
Copper	NA	NA	NA	NA	NA	NA	NA	NA	NA	1
Lead								7	37%	0.015
Mercury								3	16%	0.00105
Nickel	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.1
Selenium								1	4%	0.05
Silver								0	0%	0.0175
Vanadium	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.0035**
Zinc	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.05
ORGANICS (ug/l)										(ug/l)
cis-1,2-dichloroethene								0	0%	70
methylene chloride								0	0%	4.6
mek; 2-butanone								0	0%	4200
NOTES										
MW35 was installed in Ju										NCGS =
										2L STD or
"NE"								** 13B GWPS as of Oct 07		
"NT"										
"NA"										
*										

APPENDIX C

DATA SET 3

Recommended Test Per Constituent
Total Detects and Percentages
Set 3 Data
Dunn-Erwin MSW Landfill
Harnett County, NC

CONSTITUENT	SET 3 DATA		RECOMMENDED TEST
	Detect #	Detect %	
INORGANICS (mg/l)			
Antimony	0	0%	QUALITATIVE
Arsenic	7	8%	QUALITATIVE
Barium	18	20%	TEST OF PROPORTIONS*
Beryllium	0	0%	QUALITATIVE
Cadmium	5	6%	QUALITATIVE
Chromium	4	4%	QUALITATIVE
Cobalt	5	6%	QUALITATIVE
Copper	9	10%	TEST OF PROPORTIONS*
Lead	4	4%	QUALITATIVE
Nickel	0	0%	QUALITATIVE
Selenium	0	0%	QUALITATIVE
Silver	0	0%	QUALITATIVE
Vanadium	1	1%	QUALITATIVE
Zinc	25	28%	TEST OF PROPORTIONS*
ORGANICS (ug/l)			
Benzene	1	1%	QUALITATIVE
Chloromethane	1	1%	QUALITATIVE
cis-1,2 Dichloroethene	1	1%	QUALITATIVE
Ethylbenzene	1	1%	QUALITATIVE
Toluene	5	6%	QUALITATIVE
Vinyl chloride	1	1%	QUALITATIVE
Xylenes	1	1%	QUALITATIVE
NOTES:			
* The Test of Proportions may be performed jointly with a qualatative test to ensure more accurate results.			

Test of Proportions
Data Set 3
Dunn-Erwin MSW Landfill
Harnett County, North Carolina

Parameter	Nt	PDt	B*C	B*(1-C)	n	Pu	m	Pd	SD	Z	notes
DATA SET 3											
SWPT2											
Barium	59	0.169	10	49	29	0.172	30	0.167	0.098	0.059	not SSIOBL
Copper	59	0.085	5	54	29	0.069	30	0.100	0.073	-0.428	not SSIOBL
Zinc	59	0.271	16	43	29	0.310	30	0.233	0.116	0.665	not SSIOBL
SWPT3											
Barium	59	0.220	13	46	29	0.172	30	0.267	0.108	-0.873	not SSIOBL
Copper	59	0.102	6	53	29	0.069	30	0.133	0.079	-0.818	not SSIOBL
Zinc	59	0.305	18	41	29	0.310	30	0.300	0.120	0.086	not SSIOBL

NOTES:
Nt = total number of well samples analyzed (upgradient + particular downgradient analyzed) = m + n
PDt = total proportion of detects for Nt for parameter analyzed
m = total number of compliance well samples analyzed = # of sampling events for particular well analyzed
n = total number of upgradient well samples analyzed = # of sampling events X # of upgradient wells
Pu = proportion of upgradient detects for parameter analyzed
Pd = proportion of downgradient detects for parameter and individual well analyzed
Sd = standard error of the difference in proportions (8-4, Interim Final Guidance Doc.)
Z = If the absolute value of Z is greater than 1.96, then there is a statistically significant difference between the upgradient well detection for the given parameter and the particular dowgradient well analyzed.
* = Columns headed with B*C and B*(1-C) require values greater than or equal to 5 in order to perform the test of proportions. An asterisk denotes that the constituent did not qualify for the test of proportions for that particular well.
NA = Not Applicable. There are no detects of the particular constituent in the particular well analyzed.

Groundwater Monitoring Point Data
Surface Water Monitoring Point 1 (SWPT1)
Upgradient Point - Set 3
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	SWPT1																		
SAMPLE DATE	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Mar. 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01	Oct. 01
INORGANICS (mg/l)																			
Antimony						NA	NA												
Arsenic	0.007				0.013	NA	NA												
Barium	0.045	0.033	0.03	0.029		NA	NA												
Beryllium						NA	NA												
Cadmium					0.001	NA	NA												
Chromium	0.002					NA	NA												
Cobalt						NA	NA								0.010				
Copper	0.006			0.006		NA	NA												
Lead						NA	NA												
Nickel						NA	NA												
Selenium						NA	NA												
Silver						NA	NA												
Vanadium						NA	NA												
Zinc	0.011	0.016	0.021	0.013		NA	NA				0.022		0.04						
ORGANICS (ug/l)																			
Benzene						NA	NA												
Chloromethane						NA	NA												
cis-1,2 Dichloroethene						NA	NA												
Ethylbenzene						NA	NA												
Toluene						NA	NA								1.3				
Vinyl chloride						NA	NA												
Xylenes						NA	NA												
NOTES		- indicates concentrations exceeding NCGS																	
	"NE"	- not established																	
	"NT"	- not tested																	
	"NA"	- not applicable																	
	*	-denotes an Appendix II constituent not included in Appendix I																	

Groundwater Monitoring Point Data
Surface Water Monitoring Point 1 (SWPT1)
Upgradient Point - Set 3
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT															SWPT1 Detects		NCGS
SAMPLE DATE	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																	(mg/l)
Antimony								NA				NA			0	0%	0.0014**
Arsenic								NA				NA		0.047	3	10%	0.05
Barium								NA				NA		0.183	5	17%	2
Beryllium								NA				NA			0	0%	0.004**
Cadmium				0.001				NA				NA			2	7%	0.00175
Chromium								NA				NA			1	3%	0.05
Cobalt								NA				NA		0.031	2	7%	0.07**
Copper								NA				NA			2	7%	1
Lead								NA				NA		0.01	1	3%	0.015
Nickel								NA				NA			0	0%	0.1
Selenium								NA				NA			0	0%	0.05
Silver								NA				NA			0	0%	0.0175
Vanadium								NA				NA		0.04	1	3%	0.0035**
Zinc								NA			0.011	NA	0.022	0.033	9	31%	1.05
ORGANICS (ug/l)																	(ug/l)
Benzene								NA				NA			0	0%	1
Chloromethane								NA				NA		1.3	1	3%	2.6
cis-1,2 Dichloroethene								NA				NA			0	0%	70
Ethylbenzene								NA				NA			0	0%	550
Toluene								NA				NA			1	3%	1000
Vinyl chloride								NA				NA			0	0%	0.015
Xylenes								NA				NA			0	0%	530

NOTES

NCGS = 2L STD or ** 13B GWPS

Groundwater Monitoring Point Data
Surface Water Monitoring Point 2 (SWPT2)
Set 3 - Downgradient Point
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	SWPT2																		
SAMPLE DATE	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Mar. 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr .01	Oct. 01
INORGANICS (mg/l)																			
Antimony						NA	NA												
Arsenic		0.005				NA	NA												
Barium	0.032	0.027	0.025	0.028		NA	NA				0.01								
Beryllium						NA	NA												
Cadmium		0.001				NA	NA												
Chromium				0.002		NA	NA												
Cobalt						NA	NA								0.01				
Copper	0.005		0.006	0.005		NA	NA												
Lead			0.002			NA	NA												
Nickel						NA	NA												
Selenium						NA	NA												
Silver						NA	NA												
Vanadium						NA	NA												
Zinc	0.007	0.005	0.01	0.016		NA	NA				0.007								
ORGANICS (ug/l)																			
Benzene						NA	NA												
Chloromethane						NA	NA												
cis-1,2 Dichloroethene						NA	NA												
Ethylbenzene						NA	NA												
Toluene						NA	NA												
Vinyl chloride						NA	NA												
Xylenes						NA	NA												
NOTES		- indicates concentrations exceeding NCGS																	
	"NE"	- not established																	
	"NT"	- not tested																	
	"NA"	- not applicable																	
	*	-denotes an Appendix II constituent not included in Appendix I																	

Groundwater Monitoring Point Data
Surface Water Monitoring Point 2 (SWPT2)
Set 3 - Downgradient Point
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT															SWPT2 Detects		NCGS
SAMPLE DATE	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																	(mg/l)
Antimony												NA			0	0%	0.0014**
Arsenic												NA		0.012	2	7%	0.05
Barium												NA			5	17%	2
Beryllium												NA			0	0%	0.004**
Cadmium												NA			1	3%	0.00175
Chromium												NA			1	3%	0.05
Cobalt												NA			1	3%	0.07**
Copper												NA			3	10%	1
Lead												NA			1	3%	0.015
Nickel												NA			0	0%	0.1
Selenium												NA			0	0%	0.05
Silver												NA			0	0%	0.0175
Vanadium												NA			0	0%	0.0035**
Zinc												NA	0.02	0.014	7	23%	1.05
ORGANICS (ug/l)																	(ug/l)
Benzene												NA			0	0%	1
Chloromethane												NA			0	0%	2.6
cis-1,2 Dichloroethene												NA			0	0%	70
Ethylbenzene												NA			0	0%	550
Toluene												NA		2.3	1	3%	1000
Vinyl chloride												NA			0	0%	0.015
Xylenes												NA			0	0%	530
NOTES																	
																	NCGS =
																	2L STD or
																	** 13B GWPS

Groundwater Monitoring Point Data
Surface Water Monitoring Point 3 (SWPT3)
Set 3 - Downgradient Point
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT	SWPT3																		
SAMPLE DATE	Oct. 94	Nov.94	Jan. 95	Mar. 95	Sep. 95	Dec. 95	Feb. 96	Mar. 96	Oct. 96	Apr. 97	Oct. 97	Apr. 98	Oct. 98	Mar. 99	Oct. 99	Apr. 00	Oct. 00	Apr. 01	Oct. 01
INORGANICS (mg/l)																			
Antimony						NA	NA												
Arsenic					0.023	NA	NA												
Barium	0.035	0.03	0.025	0.029		NA	NA				0.032		0.2		0.036				
Beryllium						NA	NA												
Cadmium	0.0045				0.006	NA	NA												
Chromium				0.002		NA	NA					0.02							
Cobalt	0.006					NA	NA												
Copper	0.009	0.005	0.007	0.005		NA	NA												
Lead	0.003					NA	NA						0.02						
Nickel						NA	NA												
Selenium						NA	NA												
Silver						NA	NA												
Vanadium						NA	NA												
Zinc	0.013	0.005	0.009	0.01		NA	NA				0.026		0.1						
ORGANICS (ug/l)																			
Benzene					9.1	NA	NA												
Chloromethane						NA	NA												
cis-1,2 Dichloroethene					11	NA	NA												
Ethylbenzene					14	NA	NA												
Toluene					14	NA	NA								5.6				
Vinyl chloride					15	NA	NA												
Xylenes					20	NA	NA												

NOTES		
		- indicates concentrations exceeding NCGS
	"NE"	- not established
	"NT"	- not tested
	"NA"	- not applicable
	*	-denotes an Appendix II constituent not included in Appendix I

Groundwater Monitoring Point Data
Surface Water Monitoring Point 3 (SWPT3)
Set 3 - Downgradient Point
Dunn-Erwin Landfill
Harnett County, North Carolina

CONSTITUENT															SWPT3 Detects		NCGS
SAMPLE DATE	Apr. 02	Oct. 02	Apr. 03	Oct. 03	Apr. 04	Oct. 04	Apr. 05	Oct. 05	Apr. 06	Oct. 06	May 07	Oct. 07	Apr. 08	Oct. 08	detect#	detect%	
INORGANICS (mg/l)																	(mg/l)
Antimony												NA			0	0%	0.0014**
Arsenic												NA		0.011	2	7%	0.05
Barium												NA		0.118	8	27%	2
Beryllium												NA			0	0%	0.004**
Cadmium												NA			2	7%	0.00175
Chromium												NA			2	7%	0.05
Cobalt		0.002										NA			2	7%	0.07**
Copper												NA			4	13%	1
Lead												NA			2	7%	0.015
Nickel												NA			0	0%	0.1
Selenium												NA			0	0%	0.05
Silver												NA			0	0%	0.0175
Vanadium												NA			0	0%	0.0035**
Zinc					0.366							NA	0.016	0.028	9	30%	1.05
ORGANICS (ug/l)																	(ug/l)
Benzene												NA			1	3%	1
Chloromethane												NA			0	0%	2.6
cis-1,2 Dichloroethene												NA			1	3%	70
Ethylbenzene												NA			1	3%	550
Toluene												NA		3.5	3	10%	1000
Vinyl chloride												NA			1	3%	0.015
Xylenes												NA			1	3%	530

NOTES

NCGS = 2L STD or ** 13B GWPS

APPENDIX D

LABORATORY RESULTS AND CHAIN OF CUSTODY FORMS

DENR USE ONLY: ☐ Paper Report ☐ Electronic Data - Email CD (data loaded: Yes / No) Doc/Event #:

NC DENR
Division of Waste Management - Solid Waste

Environmental Monitoring Reporting Form

Notice: This form and any information attached to it are "Public Records" as defined in NC General Statute 132-1. As such, these documents are available for inspection and examination by any person upon request (NC General Statute 132-6).

Instructions:

- **Prepare one form for each individually monitored unit.**
- **Please type or print legibly.**
- Attach a notification table with values that attain or exceed NC 2L groundwater standards or NC 2B surface water standards. The notification must include a preliminary analysis of the cause and significance of each value. (e.g. naturally occurring, off-site source, pre-existing condition, etc.).
- Attach a notification table of any groundwater or surface water values that equal or exceed the reporting limits.
- Attach a notification table of any methane gas values that attain or exceed explosive gas levels. This includes any structures on or nearby the facility (NCAC 13B .1629 (4)(a)(i).
- In accordance with NC General Statutes Chapter 89C and 89E and NC Solid Waste Management Rules 15A NCAC 13B, be sure to affix a seal to the bottom of this page, when applicable.
- Send the original signed and sealed form, any tables, and Electronic Data Deliverable to: Compliance Unit, NCDENR-DWM, Solid Waste Section, 1646 Mail Service Center, Raleigh, NC 27699-1646.

Solid Waste Monitoring Data Submittal Information

Name of entity submitting data (laboratory, consultant, facility owner):

C.T. Clayton, Sr, PE, Inc - Consultant

Contact for questions about data formatting. Include data preparer's name, telephone number and E-mail address:

Name: Tyrus Clayton, Jr, PE Phone: (910) 897-7070

E-mail: tyrus@ctclayton.com

Facility name:	Facility Address:	Facility Permit #	NC Landfill Rule: (.0500 or .1600)	Actual sampling dates (e.g., October 20-24, 2006)
Harnett County - Dunn/Erwin Landfill	1724 Daniels Rd. Dunn, NC 28334	43-02	.1600	October 15 -24, 2008

Environmental Status: (Check all that apply)

☐ Initial/Background Monitoring ☐ Detection Monitoring ☒ Assessment Monitoring ☐ Corrective Action

Type of data submitted: (Check all that apply)

☒ Groundwater monitoring data from monitoring wells
☐ Groundwater monitoring data from private water supply wells
☐ Leachate monitoring data
☒ Surface water monitoring data
☐ Methane gas monitoring data
☐ Corrective action data (specify) _____
☐ Other(specify)

Notification attached?

☐ No. No groundwater or surface water standards were exceeded.
☒ Yes, a notification of values exceeding a groundwater or surface water standard is attached. It includes a list of groundwater and surface water monitoring points, dates, analytical values, NC 2L groundwater standard, NC 2B surface water standard or NC Solid Waste GWPS and preliminary analysis of the cause and significance of any concentration.
☐ Yes, a notification of values exceeding an explosive methane gas limit is attached. It includes the methane monitoring points, dates, sample values and explosive methane gas limits.

Certification

To the best of my knowledge, the information reported and statements made on this data submittal and attachments are true and correct. Furthermore, I have attached complete notification of any sampling values meeting or exceeding groundwater standards or explosive gas levels, and a preliminary analysis of the cause and significance of concentrations exceeding groundwater standards. I am aware that there are significant penalties for making any false statement, representation, or certification including the possibility of a fine and imprisonment.

Tyrus Clayton, Jr., PE — Facility Representative Name (Print)

Title

910-897-7070 — (Area Code) Telephone Number

Signature

3/12/09 — Date

Affix NC Licensed/ Professional Geologist/Engineer Seal here:

NORTH CAROLINA PROFESSIONAL SEAL 028909 ENGINEER C. TYRUS CLAYTON, JR.

Revised 01/2007

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 A

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/22/08
DATE REPORTED : 05/21/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	SW-1	SW-2	SW-3	Analysis Date	Analyst	Method Code
PH (field measurement), Units			6.3	6.2	6.4	04/22/08	RJH	SM4500HB
Antimony, ug/l	0.08	6.0	0.1 J	0.1 J	--- U	04/25/08	CMF	EPA200.8
Arsenic, ug/l	0.07	10.0	1.1 J	0.9 J	0.9 J	04/25/08	CMF	EPA200.8
Barium, ug/l	0.11	100.0	34.5 J	32.5 J	30.4 J	04/25/08	CMF	EPA200.8
Beryllium, ug/l	0.06	1.0	--- U	--- U	--- U	04/25/08	CMF	EPA200.8
Cadmium, ug/l	0.04	1.0	0.2 J	0.1 J	0.2 J	04/25/08	CMF	EPA200.8
Cobalt, ug/l	0.03	10.0	0.5 J	0.6 J	0.6 J	04/25/08	CMF	EPA200.8
Copper, ug/l	0.05	10.0	2.7 J	2.4 J	2.3 J	04/25/08	CMF	EPA200.8
Total Chromium, ug/l	0.11	10.0	0.8 J	0.8 J	1.2 J	04/25/08	CMF	EPA200.8
Lead, ug/l	0.04	10.0	1.1 J	1.1 J	1.3 J	04/25/08	CMF	EPA200.8
Nickel, ug/l	0.06	50.0	1.6 J	1.1 J	1.2 J	04/25/08	CMF	EPA200.8
Selenium, ug/l	0.14	10.0	0.4 J	0.3 J	0.3 J	04/25/08	CMF	EPA200.8
Silver, ug/l	0.04	10.0	0.1 J	--- U	--- U	04/29/08	CMF	EPA200.8
Thallium, ug/l	0.04	5.0	--- U	--- U	--- U	04/25/08	CMF	EPA200.8
Vanadium, ug/l	0.07	25.0	2.2 J	2.8 J	3.9 J	04/25/08	CMF	EPA200.8
Zinc, ug/l	0.04	10.0	22	20	16	04/25/08	CMF	EPA200.8
Turbidity, NTU	1.0	1.0	21	30	40	04/23/08	MDM	SM2130B
Conductivity (at 25c), uMhos	1.0	1.0	85	83	92	04/22/08	RJH	SM2510B
Temperature, °C			16	15	16	04/22/08	RJH	SM2550B

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

CLIENT ID: 6040 A

ANALYST: MAO
DATE COLLECTED: 04/22/08
DATE ANALYZED: 05/02/08
DATE REPORTED: 05/21/08

REVIEWED BY:

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	SW-1	SW-2	SW-3
1. Chloromethane	0.18	1.0	--- U	--- U	--- U
2. Vinyl Chloride	0.34	1.0	--- U	--- U	--- U
3. Bromomethane	0.26	10.0	--- U	--- U	--- U
4. Chloroethane	0.29	10.0	--- U	--- U	--- U
5. Trichlorofluoromethane	0.13	1.0	--- U	--- U	--- U
6. 1,1-Dichloroethene	0.14	5.0	--- U	--- U	--- U
7. Acetone	1.21	100.0	6.00 J	8.80 J	6.60 J
8. Iodomethane	0.12	10.0	--- U	--- U	--- U
9. Carbon Disulfide	0.14	100.0	--- U	--- U	--- U
10. Methylene Chloride	0.14	1.0	--- U	--- U	--- U
11. trans-1,2-Dichloroethene	0.13	5.0	--- U	--- U	--- U
12. 1,1-Dichloroethane	0.16	5.0	--- U	--- U	--- U
13. Vinyl Acetate	0.20	50.0	--- U	--- U	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	--- U	--- U	--- U
15. 2-Butanone	0.85	100.0	--- U	--- U	--- U
16. Bromochloromethane	0.11	3.0	--- U	--- U	--- U
17. Chloroform	0.13	5.0	--- U	--- U	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U	--- U	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U	--- U	--- U
20. Benzene	0.16	1.0	--- U	--- U	--- U
21. 1,2-Dichloroethane	0.12	1.0	--- U	--- U	--- U
22. Trichloroethene	0.13	1.0	--- U	--- U	--- U
23. 1,2-Dichloropropane	0.17	1.0	--- U	--- U	--- U
24. Bromodichloromethane	0.13	1.0	--- U	--- U	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U	--- U	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U	--- U	--- U
27. Toluene	0.13	1.0	--- U	--- U	--- U
28. trans-1,3-Dichloropropene	0.14	1.0	--- U	--- U	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U	--- U	--- U
30. Tetrachloroethene	0.16	1.0	--- U	--- U	--- U
31. 2-Hexanone	1.00	50.0	--- U	--- U	--- U
32. Dibromochloromethane	0.14	3.0	--- U	--- U	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U	--- U	--- U
34. Chlorobenzene	0.13	3.0	--- U	--- U	--- U
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U	--- U	--- U
36. Ethylbenzene	0.16	1.0	--- U	--- U	--- U
37. Xylenes	0.48	5.0	--- U	--- U	--- U
38. Dibromomethane	0.17	10.0	--- U	--- U	--- U
39. Styrene	0.16	1.0	--- U	--- U	--- U
40. Bromoform	0.11	3.0	--- U	--- U	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U	--- U	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U	--- U	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	--- U	--- U	--- U
44. 1,2-Dichlorobenzene	0.13	5.0	--- U	--- U	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U	--- U	--- U
46. Acrylonitrile	1.49	200.0	--- U	--- U	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U	--- U	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Box 7085, 114 Oakmont Dr.
nville, NC 27858

e (252) 756-6208 • Fax (252) 756-0633

CHAIN OF CUSTODY RECORD

[ENT: 6040 A Week: 18

ARNETT CO. (DUNN/ERWIN)
ENERAL SERVICES HARNETT CO.
R. JERRY BLANCHARD, MANAGER
0 SOUTH 9TH STREET
LLINGTON NC 27546

19) 233-0407

DISINFECTION: ☐ CHLORINE ☐ UV ☐ NONE ☐ _____

CHLORINE NEUTRALIZED AT COLLECTION																				
pH CHECK (LAB)																				
CONTAINER TYPE, P/G																				
CHEMICAL PRESERVATION																				
PARAMETERS				Field pH	Metals	Turbidity	Conductivity	Temperature	EPA 8260B	8260 Dup. 1	8260 Dup. 2									
				P	P	P	P	P	G	G	G									
				A	A	A	A	A	E	E	E									
					12				12	12	12									
SAMPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS															
V-1	042208	0840		15	6	G	G	G	G	G	G	G								
V-2	042208	0915		15	5	G	G	G	G	G	G	G								
V-3	042208	1035		16	5	G	G	G	G	G	G	G								

A - NONE D - NAOH
B - HNO_3 E - HCL
C - H_2SO_4 F - ZINC ACETATE
G - NA THIOSULFATE

CLASSIFICATION:
☐ WASTEWATER (NPDES)
☐ DRINKING WATER
☐ DWQ/GW
☒ SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY: (Y) N

SAMPLES COLLECTED BY: (Please Print) H Cagle / Fol

SAMPLES RECEIVED IN LAB AT 6.2 °C

QUISHED BY (SIG.) (SAMPLER)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME	COMMENTS:	
H Cagle	042208	BD	4/22 3:35		
QUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME		
QUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME		

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested.

№ 162151

A #5

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 B

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/23/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	MW-1	MW-2	MW-3R	MW-4	MW-5	Analysis Date	Analyst	Method Code
PH (field measurement), Units			5.6	4.6	5.4	4.5	6.0	04/23/08	RJH	SM4500HB
Antimony, ug/l	0.08	6.0	--- U	--- U	--- U	--- U	--- U	04/30/08	CMF	EPA200.8
Arsenic, ug/l	0.07	10.0	--- U	--- U	--- U	0.3 J	--- U	04/30/08	CMF	EPA200.8
Barium, ug/l	0.11	100.0	37.7 J	50.9 J	82.7 J	56.9 J	95.2 J	04/30/08	CMF	EPA200.8
Beryllium, ug/l	0.06	1.0	0.9 J	2	1	3	0.2 J	04/30/08	CMF	EPA200.8
Cadmium, ug/l	0.04	1.0	0.1 J	0.3 J	0.1 J	0.3 J	0.1 J	04/30/08	CMF	EPA200.8
Cobalt, ug/l	0.03	10.0	0.5 J	1.3 J	2.2 J	1.9 J	1.6 J	04/30/08	CMF	EPA200.8
Copper, ug/l	0.05	10.0	1.0 J	1.1 J	1.0 J	1.1 J	0.4 J	04/30/08	CMF	EPA200.8
Total Chromium, ug/l	0.11	10.0	--- U	--- U	--- U	--- U	--- U	04/30/08	CMF	EPA200.8
Lead, ug/l	0.04	10.0	0.3 J	0.7 J	0.4 J	0.5 J	0.1 J	04/30/08	CMF	EPA200.8
Nickel, ug/l	0.06	50.0	0.5 J	1.4 J	2.3 J	1.7 J	1.6 J	04/30/08	CMF	EPA200.8
Selenium, ug/l	0.14	10.0	--- U	0.2 J	--- U	1.0 J	--- U	04/30/08	CMF	EPA200.8
Silver, ug/l	0.04	10.0	--- U	--- U	--- U	--- U	--- U	04/30/08	CMF	EPA200.8
Thallium, ug/l	0.04	5.0	--- U	--- U	--- U	--- U	--- U	04/30/08	CMF	EPA200.8
Vanadium, ug/l	0.07	25.0	0.4 J	1.2 J	0.7 J	0.5 J	0.1 J	04/30/08	CMF	EPA200.8
Zinc, ug/l	0.04	10.0	3.8 J	12	14	17	2.9 J	04/30/08	CMF	EPA200.8
Turbidity, NTU	1.0	1.0	17	35	17	27	14	04/23/08	MDM	SM2130B
Conductivity (at 25c), uMhos	1.0	1.0	61	94	132	67	162	04/23/08	RJH	SM2510B
Temperature, °C			18	16	16	15	16	04/23/08	RJH	SM2550B
Static Water Level, feet			25.88	14.82	5.22	3.75	15.46	04/23/08	RJH	
Well Depth, feet			65.18	30.21	25.12	20.21	40.14	04/23/08	RJH	
Water Bailed, Gals.			19.2	7.2	9.3	7.8	11.7	04/23/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 B

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/23/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	MW-6	MW-7B	MW-8	MW-9	MW-10	Analysis Date	Analyst	Method Code
PH (field measurement), Units			5.2	4.6	4.3	4.4	5.6	04/23/08	RJH	SM4500HB
Antimony, ug/l	0.08	6.0	0.2 J	0.3 J	--- U	--- U	0.1 J	04/30/08	CMF	EPA200.8
Arsenic, ug/l	0.07	10.0	2.2 J	0.2 J	--- U	0.5 J	9.1 J	04/30/08	CMF	EPA200.8
Barium, ug/l	0.11	100.0	140	268	115	129	76.7 J	04/30/08	CMF	EPA200.8
Beryllium, ug/l	0.06	1.0	0.2 J	0.3 J	0.8 J	0.2 J	--- U	04/30/08	CMF	EPA200.8
Cadmium, ug/l	0.04	1.0	0.8 J	0.2 J	0.1 J	0.1 J	0.1 J	04/30/08	CMF	EPA200.8
Cobalt, ug/l	0.03	10.0	30	31	1.9 J	1.5 J	3.1 J	04/30/08	CMF	EPA200.8
Copper, ug/l	0.05	10.0	2.7 J	1.7 J	1.9 J	3.0 J	21	04/30/08	CMF	EPA200.8
Total Chromium, ug/l	0.11	10.0	0.2 J	--- U	--- U	1.1 J	1.0 J	04/30/08	CMF	EPA200.8
Lead, ug/l	0.04	10.0	2.0 J	9.9 J	1.2 J	1.9 J	1.0 J	04/30/08	CMF	EPA200.8
Nickel, ug/l	0.06	50.0	2.5 J	1.9 J	2.1 J	1.2 J	3.0 J	04/30/08	CMF	EPA200.8
Selenium, ug/l	0.14	10.0	1.0 J	0.5 J	0.4 J	0.9 J	1.7 J	04/30/08	CMF	EPA200.8
Silver, ug/l	0.04	10.0	--- U	0.1 J	0.1 J	--- U	0.1 J	04/30/08	CMF	EPA200.8
Thallium, ug/l	0.04	5.0	0.1 J	0.4 J	0.2 J	0.1 J	--- U	04/30/08	CMF	EPA200.8
Vanadium, ug/l	0.07	25.0	2.0 J	0.3 J	0.4 J	3.2 J	3.7 J	04/30/08	CMF	EPA200.8
Zinc, ug/l	0.04	10.0	16	3.6 J	7.1 J	3.2 J	13	04/30/08	CMF	EPA200.8
Turbidity, NTU	1.0	1.0	40	8.1	3.4	190	180	04/23/08	MDM	SM2130B
Conductivity (at 25c), uMhos	1.0	1.0	194	168	122	121	355	04/23/08	RJH	SM2510B
Temperature, °C			16	18	17	17	17	04/23/08	RJH	SM2550B
Static Water Level, feet			14.99	26.14	15.48	26.42	20.24	04/23/08	RJH	
Well Depth, feet			19.34	30.23	25.22	32.74	26.30	04/23/08	RJH	
Water Bailed, Gals.			2.1	2.1	2.5	3.0	2.4	04/23/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 B

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/23/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	MW-31	Trip Blank	Equipment Blank	Analysis Date	Analyst	Method Code
PH (field measurement), Units			4.8			04/23/08	RJH	SM4500HB
Antimony, ug/l	0.08	6.0	--- U		--- U	04/30/08	CMF	EPA200.8
Arsenic, ug/l	0.07	10.0	4.4 J		--- U	04/30/08	CMF	EPA200.8
Barium, ug/l	0.11	100.0	33.2 J		--- U	04/30/08	CMF	EPA200.8
Beryllium, ug/l	0.06	1.0	0.4 J		--- U	04/30/08	CMF	EPA200.8
Cadmium, ug/l	0.04	1.0	0.5 J		--- U	04/30/08	CMF	EPA200.8
Cobalt, ug/l	0.03	10.0	0.5 J		--- U	04/30/08	CMF	EPA200.8
Copper, ug/l	0.05	10.0	6.1 J		0.4 J	04/30/08	CMF	EPA200.8
Total Chromium, ug/l	0.11	10.0	9.5 J		--- U	04/30/08	CMF	EPA200.8
Lead, ug/l	0.04	10.0	14		0.1 J	04/30/08	CMF	EPA200.8
Nickel, ug/l	0.06	50.0	0.6 J		--- U	04/30/08	CMF	EPA200.8
Selenium, ug/l	0.14	10.0	0.3 J		--- U	04/30/08	CMF	EPA200.8
Silver, ug/l	0.04	10.0	0.1 J		--- U	04/30/08	CMF	EPA200.8
Thallium, ug/l	0.04	5.0	0.1 J		--- U	04/30/08	CMF	EPA200.8
Vanadium, ug/l	0.07	25.0	20.7 J		0.1 J	04/30/08	CMF	EPA200.8
Zinc, ug/l	0.04	10.0	10		1.6 J	04/30/08	CMF	EPA200.8
Turbidity, NTU	1.0	1.0	1000			04/23/08	MDM	SM2130B
Conductivity (at 25c), uMhos	1.0	1.0	27			04/23/08	RJH	SM2510B
Temperature, °C			19			04/23/08	RJH	SM2550B
Static Water Level, feet			22.95			04/23/08	RJH	
Well Depth, feet			39.33			04/23/08	RJH	
Water Bailed, Gals.			7.8			04/23/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 3771
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

CLIENT ID: 6040 B

ANALYST: MAO
DATE COLLECTED: 04/23/08
DATE REPORTED: 05/22/08

REVIEWED BY: _____

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	Date Analyzed: 05/06/08 MW-1	05/02/08 MW-2	05/02/08 MW-3R	05/02/08 MW-4	05/03/08 MW-5
1. Chloromethane	0.18	1.0	--- U	--- U	--- U	--- U	--- U
2. Vinyl Chloride	0.34	1.0	--- U	--- U	--- U	--- U	--- U
3. Bromomethane	0.26	10.0	--- U	--- U	--- U	--- U	--- U
4. Chloroethane	0.29	10.0	--- U	--- U	--- U	--- U	--- U
5. Trichlorofluoromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
6. 1,1-Dichloroethene	0.14	5.0	--- U	--- U	--- U	--- U	--- U
7. Acetone	1.21	100.0	5.20 J	5.50 J	4.10 J	4.80 J	3.80 J
8. Iodomethane	0.12	10.0	--- U	--- U	--- U	--- U	--- U
9. Carbon Disulfide	0.14	100.0	--- U	--- U	--- U	--- U	--- U
10. Methylene Chloride	0.14	1.0	--- U	--- U	--- U	--- U	--- U
11. trans-1,2-Dichloroethene	0.13	5.0	--- U	--- U	--- U	--- U	--- U
12. 1,1-Dichloroethane	0.16	5.0	--- U	0.40 J	--- U	--- U	--- U
13. Vinyl Acetate	0.20	50.0	--- U	--- U	--- U	--- U	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	--- U	--- U	--- U	--- U	--- U
15. 2-Butanone	0.85	100.0	--- U	--- U	--- U	--- U	--- U
16. Bromochloromethane	0.11	3.0	--- U	--- U	--- U	--- U	--- U
17. Chloroform	0.13	5.0	--- U	--- U	--- U	--- U	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U	--- U	--- U	--- U	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U	--- U	--- U	--- U	--- U
20. Benzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
21. 1,2-Dichloroethane	0.12	1.0	--- U	--- U	--- U	--- U	--- U
22. Trichloroethene	0.13	1.0	--- U	--- U	--- U	--- U	--- U
23. 1,2-Dichloropropane	0.17	1.0	--- U	--- U	--- U	--- U	--- U
24. Bromodichloromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U	--- U	--- U	--- U	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U	--- U	--- U	--- U	--- U
27. Toluene	0.13	1.0	--- U	--- U	--- U	--- U	--- U
28. trans-1,3-Dichloropropene	0.14	1.0	--- U	--- U	--- U	--- U	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U	--- U	--- U	--- U	--- U
30. Tetrachloroethene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
31. 2-Hexanone	1.00	50.0	--- U	--- U	--- U	--- U	--- U
32. Dibromochloromethane	0.14	3.0	--- U	--- U	--- U	--- U	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
34. Chlorobenzene	0.13	3.0	--- U	--- U	--- U	--- U	--- U
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U	--- U	--- U	--- U	--- U
36. Ethylbenzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
37. Xylenes	0.48	5.0	--- U	--- U	--- U	--- U	--- U
38. Dibromomethane	0.17	10.0	--- U	--- U	--- U	--- U	--- U
39. Styrene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
40. Bromoform	0.11	3.0	--- U	--- U	--- U	--- U	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U	--- U	--- U	--- U	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U	--- U	--- U	--- U	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	--- U	--- U	--- U	--- U	--- U
44. 1,2-Dichlorobenzene	0.13	5.0	--- U	--- U	--- U	--- U	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U	--- U	--- U	--- U	--- U
46. Acrylonitrile	1.49	200.0	--- U	--- U	--- U	--- U	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U	--- U	--- U	--- U	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

Drinking Water ID: 3771
Wastewater ID: 10

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

CLIENT ID: 6040 B

ANALYST: MAO
DATE COLLECTED: 04/23/08
DATE REPORTED: 05/22/08

REVIEWED BY:

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	05/03/08 MW-6	05/06/08 MW-7B	05/06/08 MW-8	05/06/08 MW-9	05/06/08 MW-10
Date Analyzed:							
1. Chloromethane	0.18	1.0	--- U	--- U	--- U	0.30 J	--- U
2. Vinyl Chloride	0.34	1.0	6.30	3.90	1.00	6.50	2.00
3. Bromomethane	0.26	10.0	--- U	--- U	--- U	--- U	--- U
4. Chloroethane	0.29	10.0	4.20 J	8.60 J	2.90 J	11.60	4.40 J
5. Trichlorofluoromethane	0.13	1.0	--- U	2.20	--- U	0.40 J	--- U
6. 1,1-Dichloroethene	0.14	5.0	0.30 J	4.20 J	0.40 J	0.70 J	--- U
7. Acetone	1.21	100.0	17.20 J	22.90 J	6.20 J	5.50 J	--- U
8. Iodomethane	0.12	10.0	--- U	--- U	--- U	--- U	--- U
9. Carbon Disulfide	0.14	100.0	--- U	--- U	--- U	--- U	--- U
10. Methylene Chloride	0.14	1.0	4.10	--- U	31.00	--- U	4.90
11. trans-1,2-Dichloroethene	0.13	5.0	0.20 J	--- U	--- U	0.20 J	--- U
12. 1,1-Dichloroethane	0.16	5.0	9.20	--- U	--- U	--- U	7.50
13. Vinyl Acetate	0.20	50.0	--- U	--- U	--- U	--- U	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	31.40	4.60 J	10.20	25.00	9.00
15. 2-Butanone	0.85	100.0	2.10 J	--- U	--- U	--- U	16.80 J
16. Bromochloromethane	0.11	3.0	--- U	--- U	--- U	--- U	--- U
17. Chloroform	0.13	5.0	--- U	--- U	0.20 J	--- U	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U	0.80 J	--- U	0.80 J	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U	--- U	--- U	--- U	--- U
20. Benzene	0.16	1.0	4.20	4.20	2.50	11.50	4.50
21. 1,2-Dichloroethane	0.12	1.0	0.40 J	0.30 J	--- U	0.80 J	--- U
22. Trichloroethene	0.13	1.0	5.90	9.10	4.80	5.90	1.30
23. 1,2-Dichloropropane	0.17	1.0	--- U	--- U	--- U	0.20 J	--- U
24. Bromodichloromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U	--- U	--- U	--- U	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U	--- U	--- U	--- U	--- U
27. Toluene	0.13	1.0	--- U	--- U	--- U	--- U	0.80 J
28. trans-1,3-Dichloropropene	0.14	1.0	--- U	--- U	--- U	--- U	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U	--- U	--- U	--- U	--- U
30. Tetrachloroethene	0.16	1.0	4.50	3.20	5.50	4.40	0.60 J
31. 2-Hexanone	1.00	50.0	--- U	--- U	--- U	--- U	--- U
32. Dibromochloromethane	0.14	3.0	--- U	--- U	--- U	--- U	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
34. Chlorobenzene	0.13	3.0	0.50 J	3.00	0.30 J	8.10	1.70 J
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U	--- U	--- U	--- U	--- U
36. Ethylbenzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
37. Xylenes	0.48	5.0	1.30 J	1.70 J	--- U	5.10	2.70 J
38. Dibromomethane	0.17	10.0	--- U	--- U	--- U	--- U	--- U
39. Styrene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
40. Bromoform	0.11	3.0	--- U	--- U	--- U	--- U	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U	--- U	--- U	--- U	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U	--- U	--- U	--- U	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	7.40	0.90 J	1.20	6.60	1.30
44. 1,2-Dichlorobenzene	0.13	5.0	--- U	--- U	0.30 J	--- U	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U	--- U	--- U	--- U	--- U
46. Acrylonitrile	1.49	200.0	--- U	--- U	--- U	--- U	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U	--- U	--- U	--- U	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

CLIENT ID: 6040 B

ANALYST: MAO
DATE COLLECTED: 04/23/08
DATE REPORTED: 05/22/08

REVIEWED BY: _____

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	05/06/08 MW-31	05/06/08 Trip Blank	05/06/08 Equipment Blank
	Date Analyzed:				
1. Chloromethane	0.18	1.0	--- U	--- U	--- U
2. Vinyl Chloride	0.34	1.0	--- U	--- U	--- U
3. Bromomethane	0.26	10.0	--- U	--- U	--- U
4. Chloroethane	0.29	10.0	--- U	--- U	--- U
5. Trichlorofluoromethane	0.13	1.0	--- U	--- U	--- U
6. 1,1-Dichloroethene	0.14	5.0	--- U	--- U	--- U
7. Acetone	1.21	100.0	9.60 J	1.90 J	2.50 J
8. Iodomethane	0.12	10.0	--- U	--- U	--- U
9. Carbon Disulfide	0.14	100.0	--- U	--- U	--- U
10. Methylene Chloride	0.14	1.0	--- U	--- U	0.20 J
11. trans-1,2-Dichloroethene	0.13	5.0	--- U	--- U	--- U
12. 1,1-Dichloroethane	0.16	5.0	--- U	--- U	--- U
13. Vinyl Acetate	0.20	50.0	--- U	--- U	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	--- U	--- U	--- U
15. 2-Butanone	0.85	100.0	--- U	--- U	--- U
16. Bromochloromethane	0.11	3.0	--- U	--- U	--- U
17. Chloroform	0.13	5.0	--- U	--- U	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U	--- U	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U	--- U	--- U
20. Benzene	0.16	1.0	--- U	--- U	--- U
21. 1,2-Dichloroethane	0.12	1.0	--- U	--- U	--- U
22. Trichloroethene	0.13	1.0	--- U	--- U	--- U
23. 1,2-Dichloropropane	0.17	1.0	--- U	--- U	--- U
24. Bromodichloromethane	0.13	1.0	--- U	--- U	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U	--- U	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U	--- U	--- U
27. Toluene	0.13	1.0	--- U	--- U	--- U
28. trans-1,3-Dichloropropene	0.14	1.0	--- U	--- U	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U	--- U	--- U
30. Tetrachloroethene	0.16	1.0	--- U	--- U	--- U
31. 2-Hexanone	1.00	50.0	--- U	--- U	--- U
32. Dibromochloromethane	0.14	3.0	--- U	--- U	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U	--- U	--- U
34. Chlorobenzene	0.13	3.0	--- U	--- U	--- U
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U	--- U	--- U
36. Ethylbenzene	0.16	1.0	--- U	--- U	--- U
37. Xylenes	0.48	5.0	--- U	--- U	--- U
38. Dibromomethane	0.17	10.0	--- U	--- U	--- U
39. Styrene	0.16	1.0	--- U	--- U	--- U
40. Bromoform	0.11	3.0	--- U	--- U	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U	--- U	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U	--- U	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	--- U	--- U	--- U
44. 1,2-Dichlorobenzene	0.13	5.0	--- U	--- U	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U	--- U	--- U
46. Acrylonitrile	1.49	200.0	--- U	--- U	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U	--- U	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

ironment 1, Inc.
Box 7085, 114 Oakmont Dr.
enville, NC 27858

ne (252) 756-6208 • Fax (252) 756-0633

CHAIN OF CUSTODY RECORD

IENT: 6040 B Week: 18

IARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
00 SOUTH 9TH STREET
ILLINGTON NC 27546

919) 233-0407

DISINFECTION: ☐ CHLORINE ☐ UV ☐ NONE ☐ _____

CHLORINE NEUTRALIZED AT COLLECTION																						
pH CHECK (LAB)																						
CONTAINER TYPE, P/G																						
CHEMICAL PRESERVATION																						
PARAMETERS																						
SAMPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS	Field pH	Metals	Turbidity	Conductivity	Temperature	Field Parameter	EPA 8260B	8260 Dup. 1	8260 Dup. 2								
							L2					L2	L2	L2								
						P	P	P	P	P		G	G	G								
						A	A	A	A	A		E	E	E								
IW-1	04 23 08	0935		18	6	G	G	G	G	G	G	G	G	G								
IW-2	04 23 08	0940		16	5	G	G	G	G	G	G	G	G									
IW-3R	04 23 08	0945		16	5	G	G	G	G	G	G	G	G									
IW-4	04 23 08	0950		15	5	G	G	G	G	G	G	G	G									
IW-5	04 23 08	0955		16	5	G	G	G	G	G	G	G	G									
IW-6	04 23 08	1000		16	5	G	G	G	G	G	G	G	G									
IW-7B	04 23 08	1020		18	5	G	G	G	G	G	G	G	G									
IW-8	04 23 08	1005		17	5	G	G	G	G	G	G	G	G									
IW-9	04 23 08	1010		17	5	G	G	G	G	G	G	G	G									
IW-10	04 23 08	1015		17	5	G	G	G	G	G	G	G	G									
IW-31	04 23 08	1120		19	6	G	G	G	G	G	G	G	G	G								

PARAMETERS: A - NONE, B - HNO_3, C - H_2SO_4, D - NAOH, E - HCL, F - ZINC ACETATE, G - NA THIOSULFATE

CLASSIFICATION:
☐ WASTEWATER (NPDES)
☐ DRINKING WATER
☐ DWQ/GW
☒ SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY: Y N

SAMPLES COLLECTED BY: (Please Print) N Lagoe / Fox

SAMPLES RECEIVED IN LAB AT 0.8 °C

RELINQUISHED BY (SIG.) (SAMPLER)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
N Lagoe	04 23 08	BC	4/23 11:40
RELINQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
RELINQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME

COMMENTS:

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested.

№ 162150

3M #5

Box 7085, 114 Oakmont Dr.
enville, NC 27858

ne (252) 756-6208 • Fax (252) 756-0633

CHAIN OF CUSTODY RECORD

IENT: 6040 B Week: 18

ARNETT CO. (DUNN/ERWIN)
ENERAL SERVICES HARNETT CO.
IR. JERRY BLANCHARD, MANAGER
00 SOUTH 9TH STREET
ILLINGTON NC 27546

)19) 233-0407

DISINFECTION
- ☐ CHLORINE
- ☐ UV
- ☐ NONE
- ☐ _____

AMPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS	Field pH	Metals	Turbidity	Conductivity	Temperature	Field Parameter	EPA 8260B	8260 Dup. 1	8260 Dup. 2
							12					12	12	
						P	P	P	P	P		G	G	G
						A	A	A	A	A		E	E	E
rip Blank					2									
quipment Blank	04 23 08				3		G					G	G	

PARAMETERS

CHLORINE NEUTRALIZED AT COLLECTION

pH CHECK (LAB)

CONTAINER TYPE, P/G

CHEMICAL PRESERVATION

A - NONE D - NAOH
B - HNO_3 E - HCL
C - H_2SO_4 F - ZINC ACETATE
G - NA THIOSULFATE

CLASSIFICATION:
- ☐ WASTEWATER (NPDES)
- ☐ DRINKING WATER
- ☐ DWQ/GW
- ☒ SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY
Y N

SAMPLES COLLECTED BY: (Please Print)
N Rose / fat

SAMPLES RECEIVED IN LAB AT 6.8 °C

INQUISHED BY (SIG.) (SAMPLER)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
N Rose	04 23 08		4/22 1:40
INQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
INQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME

COMMENTS:

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested.

№ 162149

IM #5

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 C

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/23/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	MW-16	MW23-B	MW-32	MW-33	MW-34	Analysis Date	Analyst	Method Code
PH (field measurement), Units			6.2	5.2	6.2	5.0	6.1	04/23/08	RJH	SM4500HB
Arsenic, ug/l	0.07	10.0	0.1 J	--- U	3.6 J			04/30/08	CMF	EPA200.8
Arsenic, ug/l	0.07	10.0				0.1 J	--- U	05/01/08	LFJ	EPA200.8
Barium, ug/l	0.11	100.0	61.7 J	101	105			04/30/08	CMF	EPA200.8
Barium, ug/l	0.11	100.0				59 J	42.6 J	05/01/08	LFJ	EPA200.8
Cadmium, ug/l	0.04	1.0	0.1 J	--- U	1			04/30/08	CMF	EPA200.8
Cadmium, ug/l	0.04	1.0				0.7 J	1.0	05/01/08	LFJ	EPA200.8
Total Chromium, ug/l	0.11	10.0	0.2 J	--- U	9.5 J			04/30/08	CMF	EPA200.8
Total Chromium, ug/l	0.11	10.0				--- U	--- U	05/01/08	LFJ	EPA200.8
Lead, ug/l	0.04	10.0	0.5 J	0.8 J	24			04/30/08	CMF	EPA200.8
Lead, ug/l	0.04	10.0				0.4 J	0.1 J	05/01/08	LFJ	EPA200.8
Mercury, ug/l	0.01	0.20	--- U	--- U	0.03 J			04/30/08	CMF	EPA200.8
Mercury, ug/l	0.01	0.20				0.01 J	0.01 J	05/01/08	LFJ	EPA200.8
Selenium, ug/l	0.14	10.0	--- U	--- U	0.6 J			04/30/08	CMF	EPA200.8
Selenium, ug/l	0.14	10.0				--- U	--- U	05/01/08	LFJ	EPA200.8
Silver, ug/l	0.04	10.0	--- U	--- U	0.1 J			04/30/08	CMF	EPA200.8
Silver, ug/l	0.04	10.0				--- U	0.1 J	05/01/08	LFJ	EPA200.8
Turbidity, NTU	1.0	1.0	21	37	2200	9.1	5.7	04/23/08	MDM	SM2130B
Conductivity (at 25c), uMhos	1.0	1.0	281	40	59	77	83	04/23/08	RJH	SM2510B
Temperature, °C			15	15	16	15	15	04/23/08	RJH	SM2550B
Static Water Level, feet			7.38	5.99	5.16	6.84	4.25	04/23/08	RJH	
Well Depth, feet			45.23	24.55	24.55	26.43	40.23	04/23/08	RJH	
Water Bailed, Gals.			18.3	9.3	8.7	9.3	17.4	04/23/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 C

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/23/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	MW-35	Analysis Date	Analyst	Method Code
PH (field measurement), Units			5.4	04/23/08	RJH	SM4500HB
Arsenic, ug/l	0.07	10.0	0.8 J	05/01/08	LFJ	EPA200.8
Barium, ug/l	0.11	100.0	225	05/01/08	LFJ	EPA200.8
Cadmium, ug/l	0.04	1.0	0.1 J	05/01/08	LFJ	EPA200.8
Total Chromium, ug/l	0.11	10.0	0.2 J	05/01/08	LFJ	EPA200.8
Lead, ug/l	0.04	10.0	0.7 J	05/01/08	LFJ	EPA200.8
Mercury, ug/l	0.01	0.20	--- U	05/01/08	LFJ	EPA200.8
Selenium, ug/l	0.14	10.0	1.0 J	05/01/08	LFJ	EPA200.8
Silver, ug/l	0.04	10.0	--- U	05/01/08	LFJ	EPA200.8
Turbidity, NTU	1.0	1.0	45	04/23/08	MDM	SM2130B
Conductivity (at 25c), uMhos	1.0	1.0	391	04/23/08	RJH	SM2510B
Temperature, °C			15	04/23/08	RJH	SM2550B
Static Water Level, feet			5.81	04/23/08	RJH	
Well Depth, feet			22.15	04/23/08	RJH	
Water Bailed, Gals.			7.8	04/23/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

REVIEWED BY:

CLIENT ID: 6040 C

ANALYST: MAO
DATE COLLECTED: 04/23/08
DATE ANALYZED: 05/06/08
DATE REPORTED: 05/22/08

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	MW-16	MW23-B	MW-32	MW-33	MW-34
1. Chloromethane	0.18	1.0	--- U	--- U	--- U	--- U	--- U
2. Vinyl Chloride	0.34	1.0	--- U	--- U	--- U	0.40 J	--- U
3. Bromomethane	0.26	10.0	--- U	--- U	--- U	--- U	--- U
4. Chloroethane	0.29	10.0	--- U	--- U	--- U	--- U	--- U
5. Trichlorofluoromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
6. 1,1-Dichloroethene	0.14	5.0	--- U	--- U	--- U	--- U	--- U
7. Acetone	1.21	100.0	5.50 J	5.50 J	6.10 J	6.00 J	5.90 J
8. Iodomethane	0.12	10.0	--- U	--- U	--- U	--- U	--- U
9. Carbon Disulfide	0.14	100.0	--- U	--- U	--- U	--- U	--- U
10. Methylene Chloride	0.14	1.0	--- U	--- U	--- U	0.20 J	--- U
11. trans-1,2-Dichloroethene	0.13	5.0	--- U	--- U	--- U	--- U	--- U
12. 1,1-Dichloroethane	0.16	5.0	--- U	--- U	--- U	0.70 J	--- U
13. Vinyl Acetate	0.20	50.0	--- U	--- U	--- U	--- U	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	--- U	--- U	--- U	1.60 J	--- U
15. 2-Butanone	0.85	100.0	--- U	--- U	--- U	--- U	--- U
16. Bromochloromethane	0.11	3.0	--- U	--- U	--- U	--- U	--- U
17. Chloroform	0.13	5.0	--- U	--- U	--- U	--- U	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U	--- U	--- U	--- U	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U	--- U	--- U	--- U	--- U
20. Benzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
21. 1,2-Dichloroethane	0.12	1.0	--- U	--- U	--- U	--- U	--- U
22. Trichloroethene	0.13	1.0	--- U	--- U	--- U	--- U	--- U
23. 1,2-Dichloropropane	0.17	1.0	--- U	--- U	--- U	--- U	--- U
24. Bromodichloromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U	--- U	--- U	--- U	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U	--- U	--- U	--- U	--- U
27. Toluene	0.13	1.0	--- U	--- U	--- U	--- U	--- U
28. trans-1,3-Dichloropropene	0.14	1.0	--- U	--- U	--- U	--- U	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U	--- U	--- U	--- U	--- U
30. Tetrachloroethene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
31. 2-Hexanone	1.00	50.0	--- U	--- U	--- U	--- U	--- U
32. Dibromochloromethane	0.14	3.0	--- U	--- U	--- U	--- U	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
34. Chlorobenzene	0.13	3.0	--- U	--- U	--- U	--- U	--- U
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U	--- U	--- U	--- U	--- U
36. Ethylbenzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
37. Xylenes	0.48	5.0	--- U	--- U	--- U	--- U	--- U
38. Dibromomethane	0.17	10.0	--- U	--- U	--- U	--- U	--- U
39. Styrene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
40. Bromoform	0.11	3.0	--- U	--- U	--- U	--- U	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U	--- U	--- U	--- U	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U	--- U	--- U	--- U	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	--- U	--- U	--- U	--- U	--- U
44. 1,2-Dichlorobenzene	0.13	5.0	--- U	--- U	--- U	--- U	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U	--- U	--- U	--- U	--- U
46. Acrylonitrile	1.49	200.0	--- U	--- U	--- U	--- U	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U	--- U	--- U	--- U	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

REVIEWED BY:

CLIENT ID: 6040 C

ANALYST: MAO
DATE COLLECTED: 04/23/08
DATE ANALYZED: 05/06/08
DATE REPORTED: 05/22/08

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	MW-35
1. Chloromethane	0.18	1.0	--- U
2. Vinyl Chloride	0.34	1.0	--- U
3. Bromomethane	0.26	10.0	--- U
4. Chloroethane	0.29	10.0	--- U
5. Trichlorofluoromethane	0.13	1.0	--- U
6. 1,1-Dichloroethene	0.14	5.0	--- U
7. Acetone	1.21	100.0	5.80 J
8. Iodomethane	0.12	10.0	--- U
9. Carbon Disulfide	0.14	100.0	--- U
10. Methylene Chloride	0.14	1.0	--- U
11. trans-1,2-Dichloroethene	0.13	5.0	--- U
12. 1,1-Dichloroethane	0.16	5.0	--- U
13. Vinyl Acetate	0.20	50.0	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	--- U
15. 2-Butanone	0.85	100.0	--- U
16. Bromochloromethane	0.11	3.0	--- U
17. Chloroform	0.13	5.0	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U
20. Benzene	0.16	1.0	--- U
21. 1,2-Dichloroethane	0.12	1.0	--- U
22. Trichloroethene	0.13	1.0	--- U
23. 1,2-Dichloropropane	0.17	1.0	--- U
24. Bromodichloromethane	0.13	1.0	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U
27. Toluene	0.13	1.0	--- U
28. trans-1,3-Dichloropropene	0.14	1.0	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U
30. Tetrachloroethene	0.16	1.0	--- U
31. 2-Hexanone	1.00	50.0	--- U
32. Dibromochloromethane	0.14	3.0	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U
34. Chlorobenzene	0.13	3.0	--- U
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U
36. Ethylbenzene	0.16	1.0	--- U
37. Xylenes	0.48	5.0	--- U
38. Dibromomethane	0.17	10.0	--- U
39. Styrene	0.16	1.0	--- U
40. Bromoform	0.11	3.0	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	--- U
44. 1,2-Dichlorobenzene	0.13	5.0	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U
46. Acrylonitrile	1.49	200.0	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

. Box 7085, 114 Oakmont Dr.
enville, NC 27858

ne (252) 756-6208 • Fax (252) 756-0633

CHAIN OF CUSTODY RECORD

Page 1 of 1

IENT: 6040 C Week: 18

IARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
00 SOUTH 9TH STREET
LLINGTON NC 27546

919) 233-0407

DISINFECTION
- [ ] CHLORINE
- [ ] UV
- [ ] NONE
- [ ] _____

																						CHLORINE NEUTRALIZED AT COLLECTION
								12					12	12	12							pH CHECK (LAB)
								P	P	P	P	P		G	G	G						CONTAINER TYPE, P/G
								A	A	A	A	A		E	E	E						CHEMICAL PRESERVATION
AMPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS	Field pH	Metals	Turbidity	Conductivity	Temperature	Field Parameter	EPA 8260B	8260 Dup. 1	8260 Dup. 2								PARAMETERS
IW-16	04 23 08	0910		15	6	G	G	G	G	G	G	G	G	G								
IW23-B	04 23 08	1040		15	5	G	G	G	G	G	G	G	G									
IW-32	04 23 08	0840		16	5	G	G	G	G	G	G	G	G									
IW-33	04 23 08	0855		15	5	G	G	G	G	G	G	G	G									
IW-34	04 23 08	0845		15	5	G	G	G	G	G	G	G	G									
IW-35	04 23 08	0905		15	5	G	G	G	G	G	G	G	G									

A - NONE D - NAOH
B - HNO_3 E - HCL
C - H_2SO_4 F - ZINC ACETATE
G - NA THIOSULFATE

CLASSIFICATION:
- [ ] WASTEWATER (NPDES)
- [ ] DRINKING WATER
- [ ] DWQ/GW
- [X] SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY
✓ N

SAMPLES COLLECTED BY: (Please Print) Hope Fox

SAMPLES RECEIVED IN LAB AT 0-8 °C

NQUISHED BY (SIG.) (SAMPLER)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
Hope	04 23 08		4/23 1:40
NQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
NQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME

COMMENTS:

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested.

M #5

№ 162148

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 E

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/22/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	Piezometer #41S	Piezometer #44S	Piezometer #44D	Piezometer #46D	Piezometer #47S	Analysis Date	Analyst	Method Code
Static Water Level, feet			14.20	2.87	11.09	29.22	5.03	04/22/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 E

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/22/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	Piezometer #47D	Piezometer #48S	Pizeometer #50	Piezometer #51	Piezometer #52	Analysis Date	Analyst	Method Code
Static Water Level, feet			27.11	14.68	14.76	10.53	18.41	04/22/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 E

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/22/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	Piezometer #53	GP-24-W	GP-25-W	GP-27-W	GP-28-W	Analysis Date	Analyst	Method Code
Static Water Level, feet			16.25	8.54	7.85	13.82	11.26	04/22/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 E

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/22/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	GP-30-W	GP-31-W	GP-33-W	GP-34-W	GP-35-W	Analysis Date	Analyst	Method Code
Static Water Level, feet			14.00	9.23	19.00	15.94	4..21	04/22/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37713
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 E

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/22/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	GP-36-W	GP-37-W	GP-38-W	Analysis Date	Analyst	Method Code
Static Water Level, feet			18.19	8.19	16.06	04/22/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

REVIEWED BY:

CLIENT ID: 6040 E

ANALYST: MAO
DATE COLLECTED: 04/22/08
DATE ANALYZED: 05/02/08
DATE REPORTED: 05/22/08

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	Piezometer #41S	GP-25-W	GP-30-W	GP-37-W	GP-38-W
1. Chloromethane	0.18	1.0	0.20 J	--- U	--- U	--- U	--- U
2. Vinyl Chloride	0.34	1.0	--- U	--- U	--- U	--- U	1.50
3. Bromomethane	0.26	10.0	--- U	--- U	--- U	--- U	--- U
4. Chloroethane	0.29	10.0	--- U	--- U	--- U	--- U	1.30 J
5. Trichlorofluoromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
6. 1,1-Dichloroethene	0.14	5.0	--- U	--- U	--- U	--- U	--- U
7. Acetone	1.21	100.0	5.00 J	9.30 J	8.80 J	5.80 J	4.40 J
8. Iodomethane	0.12	10.0	--- U	--- U	--- U	--- U	--- U
9. Carbon Disulfide	0.14	100.0	--- U	--- U	--- U	--- U	--- U
10. Methylene Chloride	0.14	1.0	0.50 J	--- U	--- U	--- U	0.40 J
11. trans-1,2-Dichloroethene	0.13	5.0	--- U	--- U	--- U	--- U	0.20 J
12. 1,1-Dichloroethane	0.16	5.0	0.50 J	--- U	--- U	3.90 J	2.00 J
13. Vinyl Acetate	0.20	50.0	--- U	--- U	--- U	--- U	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	0.30 J	--- U	--- U	--- U	18.30
15. 2-Butanone	0.85	100.0	--- U	--- U	1.40 J	--- U	--- U
16. Bromochloromethane	0.11	3.0	--- U	--- U	--- U	--- U	--- U
17. Chloroform	0.13	5.0	--- U	--- U	--- U	--- U	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U	--- U	--- U	--- U	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U	--- U	--- U	--- U	--- U
20. Benzene	0.16	1.0	0.20 J	--- U	--- U	--- U	3.60
21. 1,2-Dichloroethane	0.12	1.0	--- U	--- U	--- U	--- U	--- U
22. Trichloroethene	0.13	1.0	0.20 J	--- U	--- U	--- U	3.10
23. 1,2-Dichloropropane	0.17	1.0	--- U	--- U	--- U	--- U	--- U
24. Bromodichloromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U	--- U	--- U	--- U	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U	--- U	--- U	--- U	--- U
27. Toluene	0.13	1.0	--- U	--- U	--- U	--- U	--- U
28. trans-1,3-Dichloropropene	0.14	1.0	--- U	--- U	--- U	--- U	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U	--- U	--- U	--- U	--- U
30. Tetrachloroethene	0.16	1.0	--- U	--- U	--- U	0.20 J	1.10
31. 2-Hexanone	1.00	50.0	--- U	--- U	--- U	--- U	--- U
32. Dibromochloromethane	0.14	3.0	--- U	--- U	--- U	--- U	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
34. Chlorobenzene	0.13	3.0	--- U	--- U	--- U	--- U	--- U
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U	--- U	--- U	--- U	--- U
36. Ethylbenzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
37. Xylenes	0.48	5.0	--- U	--- U	--- U	--- U	--- U
38. Dibromomethane	0.17	10.0	--- U	--- U	--- U	--- U	--- U
39. Styrene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
40. Bromoform	0.11	3.0	--- U	--- U	--- U	--- U	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U	--- U	--- U	--- U	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U	--- U	--- U	--- U	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	--- U	--- U	--- U	--- U	0.30 J
44. 1,2-Dichlorobenzene	0.13	5.0	--- U	--- U	--- U	--- U	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U	--- U	--- U	--- U	--- U
46. Acrylonitrile	1.49	200.0	--- U	--- U	--- U	--- U	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U	--- U	--- U	--- U	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

ronment 1, Inc.
Box 7085, 114 Oakmont Dr.
nville, NC 27858

ne (252) 756-6208 • Fax (252) 756-0633

CHAIN OF CUSTODY RECORD

IENT: 6040 E Week: 18

ARNETT CO. (DUNN/ERWIN)
ENERAL SERVICES HARNETT CO.
IR. JERRY BLANCHARD, MANAGER
00 SOUTH 9TH STREET
ILLINGTON NC 27546

19) 233-0407

DISINFECTION
- [ ] CHLORINE
- [ ] UV
- [ ] NONE
- [ ] _____

																						CHLORINE NEUTRALIZED AT COLLECTION
								12	12	12												pH CHECK (LAB)
								G	G	G												CONTAINER TYPE, P/G
								E	E	E												CHEMICAL PRESERVATION
MPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS	Field Parameter	EPA 8260B	8260 Dup. 1	8260 Dup. 2													PARAMETERS
ezometer #41S	04 22 08	0925			4																	
ezometer #44S	04 22 08				1																	
ezometer #44D	04 22 08				1																	
ezometer #46D	04 22 08				1																	
ezometer #47S	04 22 08				1																	
ezometer #47D	04 22 08				1																	
ezometer #48S	04 22 08				1																	
zeometer #50	04 22 08				1																	
iezometer #51	04 22 08				1																	
iezometer #52	04 22 08				1																	
iezometer #53	04 22 08				1																	

A - NONE D - NAOH
B - HNO_3 E - HCL
C - H_2SO_4 F - ZINC ACETATE
G - NA THIOSULFATE

CLASSIFICATION:
- [ ] WASTEWATER (NPDES)
- [ ] DRINKING WATER
- [ ] DWQ/GW
- [X] SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY
Y N

SAMPLES COLLECTED BY: (Please Print)
N Cole / Fox

SAMPLES RECEIVED IN LAB AT 0.2 °C

NQUISHED BY (SIG.) (SAMPLER)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
N Cole	04 22 08		4/22 3:36
NQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
NQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME

COMMENTS:

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested.

№ 162147

M #5

. Box 7085, 114 Oakmont Dr.
enville, NC 27858

ne (252) 756-6208 • Fax (252) 756-0633

CHAIN OF CUSTODY RECORD

IENT: 6040 E **Week: 18**

IARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
00 SOUTH 9TH STREET
ILLINGTON NC 27546

919) 233-0407

DISINFECTION: ☐ CHLORINE ☐ UV ☐ NONE ☐ _____

																				CHLORINE NEUTRALIZED AT COLLECTION
							L2	L2	L2											pH CHECK (LAB)
							G	G	G											CONTAINER TYPE, P/G
							E	E	E											CHEMICAL PRESERVATION
SAMPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS	Field Parameter	EPA 8260B	8260 Dup. 1	8260 Dup. 2											PARAMETERS
P-24-W	04 22 08				1	C														
P-25-W	04 22 08	1135			3	C	C	C												
P-27-W	04 22 08				1	C														
P-28-W	04 22 08				1	C														
P-30-W	04 22 08	0955			3	C	C	C												
P-31-W	04 22 08				1	C														
P-33-W	04 22 08				1	C														
P-34-W	04 22 08				1	C														
P-35-W	04 22 08				1	C														
P-36-W	04 22 08				1	C														
P-37-W	04 22 08	1130			3	C	C	C												

A - NONE D - NAOH
B - HNO_3 E - HCL
C - H_2SO_4 F - ZINC ACETATE
G - NA THIOSULFATE

CLASSIFICATION:
☐ WASTEWATER (NPDES)
☐ DRINKING WATER
☐ DWQ/GW
☒ SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY: (Y) N

SAMPLES COLLECTED BY: (Please Print) H Lagoe / Fox

SAMPLES RECEIVED IN LAB AT 0 °C

INQUISHED BY (SIG.) (SAMPLER)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
H Lagoe	04 22 08		4/22 934
INQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
INQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME

COMMENTS:

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested.

№ 162146

M #5

CHAIN OF CUSTODY RECORD

Box 7085, 114 Oakmont Dr.
enville, NC 27858

ne (252) 756-6208 • Fax (252) 756-0633

IENT: 6040 E Week: 18

IARNETT CO. (DUNN/ERWIN)
ENERAL SERVICES HARNETT CO.
IR. JERRY BLANCHARD, MANAGER
00 SOUTH 9TH STREET
ILLINGTON NC 27546

919) 233-0407

DISINFECTION
- [ ] CHLORINE
- [ ] UV
- [ ] NONE
- [ ] _____

																				CHLORINE NEUTRALIZED AT COLLECTION
						1212														pH CHECK (LAB)
						G	G	G												CONTAINER TYPE, P/G
						E	E	E												CHEMICAL PRESERVATION
SAMPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS	Field Parameter	EPA 8260B	8260 Dup. 1	8260 Dup. 2											PARAMETERS
P-38-W	04/22/08	1300			3	G	G	G												

A - NONE D - NAOH
B - HNO_3 E - HCL
C - H_2SO_4 F - ZINC ACETATE
G - NA THIOSULFATE

CLASSIFICATION:
- [ ] WASTEWATER (NPDES)
- [ ] DRINKING WATER
- [ ] DWQ/GW
- [x] SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY
(Y) N

SAMPLES COLLECTED BY:
(Please Print)
N Roe Fo

SAMPLES RECEIVED IN LAB AT 6.2 °C

	DATE/TIME			DATE/TIME
NQUISHED BY (SIG.) (SAMPLER) N Roe	04/22/08	RECEIVED BY (SIG.)	4/22	3:05
NQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)		DATE/TIME
NQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)		DATE/TIME

COMMENTS:

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested.

№ 162145

M #5

Environment 1, Incorporated

Drinking Water ID: 37715
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

ID#: 6040 F

HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON ,NC 27546

DATE COLLECTED: 04/23/08
DATE REPORTED : 05/22/08

REVIEWED BY:

PARAMETERS	MDL	SWSL	MW-11	MW-12	MW-13	MW-14	MW-15	Analysis Date	Analyst	Method Code
PH (field measurement), Units			5.1	5.2	6.1	5.6	5.1	04/23/08	RJH	SM4500HB
Antimony, ug/l	0.08	6.0	0.1 J	--- U	0.5 J	0.1 J	0.1 J	05/01/08	LFJ	EPA200.8
Arsenic, ug/l	0.07	10.0	--- U	--- U	0.1 J	0.1 J	1.6 J	05/01/08	LFJ	EPA200.8
Barium, ug/l	0.11	100.0	17.7 J	42.2 J	82.8 J	47.3 J	32.7 J	05/01/08	LFJ	EPA200.8
Beryllium, ug/l	0.06	1.0	0.2 J	1.5	0.3 J	0.6 J	--- U	05/01/08	LFJ	EPA200.8
Cadmium, ug/l	0.04	1.0	0.1 J	0.1 J	0.1 J	0.1 J	0.2 J	05/01/08	LFJ	EPA200.8
Cobalt, ug/l	0.03	10.0	0.6 J	0.8 J	1.6 J	0.7 J	1.2 J	05/01/08	LFJ	EPA200.8
Copper, ug/l	0.05	10.0	1.4 J	2.7 J	1.1 J	1.3 J	0.9 J	05/01/08	LFJ	EPA200.8
Total Chromium, ug/l	0.11	10.0	0.9 J	0.2 J	0.3 J	0.5 J	0.2 J	05/01/08	LFJ	EPA200.8
Lead, ug/l	0.04	10.0	2.1 J	1.8 J	1.2 J	1.7 J	0.7 J	05/01/08	LFJ	EPA200.8
Nickel, ug/l	0.06	50.0	--- U	0.2 J	0.2 J	0.2 J	0.7 J	05/01/08	LFJ	EPA200.8
Selenium, ug/l	0.14	10.0	0.4 J	--- U	--- U	0.2 J	--- U	05/01/08	LFJ	EPA200.8
Silver, ug/l	0.04	10.0	0.1 J	0.1 J	0.1 J	--- U	--- U	05/01/08	LFJ	EPA200.8
Thallium, ug/l	0.04	5.0	0.1 J	--- U	0.1 J	--- U	--- U	05/01/08	LFJ	EPA200.8
Vanadium, ug/l	0.07	25.0	1.9 J	2.8 J	1.9 J	2.9 J	1.8 J	05/01/08	LFJ	EPA200.8
Zinc, ug/l	0.04	10.0	6.5 J	8.5 J	6.0 J	8.7 J	8.3 J	05/01/08	LFJ	EPA200.8
Turbidity, NTU	1.0	1.0	50	220	45	85	16	04/23/08	MDM	SM2130B
Conductivity (at 25c), uMhos	1.0	1.0	68	70	154	112	70	04/23/08	RJH	SM2510B
Temperature, °C			16	15	16	16	15	04/23/08	RJH	SM2550B
Static Water Level, feet			17.42	6.23	24.79	7.30	7.48	04/23/08	RJH	
Well Depth, feet			27.60	16.30	25.77	29.92	14.55	04/23/08	RJH	
Water Bailed, Gals.			4.8	7.8	12.0	10.5	3.6	04/23/08	RJH	

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

Environment 1, Incorporated

Drinking Water ID: 37716
Wastewater ID: 10

P.O. BOX 7085, 114 OAKMONT DRIVE
GREENVILLE, N.C. 27835-7085

PHONE (252) 756-6208
FAX (252) 756-0633

CLIENT: HARNETT CO. (DUNN/ERWIN)
GENERAL SERVICES HARNETT CO.
MR. JERRY BLANCHARD, MANAGER
900 SOUTH 9TH STREET
LILLINGTON, NC 27546

CLIENT ID: 6040 F

ANALYST: MAO
DATE COLLECTED: 04/23/08
DATE REPORTED: 05/22/08

REVIEWED BY:

VOLATILE ORGANICS
EPA METHOD 8260B

PARAMETERS, ug/l	MDL	SWSL	05/06/08 MW-11	05/07/08 MW-12	05/07/08 MW-13	05/07/08 MW-14	05/07/08 MW-15
	Date Analyzed:						
1. Chloromethane	0.18	1.0	--- U	--- U	--- U	--- U	--- U
2. Vinyl Chloride	0.34	1.0	--- U	--- U	--- U	--- U	--- U
3. Bromomethane	0.26	10.0	--- U	--- U	--- U	--- U	--- U
4. Chloroethane	0.29	10.0	--- U	--- U	--- U	--- U	--- U
5. Trichlorofluoromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
6. 1,1-Dichloroethene	0.14	5.0	--- U	--- U	--- U	--- U	--- U
7. Acetone	1.21	100.0	5.00 J	6.90 J	6.70 J	5.50 J	23.00 J
8. Iodomethane	0.12	10.0	--- U	--- U	--- U	--- U	--- U
9. Carbon Disulfide	0.14	100.0	--- U	--- U	--- U	--- U	--- U
10. Methylene Chloride	0.14	1.0	--- U	--- U	--- U	--- U	--- U
11. trans-1,2-Dichloroethene	0.13	5.0	--- U	--- U	--- U	--- U	--- U
12. 1,1-Dichloroethane	0.16	5.0	--- U	--- U	--- U	--- U	--- U
13. Vinyl Acetate	0.20	50.0	--- U	--- U	--- U	--- U	--- U
14. Cis-1,2-Dichloroethene	0.14	5.0	--- U	--- U	--- U	--- U	--- U
15. 2-Butanone	0.85	100.0	--- U	--- U	--- U	--- U	1.70 J
16. Bromochloromethane	0.11	3.0	--- U	--- U	--- U	--- U	--- U
17. Chloroform	0.13	5.0	--- U	--- U	--- U	--- U	--- U
18. 1,1,1-Trichloroethane	0.11	1.0	--- U	--- U	--- U	--- U	--- U
19. Carbon Tetrachloride	0.13	1.0	--- U	--- U	--- U	--- U	--- U
20. Benzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
21. 1,2-Dichloroethane	0.12	1.0	--- U	--- U	--- U	--- U	--- U
22. Trichloroethene	0.13	1.0	--- U	--- U	--- U	--- U	--- U
23. 1,2-Dichloropropane	0.17	1.0	--- U	--- U	--- U	--- U	--- U
24. Bromodichloromethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
25. Cis-1,3-Dichloropropene	0.17	1.0	--- U	--- U	--- U	--- U	--- U
26. 4-Methyl-2-Pentanone	0.68	100.0	--- U	--- U	--- U	--- U	3.00 J
27. Toluene	0.13	1.0	--- U	--- U	--- U	--- U	4.50
28. trans-1,3-Dichloropropene	0.14	1.0	--- U	--- U	--- U	--- U	--- U
29. 1,1,2-Trichloroethane	0.20	1.0	--- U	--- U	--- U	--- U	--- U
30. Tetrachloroethene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
31. 2-Hexanone	1.00	50.0	--- U	--- U	--- U	--- U	--- U
32. Dibromochloromethane	0.14	3.0	--- U	--- U	--- U	--- U	--- U
33. 1,2-Dibromoethane	0.13	1.0	--- U	--- U	--- U	--- U	--- U
34. Chlorobenzene	0.13	3.0	--- U	--- U	--- U	--- U	--- U
35. 1,1,1,2-Tetrachloroethane	0.14	5.0	--- U	--- U	--- U	--- U	--- U
36. Ethylbenzene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
37. Xylenes	0.48	5.0	--- U	--- U	--- U	--- U	--- U
38. Dibromomethane	0.17	10.0	--- U	--- U	--- U	--- U	--- U
39. Styrene	0.16	1.0	--- U	--- U	--- U	--- U	--- U
40. Bromoform	0.11	3.0	--- U	--- U	--- U	--- U	--- U
41. 1,1,2,2-Tetrachloroethane	0.16	3.0	--- U	--- U	--- U	--- U	--- U
42. 1,2,3-Trichloropropane	0.06	1.0	--- U	--- U	--- U	--- U	--- U
43. 1,4-Dichlorobenzene	0.21	1.0	--- U	--- U	--- U	--- U	--- U
44. 1,2-Dichlorobenzene	0.13	5.0	--- U	--- U	--- U	--- U	--- U
45. 1,2-Dibromo-3-Chloropropane	0.26	13.0	--- U	--- U	--- U	--- U	--- U
46. Acrylonitrile	1.49	200.0	--- U	--- U	--- U	--- U	--- U
47. trans-1,4-Dichloro-2-Butene	0.14	100.0	--- U	--- U	--- U	--- U	--- U

J = Between MDL and SWSL, U = Below ALL Quanititation Limits.

...ronment 1, Inc.
Box 7085, 114 Oakmont Dr.
nville, NC 27858
ie (252) 756-6208 • Fax (252) 756-0633

CHAIN OF CUSTODY RECORD

IENT: 6040 F **Week: 18**

ARNETT CO. (DUNN/ERWIN)
ENERAL SERVICES HARNETT CO.
R. JERRY BLANCHARD, MANAGER
)0 SOUTH 9TH STREET
LLINGTON NC 27546

19) 233-0407

DISINFECTION: ☐ CHLORINE ☐ UV ☐ NONE ☐ ______

															CHLORINE NEUTRALIZED AT COLLECTION
						𝒱					𝒱	𝒱	𝒱		pH CHECK (LAB)
					P	P	P	P	P		G	G	G		CONTAINER TYPE, P/G
					A	A	A	A	A		E	E	E		CHEMICAL PRESERVATION
MPLE LOCATION	COLLECTION DATE	COLLECTION TIME	TOTAL CHLORINE, mg/l AT COLLECTION	TEMPERATURE, °C AT COLLECTION	# OF CONTAINERS	Field pH	Metals	Turbidity	Conductivity	Temperature	Field Parameter	EPA 8260B	8260 Dup. 1	8260 Dup. 2	PARAMETERS
W-11	04 23 08	1030		16	6	G	G	G	G	G	G	G	G	G	
W-12	04 23 08	1045		15	5	G	G	G	G	G	G	G	G		
W-13	04 23 08	1035		16	5	G	G	G	G	G	G	G	G		
W-14	04 23 08	1050		16	5	G	G	G	G	G	G	G	G		
W-15	04 23 08	1100		15	5	G	G	G	G	G	G	G	G		

CHEMICAL PRESERVATION: A - NONE; B - HNO_3; C - H_2SO_4; D - NAOH; E - HCL; F - ZINC ACETATE; G - NA THIOSULFATE

CLASSIFICATION:
☐ WASTEWATER (NPDES)
☐ DRINKING WATER
☐ DWQ/GW
☒ SOLID WASTE SECTION

CHAIN OF CUSTODY MAINTAINED DURING SHIPMENT/DELIVERY (Y) N

SAMPLES COLLECTED BY: (Please Print) H Gore / Fox

SAMPLES RECEIVED IN LAB AT 0.3 °C

IQUISHED BY (SIG.) (SAMPLER)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
B H Gore	042308	BG	4/23 1:40
IQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME
IQUISHED BY (SIG.)	DATE/TIME	RECEIVED BY (SIG.)	DATE/TIME

COMMENTS:

Instructions for completing this form are on the reverse side.

Sampler must place a "C" for composite sample or a "G" for Grab sample in the blocks above for each parameter requested

№ 162144

1 #5