

Scanned by | Date | Doc ID # | Fnesy | 2 | 13 | 168 | RCO 3930

RECEIVED

FEB 11 2008

SOLID WASTE SECTION
ASHEVILLE REGIONAL OFFICE

February 8, 2008

Mr. Stan Steury Program Manager ASU Energy Center Appalachian State University 130 Poplar Grove Road Connector Boone, North Carolina 28608

Reference:

Methane Extraction Test - PO #0003227

Former McDowell County Landfill Transfer Station Permit #5602T

Dear Mr. Steury:

Shield Engineering, Inc. (Shield) is pleased to submit this letter report summarizing our work related to the findings associated with the initial methane field investigation, the installation of the three methane extraction wells, and the subsequent execution of a methane extraction test on the former McDowell County Landfill. Shield was subcontracted by Appalachian State University (ASU) Energy Center to install three methane extraction wells and perform a methane extraction test for a period of 48-hours. In so doing, Shield had proposed a preliminary investigation of the landfill to determine the optimum locations for the three proposed methane extraction wells.

The former McDowell County landfill is located adjacent to a permitted Transfer Station referenced above, just off NC Highway 226, south of the I-40. This landfill was operational during the 1970s through to final closure in 1994. ASU recently approached McDowell County in regard to assessing the methane potential at this landfill for possible use as a source for renewable energy for businesses located in the area around the landfill.

The preliminary investigation proposed by Shield consisted of performing a series of Geoprobe boreholes to determine the presence of methane immediately below the landfill cover. These 68 boreholes were laid out on an approximate 100' x 100' grid pattern as shown on Figure 1. The landfill cover was found to consist of tan micaeous fine to medium sandy silt and exhibited varying thicknesses across the landfill, ranging from 2 up to 10 feet thick. The average thickness of the landfill cover is 4.1 feet. A map of the landfill cover thickness is shown on Figure 2. The landfill cover thickness was thinner along the southern side of the landfill (see Figure 2).

Following the completion of each of the borings the percentage of methane in air was measured using a LandTec GEM-500 portable gas analyzer. The percentage of methane in air readings for the former McDowell County Landfill is shown on Figure 3. The percentage of methane in air ranged from 3.8 to 64.8% across the landfill, with an average methane percentage of 40.7%. Following the recording of each methane measurement, each borehole was backfilled with a bentonite slurry mix to seal the landfill cover.



The waste found in these borings, beneath the landfill cover, ranged from paper, textiles, wood, cardboard, plastic, foam rubber, asphalt, concrete, etc. The most commonly encountered waste in these borings was plastic, paper, and wood debris. Based on the methane readings collected from these shallow borings, three locations were proposed to ASU for the installation of a methane extraction well. With ASU concurrence these three sites were selected for the installation of a methane extraction well.

The three methane extraction wells were drilled by Kellett Drilling of Simpsonville, South Carolina from December 14 to 18, 2007. These three extraction wells were drilled as a 36-inch diameter borehole, with a 6-inch diameter perforated PVC screen installed to the total depth with a PVC casing up to ground surface. The methane extraction wells installed were labeled from MDW-1 through MDW-3 and their locations are shown on Figure 3. The waste encountered in these three extraction wells consisted of a mix of paper, wood, textiles, plastic, etc. There was preponderance of textile material in the form of spools of thread immediately below the landfill cover at MDW-2. Additionally, there was appreciably more plastic (e.g., IV bags) found in MDW-3 compared to the other two wells.

Each methane extraction well was drilled down to a total depth at the water table for each of the locations shown. The total depth at MDW-1 was 47 feet below ground surface. The total depths at MDW-2 and MDW-3 were 33 and 31 feet below ground surface, respectively. The depth to ground water in MDW-1 was 34 feet below ground surface, in MDW-2 the depth to ground water was 21 feet, and 13 feet in MDW-3. The top of the perforated casings were about 7 feet below ground surface. A two-foot thick bentonite seal was installed about two feet above each of the PVC screens and then a second bentonite seal was installed at a depth corresponding to the bottom of the landfill cover at each location. The landfill cover in northern area of the landfill at MDW-1 was about 5 feet, MDW-2 about 4 feet, and MDW-3 is about 2 feet.

The methane extraction test was setup with temporary flexible vacuum hoses running along the top of the landfill ground surface from each of the three extraction wells to a central location near MDW-2, where a skid-mounted vacuum pump and generator were located. Each of the dedicated vacuum hoses was combined at a manifold, next to the vacuum pump equipment. The manifold included vacuum gages and valves. A knock-out tank was included at the inflow point to these two units. Each methane extraction well was equipped with a LandTec Accu-Flow Wellhead. These wellheads were designed to reduce the gas flow from a 6-inch diameter well down to a 2-inch pipe with an access port for measuring the gas flow rate and simultaneously allowing the collection of the methane gas data using a LandTec GEM-500 gas analyzer.

The methane extraction test commenced at 10:30 a.m. on December 19, 2007 and was continued through a methane recovery phase ending at 1:40 p.m. on December 21, 2007. Since the optimum vacuum and methane extraction rates for this landfill were unknown, the test was commenced with a vacuum of 65 inches of water at the vacuum pump. Due to inherent line losses and friction losses, the wellhead vacuums ranged from 31 to 33 inches of water as shown in Table 1. The methane percentage was monitored at each extraction wellhead throughout the test. Additionally, the gas flow rate, other gas percentages, thermal value of gas, and temperature were also monitored through out the methane extraction test. These data are exhibited in Tables 2 through 4 for each of the methane extraction wells. The gas flow rates for the duration of the methane extraction test for each methane extraction well are shown in Figure 4. The mix of different gases during the methane



extraction test is shown for each extraction well for the duration of the test on Figures 5 through 7. The component labeled "other gases" shown on Figures 5 through 7 consist of nitrogen, ammonia, alcohols, hydrogen, volatile organic compounds, and other miscellaneous trace gases.

Unfortunately, the vacuum to each of the wellheads was impacted due to freezing of moisture within the vacuum lines causing blockages along these lines during the night of December 19-20, and especially in the early morning of December 20, 2007 as evidenced in Table 1 and Figure 4. The vacuum readings on the pump and at each of the wellheads started rising at midnight and continued to rise to a peak value in the early morning. The ice blockages were dislodged from the vacuum lines in the early morning, and the vacuum line to MDW-3 had to be completely broken down into separate hose lengths in order to dislodge the ice. The complete system was able to get back to a stable equilibrium after 11:00 a.m. Subsequently, the system was able to maintain stable conditions for the remainder of the test (see Figure 4). Table 1 includes the average vacuum pressures for the stable portion of the extraction test from 1:30 p.m. through to the following morning of December 21, 2007. The data for each of the methane extraction wells (see Tables 2 through 4) also exhibit stable conditions from 1:30 p.m. through to the following morning of December 21, 2007 for the methane extraction test. Average values for the main parameters are exhibited at the bottom of each table for this period of time. Hence the average vacuum pressures at the wellhead for each of the extraction wells ranged from 40.2 to 42 inches of water.

The methane extraction test did attain a good steady state condition for the last 18 hours of the test (see Figures 5 through 7). As a result the vacuum pump was discontinued at 8:00 a.m. December 21, 2007 in order to assess the rebound conditions for the landfill in terms of attaining previous methane production rates following the shutdown. The rebound conditions of each extraction well are evident in Figures 8 through 10. Methane Extraction Well MDW-1 attained similar methane production rates 5 hours after shutdown, MDW-2 took 6 hours, and MDW-3 took about 5 hours. The average methane production in MDW-1 for the latter portion of the test was 17% of methane in air at a flow rate of 40 standard cubic feet per minute (scfm). The average methane production in MDW-2 for the latter portion of the test was 3.7% of methane in air at a flow rate of 53 scfm. The average methane production in MDW-3 for the latter portion of the test was 1.5% of methane in air at a flow rate of 65 scfm. Varying leakage or short-circuiting from the atmosphere into each of the methane extraction wells was evident based on the oxygen data for the three extraction wells. The landfill cover was a fine to medium sandy silt which also varied in thickness across the landfill. Such a soil is relatively pervious and the thickness of unsaturated waste capable of producing methane decreased in each extraction well, from MDW-1 through to MDW-3. The results of the methane extraction test indicate that the vacuum pressures were higher than ideal for the specific situation at the McDowell County Landfill. As required within the original request for proposal (RFQ), the methane extraction test was conducted as a constant-rate test and not as a stepped vacuum test. Therefore, once the test commenced the system variables were maintained as much as possible at the same constant settings. However, based on our review of the test data, if the test was run as a variable rate test that would have enabled the variation of the vacuum at each of the wellheads. Thus, the gas flow from the wells would have been fine-tuned so that they would be commensurate with their ability to produce methane at higher percentage rates of methane in air at lower flow rates.

An air sample was collected on the evening of December 20, 2007 and shipped to Research Triangle Park Laboratories, Inc for analysis of siloxanes, volatile organic compounds, methane,



hydrogen, carbon dioxide, nitrogen, oxygen, reduced sulfur, hydrogen sulfur and sulfur compounds. The results of this analysis are attached. The siloxanes are important in regard to wear and tear on using electrical generating engines such as microturbines or reciprocating engines. Numerous manufacturers are now requiring the removal of siloxanes in the application of their engines for generation. otherwise warranties may be voided. Only (octamethylcyclotetrasiloxane - D4) was identified in the air sample at a concentration of 14.8 parts per billion per 20 liter volume (ppbv). This concentration is low compared to some of the engine warranty requirements. Typically the D4 siloxane is the largest contributor to the total siloxane concentration, and landfills with older wastes usually have lower siloxane concentrations. Other constituents that were identified were hydrogen sulfide at a concentration of 2.4 parts per million per 20 liter volume (ppmv) and numerous volatile organic constituents (see attached analytical laboratory report).

The power production potential for each methane extraction well is shown on each of Tables 2 through 4. The power production variation over the duration of the methane extraction test is shown for each of the extraction wells in Figures 11 through 13. The power potential as measured during the latter stable portion of the test was 124 kilowatts for MDW-1, 35 kilowatts for MDW-2, and 17 kilowatts for MDW-3. A combination of thin landfill cover and less unsaturated thickness of waste contributed to the variation of power potential for these three extraction wells.

A review of the former McDowell County Landfill was made in the context of methane percentage measured under the landfill cover (see Figure 3) and cover thickness (see Figure 2) in order to identify optimum areas of the landfill for possible development of a methane collection and extraction system. The area slated for possible development of a methane collection and extraction system is outlined on Figure 14. An area of approximately 8 acres was identified for exploitation of the potential methane resources within this landfill. Based on the literature (well spacing ranges upward from 200 feet) and the EPA assumption for their interactive landfill gas model of one well per acre (equivalent to a well spacing of 210 feet) a methane collection system is feasible at this landfill consisting of a total of 9 methane extraction wells. Hence, if the decision was made to proceed with methane recovery, Shield would recommend a series of 7 additional methane extraction wells for installation at the landfill at the locations shown on Figure 14. The optimum vacuum for operating such a methane collection system would be about 60 inches of water, with vacuum reducing valves at each wellhead in order to optimize the methane percentages with lower gas flow rates from each well. This setup would permit the fine-tuning of the system, so that the operation of the vacuum system is commensurate with the ability of the waste in the vicinity of the respective well locations to sustain a flow of methane and simultaneously maintain as high a methane percentage as feasible. In so doing this optimization of methane flow from each extraction well will permit system operations to compensate for both the limited thicknesses of the unsaturated waste, especially in the southwestern area of the landfill (i.e., as evidenced in MDW-2, and particularly in MDW-3) and the poor confining capabilities of the landfill cover.

The potential power production from a series of 9 methane extraction wells located the former McDowell County Landfill may be estimated from the power production rates exhibited during the methane extraction test from MDW-1 and MDW-2. Therefore, assuming that about five of the extraction wells are capable of producing at least 100 kilowatts each and the remaining four extraction wells are capable of producing about 30 kilowatts each, then the total power production



from the proposed methane collection system would be as much as 620 kilowatts. This power is equivalent to 105 scfm of 33% methane gas in air or 35 scfm of 100% methane gas.

The projected demand in the vicinity of the landfill is approximately 21 scfm of methane gas for 10 years for International Timber & Lumber, Inc. (ITL), and 30 scfm of methane gas for a proposed animal processing facility. Hence, assuming these projected demands are constant, the estimated methane production from the proposed methane extraction well network will be capable of meeting the demand for either ITL or the proposed animal processing facility. The capability of the proposed methane extraction system to meet both of the projected demands is dependent on the gas demand schedule for ITL and the proposed animal processing facility.

We sincerely appreciate the opportunity to provide you with this submittal. Should you have any questions, please contact Dave Wallace either by telephone at (704)-394-6913, facsimile at (704)-394-6968 or e-mail at dwallace@shieldengineering.com.

Sincerely,

SHIELD ENGINEERING, INC.

J David Wallace, P.E.

Senior Engineer

Mark C. Boland, P.E.

Principal Engineer

cc: Mike Gladden - Public Works Director (McDowell County)

Larry Frost – Solid Waste Section, NCDENR

Attachments: Tables 1 through 4

Figures 1 through 14 RTP Analytical Report



TABLE 1
Methane Extraction Test Vacuum Pressures
Methane Extraction Test
Former McDowell County Landfill
Shield Project #1070249

			MDW-1	MDW-2	MDW-3
		Vacuum Pump	Well-head	Well-head	Well-head
Time	Date	Pressure	Vacuum	Vacuum	Vacuum
I HHE	Date	(inches of	Pressure	Pressure	Pressure
		Water)	(inches of	(inches of	(inches of
			Water)	Water)	Water)
10:47	12/19/2007	65	32	31	33
11:03	12/19/2007	65	32	31	33
11:24	12/19/2007	65	32	31	33
11:50	12/19/2007	65	32	32	33
12:20	12/19/2007	65	32	32	33
12:45	12/19/2007	65	32	32	33
13:13	12/19/2007	66	32	32	34
13:48	12/19/2007	65	33	32	34
14:25	12/19/2007	65	33	32	34
14:55	12/19/2007	65	33	33	34
15:55	12/19/2007	65	33	32	34
16:50	12/19/2007	65	33	33	34
17:50	12/19/2007	66	35	34	36
18:50	12/19/2007	67	36	34	34
19;50	12/19/2007	66	35	34	35
20:50	12/19/2007	66	36	33	35
21:50	12/19/2007	67	36	33	34
22:50	12/19/2007	68	35	34	34
23:50	12/19/2007	68	37	37	38
1:00	12/20/2007	70	48	48	50
1:53	12/20/2007	72	55	55	58
2:57	12/20/2007	72	55	55	58
3:53	12/20/2007	72	55	55	55
4:51	12/20/2007	72	55	55	57
5:51	12/20/2007	72	55	55	56
6:53	12/20/2007	72	55	55	56
7:50	12/20/2007	72	55	55	56
8:50	12/20/2007	73	58	58	60
9:58	12/20/2007	76	73	74	75`
10:45	12/20/2007	72	62	63	,
11:45	12/20/2007	65	40	40	43
12:50	12/20/2007	64	40	40	42
13:45	12/20/2007	64	40	40	42
14:45	12/20/2007	64	40	40	42
15:45	12/20/2007	64	40	40	42
16:50	12/20/2007	64	40	40	41
17:50	12/20/2007	64	40	40	41
18:50	12/20/2007	64	40	41	42
19:50	12/20/2007	64	41	40	41
20:50	12/20/2007	65	40	40	43
21:50	12/20/2007	65	40	40	43
23:50	12/20/2007	65	41	40	42
0:50	12/21/2007	65	41	40	42
1:51	12/21/2007	65	41	40	42
2:51	12/21/2007	65	41	40	42
3:50	12/21/2007	65	41	40	41
4:52	12/21/2007	65	41	40	41
5:54	12/21/2007	65	41	40	42
6:53	12/21/2007	65	42	41	43
7:50	12/21/2007	65	42	42	44
			17		
11	lues for Period				
	(12/20) to 7:50	64.6	40.7	40.2	42.0
[] (1	2/21)				
l					

NOTES:

Ice Blockages in Vacuum Lines

TABLE 2

Methane Extraction Well MDW-1 Methane Extraction Test Former McDowell County Landfill Shield Project #1070249

10:34 12/19/2007 41.8 32.7 6.3 19.2 -20.9 0.43 70 39 4.83 290	Time	Date	Methane	Carbon Dioxide	Oxygen	Gas Balance	Static Pressure (inches	Differential Pressure (inches of	Temperature (°F)	Corrected Gas Flow Rate (scfm)	Епегду (kW-Hour)	Power (kilowatts)
10-51 127192/007 27			(F	ercentage	of gas in ai	r)	of Water)	Water)				
	10:34	12/19/2007	41.8	32.7	6.3	19.2	-20.9	0.43	70	39	4.83	290
11:30 12:192:007 24	9									1 :		1
1207 1279 2007 23.8 16.8 13.1 46.3 -13.8 0.96 70 62 4.38 262 223 1259 2007 22.4 16.3 12.9 47.6 -23 0.35 70 35 2.41 144 13.94 1279 2007 22.8 16.2 12.6 48.8 -23.1 0.37 70 36 2.39 143 13.91 1279 2007 22.4 15.9 12.9 48.8 -23.1 0.37 70 36 2.39 143 13.91 1279 2007 22.4 15.9 12.9 48.8 -23.1 0.37 70 36 2.39 143 13.91 1279 2007 22.2 15.9 13 48.9 -24.6 0.61 70 47 3.09 143 13.91 13.91 13.1 48.9 -22.0 0.55 70 35 2.28 137 15.30 1279 2007 21.2 15.6 13 48.9 -22.0 0.55 69 22 1.43 86 13.91 15.6 13 50.2 -24.8 0.21 69 26 1.63 86 13.91 13.91 13.3 48.9 -22.0 0.55 69 22 1.43 86 13.91	B											·
12:31 12:19	Et l											1 1
13904 1279 2007 22.8	k I											1
13:31 12/19/2007 22.4 16.9 12.9 48.8 -23.1 0.37 70 36 2.39 143 13:59 12/19/2007 22.2 15.8 13.1 49.1 -22 0.35 70 35 2.28 137 13/19/2007 21.9 16.1 13.1 49.1 -22 0.35 70 35 2.28 137 13/19/2007 21.9 16.1 13.1 49.1 -22 0.15 69 26 1.63 86 16.32 12/19/2007 21.2 15.6 13 50.2 -24.8 0.21 69 26 1.63 98 13.1 13.1 14.1 14.1 13.1 14.1 14.1 14.1 14.1 13.1 14.1	J											
14:31 12:1992007 22	13:31	12/19/2007	22.4	15.9	12.9	48.8	-23.1		70	36		143
15.33 1219 2007 21.9 16.1 13.1 48.9 .22 0.15 89 22 1.43 86 18.32 1219 2007 21.2 15.6 13.5 50.2 .24.8 0.21 69 .26 .16.3 98 17.31 1219 2007 21.1 15.9 13.3 48.7 .25.1 0.37 68 68 .36 .25.5 13.5 13.5 14.8 13.5 14.5 49.6 .26.4 0.68 69 .66 .40.3 .24.2 .29.3 .219 2007 20.5 15.9 13.9 49.7 .25.9 1.74 68 .81 4.92 .295												
18.32 12719/2007 21.2 15.6 13 50.2 2-4.8 0.21 698 268 1.63 98 1.73 12719/2007 21.1 15.9 13.3 49.7 2-5.1 0.37 68 36 22.5 135 18.30 12719/2007 20.9 16 13.5 48.6 -26.4 0.88 69 65 40.3 242 249	. 1											1 1
17:31 12/19/2007 20,9 16 135 49,6 26,4 0.68 69 66 40,3 22,5 136 137 138 139 139 139 149,7 25,9 15,0 16 136 49,7 25,9 174 68 81 49,2 29,5 139 139 149,7 25,9 174 68 81 49,2 29,5 139 139 149,7 25,9 174 68 81 49,2 29,5 12,9 12,19 12	н 1	I I				1						
18:30 12/19/2007 20.9 16 13.5 49.6 -26.4 0.68 89 66 4.03 242 245												
19.36 12/19/2007 20.5 15.9 13.9 48.7 22.9 1.74 68 81 4.92 295	31 3											1 1
21:29 21:99 2007 20.9 16.4 13 49.7 23 0.68 68 50 3.10 186 22:37 12:19 2007 20.1 16.2 13.2 50.5 24.9 0.46 67 40 2.38 143 23:36 12:19 2007 20.1 16.2 13.2 50.5 24.9 0.46 67 40 2.38 143 23:36 12:19 2007 19.2 15.7 13.7 51.4 -11 0.14 64 22 1.25 75 75 75 75 75 75 75	19:36									9 1		
22.337 22.19/2007 19.3 15.4 14.3 51 -21.8 1.01 68 62 3.55 213 23.36 12/19/2007 20.1 16.2 13.2 50.5 -24.9 0.46 67 40 2.38 143 0.41 12/20/2007 19.2 15.7 13.7 15.7 13.7 11.1 0.14 64 20 1.25 75 2.39 12/20/2007 20.9 16.7 12.7 49.7 -12.6 0.12 64 20 1.24 74 3.34 12/20/2007 20.8 16.6 13.3 49.3 -13.8 0.13 64 21 1.50 78 3.35 12/20/2007 20.8 16.4 12.9 50.5 -16.1 0.15 64 21 1.9 80.5 -18.1 1.4 1.1 1.0 78 4.2 1.1 1.0 78 4.2 1.1 1.0 78 4.2 1.1 1.0 78 1.4 1.4 1.5 2.2 1.2 1.0 1.5	# #											
23:36 1219 2007 20.1 16.2 13.2 50.5 24.9 0.46 67 440 23.8 143 143 143 143 13.2 55.5 54.9 0.46 67 40 23.8 143 143 143 13.2 55.5 54.9 0.46 67 40 23.8 143 144 13.9 54.3 144 13.9 54.3 144 13.9 54.3 145	K I			: I						: I		l li
0.441 12/20/2007 13.5 11.2 15.5 59.8 -19.8 -0.98 66 0 0.00 0 0 0 0 0 0 0	}~~~~~											
1:35 12/20/2007 19.2 15.7 13.7 51.4 -11 0.14 64 22 12.5 75 239 12/20/2007 20.8 16.6 13.3 49.3 -13.8 0.13 64 21 13.0 78 3:34 12/20/2007 20.8 16.6 15.4 12.9 50.5 -16.1 0.15 64 23 13.3 81 6:35 12/20/2007 19.7 15.7 12.7 51.9 -17.4 0.19 64 25 14.6 88 6:36 12/20/2007 19.7 15.7 12.7 51.9 -17.4 0.19 64 25 14.6 88 6:36 12/20/2007 19.5 15.8 13.4 50.6 -16.2 0.1 64 19.1 12.6 67 8:31 12/20/2007 19.5 15.8 13.5 51.2 -18.4 0.16 64 23 13.3 80 9:41 12/20/2007 19.5 15.8 13.5 51.2 -18.4 0.16 64 23 13.3 80 9:41 12/20/2007 19.5 15.8 13.5 51.2 -18.4 0.16 64 23 13.3 80 9:41 12/20/2007 19.5 14.4 13.5 54.2 -4.5 0.02 60 5 0.27 16 9:45 12/20/2007 19.7 15.7 13.5 51.0 1.5 3 0.02 80 6 5 0.27 16 9:45 12/20/2007 19.7 15.8 13 51.2 -18.4 0.16 64 23 13.3 80 13.0 12/20/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 13.30 12/20/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 13.30 12/20/2007 18.7 15.3 13.2 52.8 -28.9 0.42 65 38 2.11 126 13.30 12/20/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 18.3 19.9 120 16:33 12/20/2007 17.1 14.3 13.2 55.4 -28.0 0.46 65 40 2.18 131 14.32 12/20/2007 17.1 14.3 13.2 55.4 -28.0 0.42 65 38 1.99 120 16:33 12/20/2007 17.1 14.3 13.2 55.4 -28.0 0.42 65 38 1.99 120 16:33 12/20/2007 17.1 14.3 13.4 54.8 28.9 0.42 65 38 1.99 120 16:33 12/20/2007 17.1 14.3 14.9 15.5 55.1 -28.9 0.44 63 39 1.99 120 17.33 12/20/2007 17.1 14.4 13.4 54.8 28.9 0.42 65 38 1.99 120 18:39 12/20/2007 17.1 14.1 13.3 55.5 -28.9 0.42 65 38 1.99 120 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.90 118 19:35 12/20/2007 17.1 14.1 13.3 55.5 -28.5 0.47 65 30 39 2.01 121 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.99 119 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.99 119 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.99 119 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.99 119 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.99 119 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.99 119 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44 63 39 1.99 119 18:39 12/20/2007 17.1 14.1 13.3 55.6 -28.9 0.44	BI											
239 12/20/2007 20.9 16.7 12.7 49.7 12.6 0.12 64 20 1.24 74	lí ' I			1								
4.35 12/20/2007 20.8 16.4 12.9 50.1 -14.8 0.14 63 22 1.34 81 5.36 12/20/2007 19.7 15.7 15.7 12.7 51.9 -17.4 0.19 64 23 1.39 83 6.36 12/20/2007 19.9 16.1 13.4 50.6 16.2 0.1 64 19 1.12 67 6.37 13/20/2007 19.9 16.1 13.4 50.6 16.2 0.1 64 19 1.12 67 6.38 11/20/2007 19.9 14.4 13.5 50.6 16.2 0.1 64 19 1.12 67 6.37 13/20/2007 19.9 14.4 13.5 54.2 4.5 0.02 60 5 0.27 16 9.45 12/20/2007 20.8 16.4 12.7 50.1 5.3 0.02 60 6 0.37 22 10.30 12/20/2007 20.8 16.5 11.8 46.1 -12.8 0.14 64 22 1.54 92 11.30 12/20/2007 19.7 15.8 13 51.5 -20.2 0.39 65 36 2.10 126 12.34 12/20/2007 19.7 15.8 13 51.5 -20.2 0.39 65 36 2.10 126 13.30 12/20/2007 18.4 15 13 53.6 2-9 0.42 65 38 2.11 126 13.30 12/20/2007 18.4 15 13 53.6 2-9 0.42 65 38 2.11 126 13.30 12/20/2007 17.7 14.7 12.9 54.7 28.4 0.42 65 38 1.99 120 15.30 12/20/2007 17.7 14.7 12.9 54.7 28.4 0.42 65 38 1.99 120 15.30 12/20/2007 17.1 14.3 13.2 55.4 28.6 0.87 65 57 2.89 173 17.33 12/20/2007 17.7 14.6 13.2 54.5 28.8 0.42 65 38 1.99 120 16.33 12/20/2007 17.7 14.6 13.2 54.5 28.8 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.6 13.4 54.8 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.6 13.2 54.5 28.8 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.6 13.4 54.8 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.6 13.4 54.8 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.6 13.4 54.8 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.6 13.4 54.8 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.1 13.3 55.5 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.6 13.4 54.8 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.1 13.3 55.5 28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.7 14.7 13.2 54.4 29.2 0.41 65 38 1.99 110 18.39 12/20/2007 17.7 14.1 13.3 55.5 28.9 0.42 63 38 1.99 110 18.39 12/20/2007 17.7 14.1 13.3 55.5 28.9 0.42 63 38 1.99 110 18.39 12/20/2007 17.7 14.1 13.3 55.5 28.9 0.42 63 38 1.99 110 18.39 12/20/2007 17.7 14.1 13.3 55.5 28.9 0.44 63 39 1.99 110 18.30 12/20/2007 17.7 14.1 13.3 55.5 20.0 0.44 60 0.00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0												
5.36 12/20/2007 20.4 16.2 12.9 50.5 -16.1 0.15 64 23 1.39 83 6.36 12/20/2007 19.7 15.7 15.7 12.7 51.9 -17.4 0.19 64 25 1.46 88 7.34 12/20/2007 19.9 16.1 13.4 50.6 -16.2 0.1 64 19 1.12 67 8.31 12/20/2007 19.5 15.8 13.5 51.2 -18.4 0.16 64 23 1.33 80 9.45 12/20/2007 19.7 14.4 13.5 54.2 -4.5 0.02 60 5 0.27 16 9.45 12/20/2007 20.8 16.4 12.7 50.1 -5.3 0.02 60 6 0.37 22 9.130 12/20/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 11:30 12/20/2007 18.7 15.3 13.2 52.8 -29.2 0.39 65 36 2.10 126 12:34 12/20/2007 18.4 15 13 53.6 -29 0.46 65 38 2.11 126 13:30 12/20/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 16:33 12/20/2007 17.1 14.7 12.9 54.1 -28.4 0.35 65 34 1.83 109 16:33 12/20/2007 17.1 14.7 14.9 13.2 54.5 -28.8 0.42 65 38 1.99 120 16:33 12/20/2007 17.1 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 16:33 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65	H I		20.8	16.6	13.3		-13.8	0.13	64	21	1.30	78
6.36 12/20/2007 19.7 15.7 15.7 12.7 51.9 -17.4 0.19 64 25 1.46 88 17.34 12/20/2007 19.9 16.1 13.4 50.6 -16.2 0.1 64 19 1.12 67 63.1 12/20/2007 19.5 15.8 13.5 51.2 -18.4 0.16 64 23 1.33 80 9.41 12/20/2007 17.9 14.4 13.5 54.2 -4.5 0.02 60 5 0.27 16 69.5 12.20 17.9 14.4 13.5 54.2 -4.5 0.02 60 6 0.37 22 10.30 12/20/2007 23.6 18.5 11.8 46.1 -12.8 0.14 64 22 1.54 92 10.30 12/20/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 12.34 12/20/2007 18.7 15.3 13.2 52.8 -28.9 0.42 65 38 2.11 126 13.30 12/20/2007 18.4 15 13 53.6 -29 0.46 65 40 2.18 131 132 13/20/2007 17.7 14.7 12.9 54.1 -28.4 0.35 65 34 18.3 109 15.30 12/20/2007 17.7 14.6 13.2 55.4 -28.8 0.42 65 38 1.99 120 15.31 12/20/2007 17.7 14.6 13.2 54.5 -28.8 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 11.8 13.30 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 12.34 12/20/2007 17.4 14.4 13.4 54.5 -28.9 0.41 65 38 1.99 120 12.34 12/20/2007 17.4 14.4 13.4 54.5 -28.9 0.42 65 38 1.99 120 12.34 12/20/2007 17.4 14.4 13.4 54.5 -28.9 0.44 65 38 1.99 120 12.34 12/20/2007 17.4 14.4 13.4 54.5 -28.9 0.44 65 38 1.99 120 12.34 12/20/2007 17.4 14.4 13.3 55.5 -29.5 0.47 65 40 2.03 12/20/2007 17.4 14.4 13.1 55.9 -30.4 65 39 1.95 118 13.3 13.2 12/20/2007 17.4 14.4 13.5 55.3 -29.5 0.47 65 40 2.												
7.34 12/20/2007 19.9 16.1 13.4 50.6 -16.2 0.1 64 19 1.12 67 8.31 12/20/2007 19.5 15.8 13.5 51.2 -18.4 0.16 64 23 1.33 80 9.41 12/20/2007 20.8 16.4 12.7 50.1 -5.3 0.02 60 6 0.37 22 11.30 12/20/2007 20.8 16.4 12.7 50.1 -5.3 0.02 60 6 0.37 22 11.30 12/20/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 11.30 12/20/2007 18.7 15.3 13.2 52.8 -29.9 0.42 65 38 2.11 126 12.34 12/20/2007 18.7 15.3 13.2 52.8 -29.9 0.46 65 40 2.18 131 14.32 12/20/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 16.33 12/20/2007 17.7 14.7 12.9 54.7 -28.4 0.42 65 38 1.99 120 16.33 12/20/2007 17.7 14.6 13.2 55.4 -28.6 0.87 65 57 2.89 173 17.33 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 13.36 12/20/2007 17.4 14.4 13.3 55.5 -29.5 0.47 65 40 2.3 1.96 118 18.39 12/20/2007 17.4 14.4 13.3 55.5 -29.5 0.47 65 40 2.3 2.0 1.18 18.39 12/20/2007 17.4 14.4 13.3 55.5 -29.5 0.47 65 40 2.3 2.0 1.18 18.39 12/20/2007 17.4 14.4 13.3 55.5 -29.5 0.47 65 40 2.3 2.0 1.18 18.39 12/20/2007 17.4 14.4 13.3 55.5 -29.5 0.47 65 40 2.3 2.0 1.18 18.39 12/20/2007 17.4 14.4 13.3 56.3 -29.5 0.44 63 39 1.99 1.9 1.18 18.30 12/21/2007 1	H 1									1 8		1 3
8:31 1220/2007 19.5 15.8 13.5 51.2 -18.4 0.16 64 23 1.33 80 841 1220/2007 20.8 16.4 13.5 54.2 -4.5 0.02 60 6 0.5 0.27 16 64 1220/2007 20.8 16.4 12.7 50.1 5.3 0.02 60 6 0.37 22 10.30 1220/2007 23.6 18.5 11.8 46.1 -12.8 0.14 64 22 1.54 92 11.30 1220/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 12.34 1220/2007 18.7 15.3 13.2 52.8 -28.9 0.42 65 38 2.11 126 12.34 1220/2007 18.4 15 13 53.6 -29 0.46 65 40 2.18 131 14.32 1220/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 15.30 1220/2007 17.7 14.7 12.9 54.7 -28.4 0.35 65 34 1.83 109 15.30 1220/2007 17.7 14.6 13.2 55.4 -28.8 0.42 65 38 1.99 120 1233 1220/2007 17.7 14.6 13.2 54.5 -28.8 0.42 65 38 1.99 120 1233 1220/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 1234 1220/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 1234 1220/2007 17.7 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 1234 1220/2007 17.7 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 1234 1220/2007 17.7 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 1238 1220/2007 17.7 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 1238 1220/2007 17.7 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 1238 1220/2007 17.7 14.7 13.2 55.4 -28.9 0.42 65 38 1.99 120 1238 1220/2007 17.7 14.7 13.2 55.4 -28.9 0.42 65 38 1.99 120 1238 1220/2007 17.7 14.7 13.2 55.5 -29.5 0.47 65 38 1.99 120 1234 1220/2007 17.7 14.7 13.2 55.7 -29.5 0.44 63 39 1.97 118 13.6 1220/2007 17.1 14.1 13.3 55.5 -29.5 0.44 63 39 1.97 118 13.6 1220/2007 17.1 14.2 13.1 55.7 -29.5 0.44 63 39 1.97 118 13.6 1220/2	я 1											1 31
9.41 1220/2007 17.9 14.4 13.5 54.2 4.5 0.02 60 5 0.27 16 9.45 1220/2007 20.8 16.4 12.7 50.1 -5.3 0.02 60 60 6 0.37 22 11:30 1220/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 12:34 1220/2007 18.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 13:30 1220/2007 18.4 15 13 53.6 -29 0.46 65 40 2.18 131 14:32 1220/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 16:30 1220/2007 17.7 14.7 12.9 54.7 -28.4 0.42 65 38 1.99 120 16:33 1220/2007 17.1 14.3 13.2 55.4 -28.6 0.87 65 57 2.89 173 17:33 1220/2007 17.4 14.6 13.2 54.5 -28.8 0.42 65 38 1.99 120 18:39 1220/2007 17.5 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 18:39 1220/2007 17.5 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 18:39 1220/2007 17.5 14.6 13.4 54.8 -28.9 0.42 65 38 1.99 120 18:39 1220/2007 17.5 14.6 13.4 54.8 -28.9 0.42 65 38 1.96 118 18:39 1220/2007 17.5 14.6 13.4 54.5 -28.9 0.42 65 38 1.99 120 18:31 1220/2007 17.5 14.6 13.4 54.5 -28.9 0.42 65 38 1.99 120 12:38 1220/2007 17.5 14.6 13.4 54.5 -28.9 0.42 65 38 1.99 120 12:38 1220/2007 17.1 14.1 13.3 55.5 -29.5 0.41 65 38 1.99 120 12:38 1220/2007 17.1 14.1 13.3 55.5 -29.5 0.44 63 39 1.97 118 136 1221/2007 17.1 14.1 13.3 55.5 -29.5 0.44 63 39 1.93 116 136 1221/2007 16.8 14.1 13.1 55.7 -29.5 0.44 63 39 1.99 116 136 1221/2007 17.1 14.1 13.1 55.9 -30.6 0.44 63 39 1.99 114 136 1221/2007 16.8 14.1 13.1 55.9 -30.6 0.44 63 39 1.99 114 136 1221/2007 17.4 14.5 13.1 55.6 -30.6 0.44 63 39 1.99 114 137 1221/2007 16.8 14.1 13.3 55.8 -30.6 0.44 63 39 1.99 114 136 12	***************************************								***************************************			
9.45 12/20/2007 20.8 16.4 12.7 50.1 5.3 0.02 60 6 0.37 22 11.30 12/20/2007 23.6 18.5 11.8 46.1 -12.8 0.14 64 22 1.54 92 11.30 12/20/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 12.34 12/20/2007 18.7 15.3 13.2 52.8 -28.9 0.42 65 38 2.11 126 13.30 12/20/2007 18.4 15 13 53.6 -29 0.46 65 40 2.18 131 14.32 12/20/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 15.30 12/20/2007 17.7 14.7 12.9 54.7 -28.4 0.42 65 38 1.99 120 15.33 12/20/2007 17.7 14.6 13.2 55.4 -28.6 0.87 65 57 2.89 173 17.33 12/20/2007 17.7 14.6 13.2 55.4 -28.8 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18.39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.96 118 19.35 12/20/2007 17.5 14.6 13.4 54.5 -28.9 0.42 65 38 1.96 118 19.35 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.97 118 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.99 120 12/24 12/20/2007 17.7 14.1 13.3 55.5 -28.9 0.42 63 38 1.97 118 12/24 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.99 120 12/24 12/20/2007 17.7 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 12/24 12/20/2007 17.7 14.1 13.1 55.7 -29.5 0.44 63 39 1.97 118 136 12/21/2007 16.8 13.1 55.5 -29.5 0.44 63 39 1.97 118 136 12/21/2007 16.8 13.1 55.5 -30.5 0.44 63 39 1.97 118 136 12/21/2007 16.8 13.1 55.6 -30.3 0.44 63 39 1.95 117 14.3 13.1 55.6 -30.3 0.44 63 39 1.95 117 14.3 13.1 55.6 -30.3 0.44 63 39 1.95 117 14.3 13.1 55.6 -30.6 0.44 63 39 1.95 117 14.5 13.1 55.6 -30.6 0.44 63 39 1.95 117 14.5 13.1 55.6 -30.6 0.4	!! {	18										
11:30 12/20/2007 19.7 15.8 13 51.5 -29.2 0.39 65 36 2.10 126 12:34 12/20/2007 18.7 15.3 13.2 52.8 -28.9 0.42 65 38 2.11 126 13:30 12/20/2007 18.4 15 13 53.6 -29 0.46 65 40 2.18 131 14:32 12/20/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 15:30 12/20/2007 17.7 14.7 12.9 54.1 -28.4 0.42 65 38 1.99 120 16:33 12/20/2007 17.7 14.7 12.9 54.7 -28.4 0.42 65 38 1.99 120 16:33 12/20/2007 17.1 14.3 13.2 55.4 -28.8 0.87 65 57 2.89 173 12/20/2007 17.4 14.6 13.2 55.4 -28.8 0.87 65 57 2.89 173 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 120 120 120 120 120 120 120 120 120	9:45	12/20/2007	20.8			50.1	-5.3					
12:34 12/20/2007 18.7 15.3 13.2 52.8 -28.9 0.42 65 38 2.11 126 13:30 12/20/2007 18.4 15 13 53.6 -29 0.46 65 40 2.18 131 14:32 12/20/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 15:30 12/20/2007 17.7 14.7 12.9 54.7 -28.6 0.87 65 38 1.99 120 16:33 12/20/2007 17.7 14.6 13.2 55.4 -28.8 0.42 65 38 1.99 120 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.96 118 18:39 12/20/2007 17.5 14.6 13.4 54.8 -28.9 0.42 63 38 1.96 118 18:39 12/2	8	l.										1
13:30 12/20/2007 18.4 15 13 53.6 -29 0.46 65 40 2.18 131 14:32 12/20/2007 18.1 14.9 12.9 54.1 -28.4 0.35 65 34 1.83 109 120 15:30 12/20/2007 17.7 14.7 12.9 54.7 -28.4 0.42 65 38 1.99 120 16:33 12/20/2007 17.7 14.6 13.2 55.4 -28.6 0.87 65 57 2.89 173 17:33 12/20/2007 17.7 14.6 13.2 55.4 -28.6 0.87 65 38 1.99 120 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.99 120 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.96 118 18:39 12/20/2007 17.5 14.6 13.4 54.8 -28.9 0.42 65 38 1.96 118 18:39 12/20/2007 17.5 14.6 13.4 54.5 -28.9 0.42 65 38 1.96 118 18:35 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.99 120 118 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.44 65 38 1.99 120 12:38 12/20/2007 17.7 14.7 13.2 54.3 -29.3 0.43 62 39 2.01 121 1222221 12/20/2007 17.1 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 122 12/20/2007 17.1 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 1238 12/21/2007 17 14.1 13.2 55.7 -29.4 0.85 64 56 2.82 169 0.38 12/21/2007 16.7 14.1 13.2 55.7 -29.4 0.85 64 56 2.82 169 0.38 12/21/2007 16.7 14.1 13.3 56.3 -22.8 0.44 63 39 1.97 118 13.6 12/21/2007 16.8 13.9 13.1 66.3 -22.4 5.08 63 38 1.99 1.97 118 13.6 12/21/2007 16.8 13.9 13.1 66.3 -22.4 5.08 63 38 1.99 1.97 118 13.6 12/21/2007 16.8 13.9 13.1 55.7 -29.5 0.44 63 39 1.93 116 13.6 12/21/2007 16.8 13.9 13.1 56.3 -22.4 5.08 63 38 1.89 114 13.3 16.3 12/21/2007 16.8 13.9 13.1 56.3 -22.4 5.08 63 38 1.89 114 13.3 16.3 12/21/2007 16.8 13.9 13.1 56.3 -22.4 5.08 63 38 1.89 114 13.3 16.3 12/21/2007 16.8 13.9 13.1 55.0 -30.2 0.45 63 39 1.95 117 14.2 13.1 55.0 -30.2 0.45 63 39 1.95 117 14.2 13.1 55.0 -30.0 0.44 63 39 1.95 117 14.2 13.1 55.0 -30.0 0.44 63 39 1.95 117 118 119 119 119 119 119 119 119 119 119	8 1	l l								I .		1
14:32 12/20/2007 18:1 14:9 12:9 54.1 -28.4 0.35 65 34 1.83 109 120 15:30 12/20/2007 17:7 14:7 12:9 54:7 -28.4 0.42 65 38 1.99 120 13:30 12/20/2007 17:1 14:3 13:2 54.5 -28.8 0.42 65 38 1.99 173 17:33 12/20/2007 17:7 14:6 13:2 54.5 -28.8 0.42 65 38 1.99 120 18:39 12/20/2007 17:4 14:4 13:4 54.8 -28.9 0.42 65 38 1.96 118 18:39 12/20/2007 17:4 14:4 13:4 54.8 -28.9 0.42 65 38 1.96 118 19:35 12/20/2007 17:5 14:6 13:4 54.5 -28.9 0.42 63 38 1.96 118 19:35 12/20/2007 17:5 14:6 13:4 54.5 -28.9 0.42 63 38 1.97 118 20:40 12/20/2007 17:7 14:7 13:2 54.4 -29.2 0.41 65 38 1.99 120 12:38 12/20/2007 17:1 14:1 13:3 55.5 -29.5 0.47 65 38 1.99 120 12:38 12/20/2007 17:1 14:1 13:3 55.5 -29.5 0.47 65 40 2.03 122 23:40 12/20/2007 17:1 14:1 13:3 55.7 -29.4 0.85 64 56 2.82 169 13:81 12/21/2007 16:7 13:9 13:1 55.7 -29.4 0.85 64 56 2.82 169 13:81 12/21/2007 16:7 13:9 13:1 55.7 -29.8 0.44 63 39 1.97 118 1:36 12/21/2007 16:8 13:9 13:1 55.6 -29.8 0.44 63 39 1.97 118 1:36 12/21/2007 16:8 13:9 13:1 55.6 -29.8 0.44 63 39 1.93 116 12:36 12/21/2007 16:8 13:9 13:1 55.6 -29.8 0.44 63 39 1.93 116 12:36 12/21/2007 17:1 14:1 13:1 55.6 -29.8 0.44 63 39 1.93 116 12:36 12/21/2007 17:1 14:2 13:1 55.6 -30.3 0.44 63 39 1.93 116 13:36 12/21/2007 17:1 14:2 13:1 55.6 -30.3 0.44 63 39 1.93 116 13:36 12/21/2007 17:1 14:2 13:1 55.6 -30.3 0.44 63 39 1.93 116 13:36 12/21/2007 17:1 14:2 13:1 55.6 -30.3 0.44 63 39 1.98 119 114 13:1 55.6 12/21/2007 17:1 14:2 13:1 55.6 0.04 16:3 38 1.94 114 13:1 55.9 0.04 16:3 38 1.94 114 13:1 55.9 0.04 16:3 38 1.94 114 13:1 55.9 0.04 16:3 38 1.94 114 13:1 55.9 0.04 16:3 38 1.99 1.99 1.91 117 11:1 14:2 13:1 55.6 0.04 16:3 38 1.94 114 13:1 55.9 0.04 16:3 18:3 1.94 114 13:1 55.9 0.04 16:3 18:3 1.99 1.99 1.99 1.91 117 13:1 14:2 13:1 55.6 0.04 16:3 38 1.94 114 13:1 13:1 55.0 0.04 16:3 38 1.99 1.99 1.99 1.91 117 13:1 14:2 13:1 55.6 0.04 16:3 38 1.99 1.99 1.99 1.91 117 14:2 13:1 55.6 0.04 16:3 0.04 16:3 0.04 16:3 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.												
15:30 12/20/2007 17.7 14.7 12.9 54.7 -28.4 0.42 65 38 1.99 120 16:33 12/20/2007 17.1 14.3 13.2 55.4 -28.6 0.87 65 57 2.89 173 17:33 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.96 118 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.41 65 38 1.96 118 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.41 65 38 1.96 118 18:35 12/20/2007 17.7 14.7 13.2 54.5 -28.9 0.41 65 38 1.96 118 20:40 12/20/2007 17.7 14.7 13.2 54.5 -28.9 0.41 65 38 1.99 120 21:38 <t< td=""><td>R I</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>1</td><td></td><td> </td></t<>	R I									1		
16:33 12/20/2007 17.1 14.3 13.2 55.4 -28.6 0.87 65 57 2.89 173 17:33 12/20/2007 17.7 14.6 13.2 54.5 -28.8 0.42 65 38 1.99 120 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.42 65 38 1.96 118 18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.41 65 38 1.96 118 19:35 12/20/2007 17.5 14.6 13.4 54.5 -28.9 0.42 63 38 1.97 118 19:35 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.96 118 19:38 12/20/2007 17.4 14.4 13.9 54.3 -29.3 0.43 62 39 2.01 121 22:40 12/20/2007 17 14.2 13.1 55.7 -29.5 0.47 65 <	!			3		1						
18:39 12/20/2007 17.4	16:33	12/20/2007	17.1	14.3	13.2	55.4	-28.6	0.87	65	57	2.89	
18:39 12/20/2007 17.4 14.4 13.4 54.8 -28.9 0.41 65 38 1.96 118 19:35 12/20/2007 17.5 14.6 13.4 54.5 -28.9 0.42 63 38 1.97 118 20:40 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.99 120 21:38 12/20/2007 17.4 14.4 13.9 54.3 -29.3 0.43 62 39 2.01 121 22:42 12/20/2007 17.1 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 23:40 12/20/2007 17 14.2 13.1 55.7 -29.4 0.85 64 56 2.82 169 13.3 12/21/2007 17 14.1 13.2 55.7 -29.5 0.44 63 39 1.97 118 1:36 12/21/2007 16.7 13.9 13.1 56.3 -29.8 0.44 63 39 1.97 118 1:36 12/21/2007 16.8 13.9 13.1 56.3 -29.8 0.44 63 39 1.97 118 1:36 12/21/2007 16.8 13.9 13.1 56.3 -29.8 0.44 63 39 1.97 118 1:36 12/21/2007 16.8 13.9 13.1 55.5 -30.2 0.45 63 38 1.89 114 13.3 55.6 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.96 117 14.2 13.1 55.6 30.3 0.44 63 39 1.98 119 5:36 12/21/2007 17.1 14.2 13.1 55.6 30.3 0.44 63 39 1.98 119 5:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.94 116 63.6 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 116 63.6 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.89 114 116 63.6 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.89 114 116 63.6 12/21/2007 0 0.3 20.8 78.9 -2 0.01 48 3 0.00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0				1								
19:35 12/20/2007 17.5 14.6 13.4 54.5 -28.9 0.42 63 38 1.97 118 20:40 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.99 120 21:38 12/20/2007 17.4 14.4 13.9 54.3 -29.3 0.41 65 38 1.99 120 21:38 12/20/2007 17.1 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 23:40 12/20/2007 17 14.2 13.1 55.7 -29.4 0.85 64 56 2.82 169 0.38 12/21/2007 17 14.1 13.2 55.7 -29.5 0.44 63 39 1.97 118 13.6 12/21/2007 16.7 13.9 13.1 56.3 -29.8 0.44 63 39 1.97 118 13.3 12/21/2007 16.8 13.9 13 56.3 -29.8 0.44 63 39 1.93 116 2.36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 38 1.89 114 3.36 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.95 117 4.56 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 39 1.98 119 5.36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.94 116 63.6 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.94 116 63.6 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 0 8.36 12/21/2007 0 0.3 20.8 78.9 -0.5 0 46 0 0 0.00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0												
20:40 12/20/2007 17.7 14.7 13.2 54.4 -29.2 0.41 65 38 1.99 120 21:38 12/20/2007 17.4 14.4 13.9 54.3 -29.3 0.43 62 39 2.01 121 22:42 12/20/2007 17.1 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 23:40 12/20/2007 17 14.2 13.1 55.7 -29.4 0.85 64 56 2.82 169 0:38 12/21/2007 17 14.1 13.2 55.7 -29.5 0.44 63 39 1.97 118 1:36 12/21/2007 16.7 13.9 13.1 56.3 -29.8 0.44 63 39 1.93 116 2:36 12/21/2007 16.8 13.9 13 56.3 -22.4 5.08 63 38 1.89 114 3:36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.95 117 4:36 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.95 117 4:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.89 114 6:36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 8:36 12/21/2007 0 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 9:02 12/21/2007 0 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 9:03 12/21/2007 9.2 7.4 17.6 66.5 0 0 0 46 0 0 0.00 0 0:03 12/21/2007 20 13.5 13.3 53.2 0 0 41 0 0 0.00 0 0 10:37 12/21/2007 20 13.5 13.3 53.2 0 0 41 0 0 0.00 0 0 Average Values for Feriod from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6			t t							1		
21:38 12/20/2007 17.4 14.4 13.9 54.3 -29.3 0.43 62 39 2.01 121 22:42 12/20/2007 17.1 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 23:40 12/20/2007 17 14.2 13.1 55.7 -29.4 0.85 64 56 2.82 169 169 13.3 12/21/2007 17 14.1 13.2 55.7 -29.5 0.44 63 39 1.97 118 1:36 12/21/2007 16.7 13.9 13.1 56.3 -29.8 0.44 63 39 1.93 116 2:36 12/21/2007 16.8 13.9 13 56.3 -22.4 5.08 63 38 1.89 114 3:36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.95 117 14.2 13.1 55.6 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.95 117 14.36 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.95 117 16.36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.94 116 16.36 12/21/2007 17.4 14.5 13.1 55.6 -30.3 0.44 63 38 1.94 116 16.36 12/21/2007 17.4 14.5 13.1 55.6 -30.6 0.41 63 38 1.94 116 16.36 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0												
22:42 12/20/2007 17.1 14.1 13.3 55.5 -29.5 0.47 65 40 2.03 122 23.40 12/20/2007 17 14.2 13.1 55.7 -29.4 0.85 64 56 2.82 169 0.38 12/21/2007 17 14.1 13.2 55.7 -29.5 0.44 63 39 1.97 118 122 13.6 12/21/2007 16.7 13.9 13.1 56.3 -29.8 0.44 63 39 1.93 116 2:36 12/21/2007 16.8 13.9 13 56.3 -22.4 5.08 63 38 1.89 114 3:36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.95 117 14.2 13.1 55.6 -30.3 0.44 63 39 1.95 117 14.2 13.1 55.6 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.98 119 5:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.89 114 116 16:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.89 114 16 16:36 12/21/2007 17.4 14.5 13.1 55.8 -30.6 0.41 63 38 1.89 114 116 13:3 12/21/2007 17.4 14.5 13.1 55.8 -30.6 0.44 62 39 2.01 121 121 121 121 121 121 121 121 121 1												
0:38 12/21/2007 17 14.1 13.2 55.7 -29.5 0.44 63 39 1.97 118 1:36 12/21/2007 16.7 13.9 13.1 56.3 -29.8 0.44 63 39 1.93 116 2:36 12/21/2007 16.8 13.9 13 56.3 -22.4 5.08 63 38 1.89 114 3:36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.95 117 4:36 12/21/2007 17.1 14.2 13.1 55.9 -30.2 0.44 63 39 1.95 117 5:36 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.98 119 5:36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007	22:42	12/20/2007	17.1	14.1	13.3	55.5	-29.5		65	40		
1:36 12/21/2007 16.7 13.9 13.1 56.3 -29.8 0.44 63 39 1.93 116 2:36 12/21/2007 16.8 13.9 13 56.3 -22.4 5.08 63 38 1.89 114 3:36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.95 117 4:36 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.98 119 5:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.98 119 6:36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007 17.4 14.5 13.1 55 -30.6 0.44 62 39 2.01 121 8:07 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 <	L											
2:36 12/21/2007 16.8 13.9 13 56.3 -22.4 5.08 63 38 1.89 114 3:36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.95 117 4:36 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.98 119 5:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.94 116 6:36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007 17.4 14.5 13.1 55 -30.6 0.44 62 39 2.01 121 8:07 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 8:36 12/21/2007		F			E	1						
3:36 12/21/2007 16.9 14.1 13.1 55.9 -30.2 0.45 63 39 1.95 117 14.2 13.1 55.6 -30.3 0.44 63 39 1.98 119 5:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.94 116 6:36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.94 116 6:36 12/21/2007 17.4 14.5 13.1 55 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 0 0 0 0 0 0 0	1					1	1					
4:36 12/21/2007 17.1 14.2 13.1 55.6 -30.3 0.44 63 39 1.98 119 5:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.94 116 6:36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007 17.4 14.5 13.1 55 -30.6 0.44 62 39 2.01 121 8:07 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 8:36 12/21/2007 0 0.3 20.8 78.9 -0.5 0 46 0 0.00 0 9:02 12/21/2007 0 0 20.4 79.6 0 0 46 0 0.00 0 9:38 12/21/2007 3.5 3.8 19 73.7 0 0 46 0 0.00 0												
5:36 12/21/2007 17.2 14.4 13.6 54.8 -30.4 0.41 63 38 1.94 116 6:36 12/21/2007 16.8 14.1 13.3 55.8 -30.6 0.41 63 38 1.89 114 7:37 12/21/2007 17.4 14.5 13.1 55 -30.6 0.44 62 39 2.01 121 8:07 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 8:36 12/21/2007 0 0.3 20.8 78.9 -0.5 0 46 0 0.00 0 9:02 12/21/2007 0 0 20.8 78.9 -0.5 0 46 0 0.00 0 9:38 12/21/2007 0 0 20.4 79.6 0 0 46 0 0.00 0 10:06 12/21/2007 8.8 7.1						1				1		13
7:37 12/21/2007 17.4 14.5 13.1 55 -30.6 0.44 62 39 2.01 121 8:07 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 8:36 12/21/2007 0 0.3 20.8 78.9 -0.5 0 46 0 0.00 0 9:02 12/21/2007 0 0 20.4 79.6 0 0 46 0 0.00 0 9:38 12/21/2007 3.5 3.8 19 73.7 0 0 46 0 0.00 0 10:06 12/21/2007 8.8 7.1 17.6 66.5 0 0 45 0 0.00 0 10:37 12/21/2007 9.2 7.4 17.6 65.8 0.1 0 41 0 0.00 0 11:39 12/21/2007 20 13.5 13.3 53.2 0 0 41 0 0.00 0 12:34 12/21/2007 29.9 19.2 10.1 40.8 0.3 0.04 41 9 0.80 48 13:39 12/21/2007 40.9 24.8 7.1 27.2 0.4 0 41 0 0.00 0 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6			17.2	14.4	13.6	54.8	-30.4	0.41	63	38	1.94	Iš
8:07 12/21/2007 0 0.2 20.9 78.9 -2 0.01 48 3 0.00 0 8:36 12/21/2007 0 0.3 20.8 78.9 -0.5 0 46 0 0.00 0 9:02 12/21/2007 0 0 20.4 79.6 0 0 46 0 0.00 0 9:38 12/21/2007 3.5 3.8 19 73.7 0 0 46 0 0.00 0 10:06 12/21/2007 8.8 7.1 17.6 66.5 0 0 45 0 0.00 0 10:37 12/21/2007 9.2 7.4 17.6 65.8 0.1 0 41 0 0.00 0 11:39 12/21/2007 20 13.5 13.3 53.2 0 0 41 0 0.00 0 12:34 12/21/2007 29.9 19.2 10.1 40.8 0.3 0.04 41 9 0.80 48 13:39 12/21/2007 40.9 24.8 7.1 27.2 0.4 0 41 0 0.00 0 Average Values for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6	5			1				1				19
8:36 12/21/2007 0 0.3 20.8 78.9 -0.5 0 46 0 0.00 0 0 0 0 12/21/2007 0 0 20.4 79.6 0 0 0 46 0 0.00 0 0 0 0 0 0 0												I f
9:02 12/21/2007 0 0 20.4 79.6 0 0 46 0 0.00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0												
9:38 12/21/2007 3.5 3.8 19 73.7 0 0 46 0 0.00 0 10:06 12/21/2007 8.8 7.1 17.6 66.5 0 0 45 0 0.00 0 10:37 12/21/2007 9.2 7.4 17.6 65.8 0.1 0 41 0 0.00 0 11:39 12/21/2007 20 13.5 13.3 53.2 0 0 41 0 0.00 0 12:34 12/21/2007 29.9 19.2 10.1 40.8 0.3 0.04 41 9 0.80 48 13:39 12/21/2007 40.9 24.8 7.1 27.2 0.4 0 41 0 0.00 0 Average Values for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6								1				
10:06 12/21/2007 8.8 7.1 17.6 66.5 0 0 45 0 0.00 0 10:37 12/21/2007 9.2 7.4 17.6 65.8 0.1 0 41 0 0.00 0 11:39 12/21/2007 20 13.5 13.3 53.2 0 0 41 0 0.00 0 12:34 12/21/2007 29.9 19.2 10.1 40.8 0.3 0.04 41 9 0.80 48 12:34 12/21/2007 40.9 24.8 7.1 27.2 0.4 0 41 0 0.00 0 Average Values for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6								1				13
11:39 12/21/2007 20 13.5 13.3 53.2 0 0 41 0 0.00 0 12:34 12/21/2007 29.9 19.2 10.1 40.8 0.3 0.04 41 9 0.80 48 13:39 12/21/2007 40.9 24.8 7.1 27.2 0.4 0 41 0 0.00 0 Average Values for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6	r							i		0	0.00	0
12:34 12/21/2007 29.9 19.2 10.1 40.8 0.3 0.04 41 9 0.80 48 13:39 12/21/2007 40.9 24.8 7.1 27.2 0.4 0 41 0 0.00 0 Average Values for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6									,			
13:39 12/21/2007 40.9 24.8 7.1 27.2 0.4 0 41 0 0.00 0 Average Values for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6		~~~~										
Average Values for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6			t t		4							
for Period from 13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6			40.9	24.0	1.1	21.2	V.4	· · · · · ·	41	<u> </u>	0.00	<u> </u>
13:30 (12/20) to 17.3 14.4 13.2 55.1 -29.1 0.70 63.9 40.2 2.06 123.6		-		[1	_ [1		
7:37 (12/21)			17.3	14.4	13.2	55.1	-29.1	0.70	63.9	40.2	2.06	123.6
	7:37	7 (12/21)			1					1		-

TABLE 3 Methane Extraction Well MDW-2


Methane Extraction Test Former McDowell County Landfill Shield Project #1070249

Time	Date	Methane	Carbon Dioxide	Oxygen	Gas Balance	Static Pressure (inches of	Differential Pressure (inches of	Temperature (⁰ F)	Gas Flow Rate	Corrected Gas Flow Rate	Energy (kW-	Power (kilowatts)
		(1	Percentage	of gas in a	ir)	`Water)	`Water)	(. ,	(scfm)	(scfm)	Hour)	
10:39	i I	25.7	18.4	12.5	43.4	-16.9	0.58	63	47	48	3.66	219
10:55 11:16	i I	20.3	15.1	13.6	51	-17.4	0.53	63	45 65	45 ==	2.71	162
11:39	12/19/2007	15,1 13.4	12.6 11.8	13.8 14.2	58.5 60.6	-17.8 -17.5	0.79 0.57	63 62	55 46	55 47	2.46 1.87	148 112
12:11	12/19/2007	11	10.3	15.2	63.5	-17.2	1.52	62	78	78	2.54	153
12:36	12/19/2007	9.9	9.5	15.3	65.3	-14.8	0.54	62	45	45	1.32	79
13:09 13:37	12/19/2007 12/19/2007	9 8.4	8.8 8.4	15.5 15.8	66.7 67.4	-17.6 -13.8	0.54 2.58	62 62	45 103	45 103	1.20 2.57	72 154
13:40		8.3	8.3	15.6	67.8	-17.2	0.14	62	22	22	0.54	32
14:11	12/19/2007	7.8	8	15.7	68.5	-14.1	0.42	62	40	40	0.93	55
14:38 15:38		7.5 7	7.7 7.5	16.2 16.4	68.6 69.1	-17.7 -16.8	0.32 0.46	62 62	35 41	34 42	0.76 0.87	45 52
16:39	12/19/2007	6.3	7.1	16.2	70.4	-19.6	0.68	62	51	51	0.95	57
17:36		6.2	7.1	16.6	70.1	-19.7	2.54	61	101	101	1.86	111
18:37 19:36	12/19/2007 12/19/2007	- 6 - 5	7 5.9	16.9 17.3	70.1 71.8	-19.8 -19.1	1.84 2.4	60 60	85 98	86 98	1.53 1.45	92 87
20:41	12/19/2007	5.7	6.8	16.8	70.7	-15.1	1.94	60	90	89	1.50	90
21:35	12/19/2007	5.7	6.7	16.7	70.9	-17.2	2.19	60	94	94	1.59	95
22:36 23:42	12/19/2007 12/19/2007	4.9 5.2	6 6.4	17.6 16.6	71.5 71.8	-16.3 -17.6	0.54 1.97	59 60	45 90	45 90	0.65	39
0:48	12/19/2007	5.2 3.8	5.1	17.8	73.3	-17.6 -17.1	0.35	60	90 34	90 36	1,39 0.41	83 24
1:43	12/20/2007	4	5.5	17	73.5	-7.4	0.07	58	15	14	0.17	10
2:45 3:42	12/20/2007	4.6	5.7	17.4	72.3	-8.7	0.18	58	24	26	0.35	21
3:42	12/20/2007 12/20/2007	5.2 5.2	6.4 6.4	16.4 16.4	72 72	-9.8 -0.2	0.18 0.03	58 58	28 28	26 7	0.40 0.11	24 6
4:42	12/20/2007	5.1	6.1	16.6	72.2	-10.4	0.24	58	30	30	0.45	27
	12/20/2007	5.2	6.1	16.5	72.2	-11	0.28	57	32	33	0.51	31
6:43 7:39	12/20/2007 12/20/2007	4.9 5	5.8 5.9	16.4 16.9	72.9 72.2	-11.3 -10	0.29 0.15	57 57	33 23	33 23	0.48 0.34	29 20
8:40	12/20/2007	5	5.8	17.3	71.9	-11.4	0.24	58	33	30	0.44	27
9:50	12/20/2007	3.3	4.7	17.6	74.4	-2.2	0	56	1	0	0.00	0
10:36 11:35	12/20/2007 12/20/2007	6.8 4.8	7.2 5.6	16.5 17.2	69.5 72.4	-30.8 -22.5	1.2 0.73	59 58	67 52	67 53	1.35 0.75	81 45
12:40	12/20/2007	4.5	5.4	17.3	72.8	-22.4	0.73	58	51	51	0.68	41
13:35	12/20/2007	4.2	5.2	17.4	73.2	-22.3	0.74	58	53	53	0.66	40
14:37 15:36	12/20/2007	4.2	5.1 5	17.6 17.4	73.1 73.6	-22 -22	0.68 0.69	57 57	51 51	51 51	0.64	38 36
16:39	12/20/2007	4	4,9	17.2	73.9	-22	1.36	57	74	73	0.61 0.87	50 52
17:38	12/20/2007	3.8	4.8	17.5	73.9	-21.9	0.68	57	50	50	0.56	34
18:44 19:42	12/20/2007 12/20/2007	3.7 3.8	4.7 4.7	17.5 17.2	74.1 74.3	-22.1 -22.1	0.7 0.72	57 57	52 52	51 52	0.56 0.59	34 35
1 1	12/20/2007	3.8	4.7	17.3	74.5	-22.1	0.72	57	52 50	52 51	0.59	35 34
	12/20/2007	3.7	4.5	17.9	73.9	-22.4	0.73	57	52	53	0.58	35
22:48 23:44	12/20/2007	3.6	4.3	17.7	74.4	-22.4	0.7	57	52	51	0.54	33
0:43	12/20/2007	3.6 3.4	4.5 4.3	17.8 17.4	74.1 74.9	-22.5 -22.8	0.71 0.7	57 56	52 52	52 51	0.56 0.51	33 31
1:41	12/21/2007	3.5	4.3	17.6	74.6	-22.9	0.71	57	52	52	0.54	32
2:41 3:41	12/21/2007 12/21/2007	3.4 3.4	4.2 4.2	17,7 17.0	74.7	-22.8 -23.2	0.61	57 57	52 54	48	0.48	29
	12/21/2007	3.4	4.2	17.9 18.1	74.5 74	-23.2 -23.4	0.73 0.73	57 57	54 54	52 52	0.52 0.56	31 33
5:40	12/21/2007	3.6	4.3	17.8	74.3	-23.5	0.72	56	51	52	0.56	33
	12/21/2007 12/21/2007	3.6 3.7	4.3	18 18.4	74.1	-23.6	0.74	57 56	52 55	53 56	0.57	34
	12/21/2007	3. <i>1</i> 0	4.4 0	21	73.5 79	-23.7 -0.3	0.77 0	56 41	55 0	55 0	0.60 0.00	36 0
8:12	12/21/2007	0	0	21.1	78.9	-0.3	0	41	0	0	0.00	0
	12/21/2007	0	0.1	20.9	79 70.6	-0.1	0	42	0	0	0.00	0
	12/21/2007 12/21/2007	0	0.2	20.5	79.5 79.1	0	0	42 40	0	0	0.00	0
10:12	12/21/2007	0.5	0.8	20.6	78.1	ő	ő	40	ő	ő	0.00	0
	12/21/2007	1,4	1.7	20	76.9	0	0	42	0	0	0.00	0
	12/21/2007 12/21/2007	12.3 22	9.4 16.1	15.7 12.8	62.6 49.1	0	0	40 41	0	1 0	0.04	2 0
, ,	12/21/2007	20.5	14.5	13.1	51.9	0	ő	41	0	0	0.00	0
	ige Values											
13:35	eriod from i (12/20) to 1 (12/21)	3.7	4,6	17.7	74.1	-22.6	0.7	56.9	53.2	52.8	0.58	35

TABLE 4 Methane Extraction Well MDW-3

Methane Extraction Test
Former McDowell County Landfill
Shield Project #1070249

Time	Date	Methane	Carbon Dioxide (Percentage	Oxygen of gas in air	Gas Balance	Static Pressure (inches of Water)	Differential Pressure (inches of Water)	Temperature (⁰ F)	Corrected Gas Flow Rate (scfm)	Energy (kW-Hour)	Power (kilowatts)
10:43	12/19/2007	4.6	3.4	19.5	72.5	-7.7	0.76	60	56	0.76	46
11:00	12/19/2007	4.1	2.8	20.1	73	-7.4	0.6	61	49	0.60	36
11:21	12/19/2007	3.7	2.5	19	74.8	-8.1	0.75	60	56	0.61	37
11:44	12/19/2007	3.6	2.4	19.8	74.2	-8	0.73	61	55	0.59	35
12:17	12/19/2007	3.4	2.3	19.8	74.5	-7.2	0.4	60	40	0.40	24
12:42	12/19/2007	3.2	2.3	19.8	74.7	-7.7	0.61	60	50	0.47	28
13:14	12/19/2007	3	2.2	19.8	75	-7.2	0.74	60	55	0.49	29
13:44	12/19/2007	2.9	2.1	19.7	75.3	-7.2	0.67	60	52	0.45	27
14:18	12/19/2007	2.8	2.1	19.9	75.2	-6.6	0.7	60	54	0.45	27
14:46	12/19/2007	2.7	2.1	20.1	75.1	-8.4	0.76	60	56	0.45	27
15:45	12/19/2007	2.8	2.4	19.7	75.1	-9.1	0.71	60	54	0.45	27
16:47	12/19/2007	2.6	2.3	19.6	75.5	-9.6	0.85	60	59	0.45	27
17:43	12/19/2007 12/19/2007	2.5	2.4	19.8	75.3	-9.7	0.87	60	60	0.44	27
18:41 19:48	12/19/2007	2.4 2.3	2.4 2.4	19.6	75. 6 75. 6	-9.2	1.67	59 50	85	0.61	36
21:42	12/19/2007	2.2	2.5	19.7 19.5	75.8	-8.6 -7.9	1.3 0.98	59 58	74 64	0.50 0.42	30 25
22:50		2.3	2.6	19.7	75.4	-7. 9	0.94	58	63	0.42	25 26
23:47	12/19/2007	2.3	2.6	19.3	75.8	-8.5	0.76	57	56	0.43	23
	12/20/2007	2.1	2.6	19.6	75.7	-9.3	1.54	56	81	0.50	30
1:50	12/20/2007	2.1	2.6	19.5	75.8	-10.2	0.83	56	59	0.37	22
2:52	12/20/2007	1.9	2.4	19.5	76.2	-8.6	0.49	57	44	0.25	15
3:49	12/20/2007	2	2.5	19.5	76	-8.6	0.63	57	50	0.30	18
4:48	12/20/2007	2	2.5	19.4	76.1	-8.2	0.62	56	50	0.30	18
5:48	12/20/2007	2	2.4	19.5	76.1	-7.9	0.58	56	49	0.29	17
6:51	12/20/2007	1.9	2.3	19.4	76.4	-7.6	0.58	56	49	0.28	17
7:45	12/20/2007	2	2.4	20	75.6	-7	0.44	56	43	0.26	15
8:46	12/20/2007	2	2.4	19.9	75.7	-7.7	0.57	56	48	0.28	17
9:55	12/20/2007	3.7	2.9	19.6	73.8	-0.2	-0.01	48	0	0.00	0
11:40	12/20/2007	2.2	2.5	19.6	75.7	-11.6	0.95	56	63	0.41	25
12:45	12/20/2007	1.9	2.3	19.6	76.2	-11.5	0.97	56	63	0.36	21
13:40 14:41	12/20/2007 12/20/2007	1.8 1.6	2.2 2	19.5	76.5	-11.3	0.96	56	63	0.34	20
II 1	12/20/2007	1.6	2	19.7 19.7	76.7 76.7	-11 -10.9	0.98 0.95	55 55	64 63	0.30 0.30	18 18
	12/20/2007	1.5	1.9	19.6	77	-10.4	1.91	55	92	0.30	25
	12/20/2007	1,4	1.9	19.7	77	-10.6	0.97	55	64	0.27	16
II 3	12/20/2007	1.3	1.9	19.7	77.1	-10.4	0.95	55	63	0.24	15
19:47	12/20/2007	1.3	1.9	19.7	77.1	-10.5	0.94	53	63	0.24	15
20:53	12/20/2007	1.5	2	19.5	77	-11	0.99	53	65	0.29	17
21:47	12/20/2007	1.5	1.9	19.9	76.7	-11	0.92	53	63	0.28	17
22:55	12/20/2007	1.4	1.8	19.8	77	-11	0.95	53	64	0.27	16
1 1	12/20/2007	1.4	1.9	19.7	77	11.2	0.96	53	64	0.27	16
0:47	12/21/2007	1.4	1.8	19.6	77.2	-11.3	0.96	52	64	0.27	16
a 1	12/21/2007 12/21/2007	1.4	1.8	19.7	77.1	-11.6	0.96	52	64	0.27	16
2:46 3:46	12/21/2007	1.3 1.4	1.8 1.8	19.8 19.8	77.1 77	-10.7 -12.1	-0.12 0,99	51 51	64 65	0.25 0.27	15 16
J	12/21/2007	1.5	1.9	19.7	76.9	-12.1	0.97	52	64	0.27	17
	12/21/2007	1.5	1.9	19.9	76.7	-12.4	0.96	52	64	0.28	17
	12/21/2007	1.6	1.9	19.7	76.8	0	-0.06	52	62	0.29	18
	12/21/2007	1.7	2	19.9	76.4	~13	0.98	51	64	0.32	19
	12/21/2007	1.7	2	19.8	76.5	o	0	43	0	0.00	o l
8:46	12/21/2007	1.6	1.9	19.8	76.7	0	0	42	0	0.00	0
	12/21/2007	1.7	2	19.6	76.7	0	0	42	0	0.00	0
	12/21/2007	1.3	1.6	20.1	77	0	0.02	42	4	0.02	1
	12/21/2007	6.5	5	19.1	69.4	0	0	40	0	0.00	0
	12/21/2007	17.5	11.3	15.1	56.1	0	0	40	0	0.00	0
	12/21/2007	19	12.1	14.6	54.3	0	0	40	0	0.00	0
	12/21/2007 12/21/2007	22.4	13.9 15.4	13.1	50.6	0	0	42	0	0.00	0
·		25	10.4	13,1	46.5	0	0	44	0	0.00	00
for Po 13:40	ge Values eriod from (12/20) to 7 (12/21)	1.48	1.91	19.72	76.89	-10.66	0.90	53.11	65.21	0,29	17



0 100' 200' APPROXIMATE SCALE: 1 in. = 200 ft.

LEGEND

*

PROPOSED BORING LOCATION



4301 TAGGART CREEK ROAD CHARLOTTE, NC 28208 704-394-6913 704-394-6968 tex www.shieldengineering.com

RBS

1


PROPOSED METHANE INVESTIGATION PROBE LAYOUT


FORMER McDOWELL COUNTY LANDFILL MARION COUNTY, NORTH CAROLINA


SHIELD # 1070249-01


DATE: 10/29/07 DRAWN BY: SCALE: AS SHOWN FIGURE:


H:\PROJECTS\2007\1070249-01 ASU METHANE INVESTIGATION\FIGURES\FIGURE 1



















TIME











Research Triangle Park Laboratories, Inc. 8109 Ebenezer Church Road
Raleigh, NC 27612

919 510-0228 Telephone 919 510-0141 Fax





January 7, 2008

Shield Engineering 4301 Taggart Creek Road Charlotte, NC 28208

Attn: David Wallace

PROJECT: Former McDowell County Landfill; PO 1070249 RTP Labs # 07-265

Enclosed with this letter is the report on the chemical analyses for the samples received December 21, 2007 for a normal turnaround. One Tedlar bag and one XD-2 sorbent tube samples were received in good condition. The Tedlar bag sample was analyzed for VOCs by EPA Method TO-15 GC/MS for 60 VOC Target Compounds. In addition, a library search was performed for the top 30 organic compounds (Tentatively Identified Compounds) using EPA/NIST 149,000 mass spectral database. The Tedlar bag samples were also analyzed for sulfur compounds by EPA Modified Method 15/16 GC/FPD and for Fixed Gases by EPA Method 3C GC/TCD. The XAD-2 sorbent tubes were analyzed for Siloxanes by GC/MS using an in-house RTP Labs method.

Please note that ND means not detected at the reporting limits expressed.

Sincerely,

Alston Sykes, Principal Chemist

Alston Lykes

Attachments: Sulfur & Fixed Gases report, Siloxanes report; TO-15 report, COC form.

File: ShieldEng 07-265.doc/als

Research Triangle Park Laboratories, Inc. 8109 Ebenezer Church Road

Raleigh, NC 27612

919 510-0228 Telephone 919 510-0141 Fax





Laboratory Report

Client: Shield Engineering Contact: David Wallace

Client Proj. #: Former McDowell Cty Landfill

Sample Date: 12/20/2007 Matrix: XAD-2 Sorbent RTP Labs Proj. #:07-265

Date Received: 12/21/2007 Analysis Date: 1/4/2008

EPA Method 15/16 for Sulfurs by GC/FPD

Sample	H₂S	cos	CH ₄ S	(CH₃)₂S	C ₂ H ₆ S ₂	CS ₂	Detection
ID	Hydrogen	Carbonyl	Methyl	Dimethyl	Dimethyl	Carbon	Limit
	Sulfide	Sulfide	Mercaptan	Sulfide	Disulfide	Disulfide	
MDLF#1	2.4	ND	ND	ND	ND	ND	0.5 ppmv

EPA Method 3C for Fixed Gases by GC/TCD

Sample ID	H ₂ Hydrogen	CO₂ Carbon	O ₂ Oxygen	N ₂ Nitrogen	CH₄ Methane	CO Carbon	Detection Limit
10	ilyurogen	Dioxide	Oxygen	ratio Scii	Methane	Monoxide	
MDLF #1	18.8	3.9	11.2	36.1	31.7	1	1 %

File: ShieldEng 07-265.doc/als Page 2 of 7

8109 Ebenezer Church Road Raleigh, NC 27612

919 510-0228 Telephone 919 510-0141 Fax





Laboratory Report

Client: Shield Engineering Contact: David Wallace

Client Proj. #: Former McDowell Cty Landfill

Sample Date: 12/20/2007 Matrix: XAD-2 Sorbent RTP Labs Proj. #:07-265

Date Received: 12/21/2007

Analysis Date: 1/4/2008

Siloxanes Analysis by GC/MS

Sample Description	MDLF #1	Reporting Limits
Compound		Units, μg ppbv 20L
Hexamethyldisiloxane (L2)	ND	1.0µg 8 ppbv
Hexamethylcyclotrisiloxane (D3)	ND	1.0µg 6 ppbv
Octamethyltrisiloxane (L3)	ND	1.0μg 5 ppbv
Octamethylcyclotetrasiloxane (D4)	3.7 μg 14.8 ppbv	1.0μg 4 ppbv
Decamethyltetrasiloxane (L4)	ND	1.0μg 4 ppbv
Decamethylcyclopentasiloxane (DS)	ND	1.0µg 3 ppbv
Dodecamethylpentasiloxane, (L5)	ND	1.0μg 3 ppbv
Dodecamethylcyclohexasiloxane (D6)	ND	1.0μg 3 ppbv

ND = Non-detect at Reporting Limit, Units are Total micrograms found on the sample tube. Parts per billion by volume (ppbv) is based on a assumed 20 liter air samples.

File: ShieldEng 07-265.doc/als

8109 Ebenezer Church Road Raleigh, NC 27612 onelac :



919 510-0228 Telephone 919 510-0141 Fax

Web Site: www.rtp-labs.com

EPA Method TO-15 GC/MS VOLATILE ORGANICS ANALYSIS REPORT

Data File: c:\varianws\wsdatafiles\voc022707\07-265-01b.sms Acquisition Date: 12/24/2007 12:03

Comment: Shield Eng/Former McDowell Cty LF #1 12/20/07; 10mL DF=50

CAS NO.	COMPOUND	CONCENTRATION	UNITS	Method Detection Limit
75-71-8	Dichlorodifluoromethane (Freon 12)	43.74	ppbv	0.5
76-14-2	1,2-Chloro-1,1,2,2-Tetrafluoroethane	Not Found	ppbv	0.5
74-87-3	Chloromethane	20.55	ppbv	0.5
75-01-4	Vinyl chloride	Not Found	ppbv	0.5
106-99-0	1,3-Butadiene	Not Found	ppbv	0.5
74-83-9	Bromomethane	Not Found	ppbv	0.5
75-00-3	Chloroethane	Not Found	ppbv	0.5
75-69-4	Trichloromonofluoromethane	Not Found	ppbv	0.5
		Not Found	ppbv	0.5
75-35-4	1,1-dichloroethene	Not Found Not Found		0.5
76-13-1	1,1,2-trichloro-1,2,2-trifluoroethane		ppbv	0.5
64-17-5	Ethanol	22,37	ppbv	0.5
75-15-0	Carbon disulfide	Not Found	ppbv	
67-63-0	Isopropyl alcohol	9.89	ppbv	0.5
75-09-2	Methylene chloride	Not Found	ppbv	0.5
67-64-1	Acetone	210.10	ppbv	0.5
156-60-5	t-1,2-dichloroethene	Not Found	ppbv	0.5
11-05-3	Hexane	80.94	ppbv	0.5
1634-04-4	Methyl-t-butyl ether (MTBE)	1.46	ppbv	0.5
75-34-3	1,1-Dichloroethane	Not Found	ppbv	0.5
108-05-4	Vinyl acetate	Not Found	ppbv	0.5
156-59-2	cis-1,2-dichloroethene	Not Found	ppbv	0.5
110-82-7	Cyclohexane	17.81	ppbv	0.5
67-66-3	Chloroform	Not Found	ppbv	0.5
141-78-6	Ethyl Acetate	Not Found	ppbv	0.5
109-99-9	Tetrahydrofuran	75.31	ppbv	0.5
71-55-6	1,1,1-trichloroethane	Not Found	ppbv	0.5
56-23-5	Carbon Tetrachloride	Not Found	ppbv	0.5
78-93-3	2-Butanone	Not Found	ppbv	0.5
142-82-5	Heptane	21.67	ppbv	0.5
71-43-2	Benzene	63.90	ppbv	0.5
107-06-2	1,2-dichloroethane	Not Found	ppbv	0.5
79-01-6	Trichloroethylene	Not Found	ppbv	0.5
78-87-5	1,2-dichloropropane	Not Found	ppbv	0.5
75-27-4	Bromodichloromethane	Not Found	ppbv	0.5
123-91-1	1.4-dioxane	Not Found	ppbv	0.5
10061-01-5	cis-1,3-dichloropropene	Not Found	ppbv	0.5
108-88-3	Toluene	22.36	ppbv	0.5
108-10-1	4-Methyl-2-pentanone (MIBK)	21.78	ppbv	0.5
	t-1,3-dichloropropene	Not Found	ppbv	0.5
1006-02-6	Tetrachloroethylene	Not Found	ppbv	0.5
127-18-4	1,1,2-trichloroethane	Not Found	ppbv	0.5
79-00-5 124-48-1	Dibromochloromethane	Not Found	ppbv	0.5
	1,2-dibromoethane	Not Found	vdqq	0.5
106-93-4	•	140.31	bbpa	0.5
591-78-6	2-Hexanone	189.57	ppbv	0.5
100-41-4	Ethylbenzene	38.88		0.5
108-90-7	Chlorobenzene		ppbv	0.5
1330-20-7	m/p-Xylene	246.93	ppbv	0.5
95-47-6	o-Xylene	49.92	ppbv	0.5
100-42-5	Styrene	Not Found	ppbv	
75-25-2	Tribromomethane	Not Found	ppbv	0.5
79-34-5	1,1,2,2-tetrachloroethane	Not Found	ppbv	0.5
622-96-8	1-ethyl-4-methylbenzene	55.10	ppbv	0.5
108-67-8	1,3,5-trimethylbenzene	137.57	ppbv	0.5
95-63-6	1,2,4-trimethylbenzene	58.73	ppbv	0.5
541-73-1	1,3-dichlorobenzene	Not Found	ppbv	0.5
106-46-7	1,4-dichlorobenzene	Not Found	ppbv	0.5
100-44-7	Benzyl chloride	Not Found	ppbv	0.5
95-50-1	1,2-dichlorobenzene	Not Found	ppbv	0.5
87-68-3	1,1,2,3,4,4-hexachloro-1,3-butadiene	Not Found	ppbv	0.5
120-82-1	1,2,4-trichlorobenzene	Not Found	ppbv	0.5

8109 Ebenezer Church Road Raleigh, NC 27612

Web Site: www.rtp-labs.com



919 510-0228 Telephone 919 510-0141 Fax

TENTATIVELY IDENTIFIED COMPOUNDS EPA Method TO-15 GC/MS VOLATILE ORGANICS ANALYSIS REPORT

Data File: c:\varianws\wsdatafiles\voc022707\07-265-01b.sms Acquisition Date: 12/24/2007 12:03

Comment: Shield Eng/Former McDowell Cty LF #1 12/20/07; 10mL DF=50

CAS NO. COMPOUND NAME		Retention Time	Estimated Concentra	ation,
79-46-9	Propane, 2-nitro-	8.78	116.91	ppbv
1768-25-8	Cyanic acid, 2-methylpropyl ester	17.1	199.84	ppbv
37533-06-5	N-(2,6-Dichlorophenyl)-N-[(2E)-3-methyl-	17,4	538.42	ppbv
625-74-1	Propane, 2-methyl-1-nitro-	18.5	285.98	ppbv
6236-88-0	Cyclohexane, 1-ethyl-4-methyl-, trans-	19.0	258.95	ppbv
625-74-1	Propane, 2-methyl-1-nitro-	19.6	302.79	ppbv
75991-61-6	2,7-Octadiene-1,6-diol, 2,6-dimethyl-, (19.7	140.11	ppbv
4558-27-4	5-Bromo-1-hexene	19.8	579.05	ppbv
51677-41-9	Butane, 2-azìdo-2,3,3-trimethyl-	20.0	681.04	ppbv
625-74-1	Propane, 2-methyl-1-nitro-	20.0	354.80	ppbv
66407-26-9	Cyclopenta[c]pyran-1,3-dione, 4,4a,5,6-t	20.4	142.93	ppbv
625-74-1	Propane, 2-methyl-1-nitro-	20.5	523.78	ppbv
99-82-1	1-Methyl-4-(1-methylethyl)-cyclohexane	20.6	506.65	ppbv
103-65-1	Benzene, propyl-	20.6	373.47	ppbv
3404-77-1	1-Hexene, 3,3-dimethyl-	20.7	429.99	ppbv
None	6-Chloro-2,2,9,9-tetramethyl-3,7-decadiy	20.9	228.75	ppbv
7214-61-1	Benzene, (1-nitroethyl)-	21.1	352.55	ppbv
498-51-1	2-Heptanone, 6-methyl-5-methylene-	21.4	178.91	ppbv
21195-59-5	1,3,8-p-Menthatriene	21.6	134.58	ppbv

(IS) is BFB Internal Standard and (SS) are Surrogate Standards that are added to each sample.

1/7/2008 15:30 Page 1 of 1 CLP TiC 07-265-01b.sms

File: ShieldEng 07-265.doc/als


Research Triangle Park Laboratories, Inc. 8109 Ebenezer Church Road

Raleigh, NC 27612

919 510-0228 Telephone 919 510-0141 Fax







8109 Ebenezer Church Road Raleigh, NC 27612

919 510-0228 Telephone 919 510-0141 Fax





Address: CantractPurchase Order No. Turn Around Time Requested for Report: Business Days; 'Rush Multipilors (Xx)

1 dayr'(4x) 2 days'(3x) 3 days'(2x) 5 days'(1.5x) 10 days'(1.1x) 5 days アプロスアー 1070249 Sample ID No. & Description ンメノモレロ Research Triangle Park Laboratories, Inc 8109 Ebenezer Church Road Raleigh, North Carolina 27612-7307 Phone: 919-510-0228 Fax: 919-510-0141 Web Site; www.rtp-labs.com TAGGART ENGMICERING 2 が大学がス 3008 HEDWORK CHANK 1630 Š Ä ξ. Matrix Send Report To Atte 20:00 Source Liquid/Solid Chain of Custody Record Compliance Test Preservatives Electronic Deliverable: 1.1x surcharge Data Pack: Std 🔲 Full 🔲 1.1x surcharge # of Containers NELAP Accredited NJ #NC003 ISO 17025 dunitace a sheldengineering, com SEE ATTACHED QUOTE FER ANALYSE Requested Analyses Sulfurs, Fixalgers Siloxanes by GC/MS 70-15 VOCS Field Initial EPA Level IV for Compliance D
Requires approved QAPP sent to lab
Date: Time: Tedlarbag QC Requirements: XAD-2 sorbert (5) loxone 72-1) 394-6965 Summa Canisters RTP Labs Project Tracking Number: Vacuum or Pressure 07-Air Samples Field Final Lab Lab Receipt Final 265 Screen 12/20/07 Page L of L gisd Standard [] Fracking # Sample Fraction