



North Carolina Department of Environment and Natural Resources

Division of Waste Management

Dexter R. Matthews

Director

Beverly Eaves Perdue
Governor

Dee Freeman
Secretary

SOLID WASTE SECTION

June 10, 2010

Mr. Kenneth Hardin, Owner
AAA Hauling of NC, Inc.
1171 South Eastern Boulevard
Fayetteville, North Carolina 27343

Subject: Permit to Construct/Operate – Completeness Determination and Technical Review
AAA Hauling of NC, Inc
Cumberland County, DIN 10832

Dear Mr. Hardin:

On February 22, 2010 the Division of Waste Management (Division), Solid Waste Section (Section) received your application for a new Permit to Construct/Operate AAA Hauling of NC, Inc Construction and Demolition Debris Transfer Station in Cumberland County, entitled;

Application for New Permit. Prepared by AAA Hauling of North Carolina, Inc. Dated February 15, 2010. Received in Raleigh February 22, 2010. Received ARO June 10, 2010. DIN 10831.

The Section has performed a review of you application for a determination of completeness and determined the application is complete in accordance North Carolina General Statute NCGS 130A-295.8(e). A determination of completeness means the application contains the required components in accordance with North Carolina Administrative Code 15A NCAC 13B .0400. In addition to the determination of completeness the Division has completed the technical review of the application and requests that you respond to the following items in order to expedite the application;

1. Items 14. through 33. – You have developed your Operation Plan as a list of answers. The guidance provided you for preparing your Plan is simply that. Please rewrite the Plan in a narrative style.
Example; 15. The Facility will process approximately 15 tons of waste per day.
2. Item 14. – Change to Construction and Demolition Debris Waste followed by a list of materials you intend to recycle, such as, metal, cardboard, plastic, and so on.
3. Item 17. – You list 3 facilities; designate which facility will take what materials.
4. Add to your Plan a statement that no material will be stored on the Concrete Pad over night and the pad will be swept at the end of each day.
5. Item 25. – Describe your process to determine that you are not receiving contaminated waste. Example; what will you do to prevent receiving household waste.



Page 2

AAA Hauling of NC, Inc.

June 10, 2010

6. Item 29. – Contact the Fayetteville Regional Office of the Division of Air Quality to ensure no permit is required.
7. Item 32. – Records should include the weight of out going containers as well.
8. Provides me with an additional set of drawings for my records. On your sketch of the Concrete Pad remove the dimensions. I recommend you add a sump to the design and slope the pad to the sump to capture any water that might have been contaminated by waste. Note: water that comes in contact with waste is considered leachate, and must be contained and properly handled.
9. Add the name of the facility to Applicant and Operator Certification pages; *AAA Hauling of NC, Inc.*

Finally, you will soon receive a request for information regarding a Compliance Review from Mr. Donald Herndon and an invoice for the proper permitting fee from Mr. Jeff Skabo, your immediate attention to these issues will prevent delays in permitting your facility. Should you have any questions regarding this matter you may contact me at (828) 296-4704 or at Larry.Frost@ncdenr.gov.

Sincerely,

A handwritten signature in black ink, appearing to read "Larry Frost", written in a cursive style.

Larry Frost
Environmental Engineer

cc: Drew Hammonds – SWS/FRO