



North Carolina Department of Environment and Natural Resources

Division of Waste Management

Dexter R. Matthews

Director

Beverly Eaves Perdue
Governor

Dee Freeman
Secretary

SOLID WASTE SECTION

February 22, 2011

Mr. Kenneth Hardin, Owner
AAA Hauling of NC, Inc.
1171 South Eastern Boulevard
Fayetteville, North Carolina 27343

Subject: Proposal for Additions – Response
AAA Hauling of NC, Inc. – Permit No. 2613
Cumberland County, DIN 13000

Dear Mr. Hardin:

On February 14, 2011, the Division received your email entitled;

Proposal for Additions. Prepared by AAA Hauling of NC. February 2011. DIN 12998.

In the email you ask if there was anything else I would need and on February 22, 2011 you ask, by email, for my thoughts regarding your proposal. I would refer you to my letter dated December 21, 2010, entitled;

Permit Modification Request – Response. December 2010. DIN 12553.

The following are the items I will need, for submission of a permit application, that do not appear in your email;

1. You have included a cover letter that must be signed by the owner and/or operator of the facility.
2. You have not included a revised operation plan that will be required for the addition of ;
 - a. The picking station - include a complete procedure for the station's operation.
 - b. The revised procedures that ensure the collection, recovery and treatment of leachate, once the leachate tank is removed.
 - c. The operation of the Stockpile Area for Concrete, Brick and Asphalt. See Notes.
 - d. The operation of the Stockpile Area for Land Clearing Debris and Clean Wood. See notes.
3. You have included a revised site plan/map. The area designated for "Concrete Debris" should be changed to Stockpile Area for Concrete, Brick and Asphalt. The area designated as "Wood/Yard Debris" should be changed to Stockpile Area for Land Clearing Debris and Clean Wood.
4. You have included engineering drawings of the modifications and/or additions and the drawings appear to be stamped by a North Carolina licensed Professional Engineer (PE). I think a detailed drawing of the concrete pad, upon which the picking station will be erected, should be added. The concrete pad design should ensure the collection, recovery and treatment of leachate.
5. You have not proposed an increase in your permitted volume; therefore you will not be required to revise the Facility's Financial Assurance mechanism.
6. When you submit the application you should include one (1) complete printed copy and one (1) complete electronic copy, in pdf format. Once the application is received you will be invoiced for the appropriate permitting fee, in this case \$500.00.



Page 2

AAA Hauling of NC, Inc.

February 22, 2011

Notes:

1. Stockpiling of concrete, brick and asphalt – you must submit a revised operations plan including a complete procedure for the stocking of the material. Within the revised procedures there should be a section regarding the handling of source separated materials (not containing waste material, painted concrete or exposed re-bar) and a section regarding the materials with mixed waste. The section regarding materials with mixed waste will require; 1) the removal of the waste from the incoming material, 2) the removal and proper disposal of painted concrete, 3) and the removal of exposed re-bar from the concrete (these procedures must take place prior to stockpiling).
2. Stockpiling of land clearing debris and clean wood – you will to submit a revised operations plan, which includes a complete description of the material, procedures for the stocking the material and procedures for processing of the material. Within the revised procedures there should be a section regarding the handling of source separated Land Clearing Debris and “clean wood”, and a section regarding Land Clearing Debris and wood with mixed waste and/or painted, treated and dimensional lumber. The section regarding Land Clearing Debris and clean wood with mixed waste and/or painted, treated and dimensional lumber will require the removal of waste material from the Land Clearing Debris, and the removal and proper disposal of wood that is considered not clean (these procedures must take place prior to stockpiling).
3. Once a complete application has been received you can expect further technical review of the information received.

Should you have any questions regarding this matter you may contact me at (828) 296-4704 or at larry.frost@ncdenr.gov.

Sincerely,

A handwritten signature in black ink, appearing to read "Larry Frost".

Larry Frost
Environmental Engineer

cc: Drew Hammonds – SWS/FRO