2-8-99 3:35 24

Permit No.	Issue Date	DIN
5504	March 14, 2011	13225

BOOK 1095 PAGE 173

NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES

DIVISION OF WASTE MANAGEMENT

Filed for registration and recorded this the 8th day of February, 1999, at 3:35 P.M. in Book 1095, Page 173.

ELAINE N. HARMON
Register of Deeds for Lincoln County

BY: Judith W. Martin
Asst Register of Deeds

PERMIT NO. 55-04
ISSUED 21 AUGUST 1998

JAMES B. HUNT JR.
GOVERNOR

WAYNE MCDEVITT
SECRETARY

WILLIAM L. MEYER
DIRECTOR

STATE OF NORTH CAROLINA

DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES

✓DIVISION OF WASTE MANAGEMENT

P.O. BOX 27687 RALEIGH, NC 27611

SOLID WASTE PERMIT

LAKE NORMAN LANDFILL, INC.

is hereby issued a PERMIT TO CONSTRUCT a

CONSTRUCTION AND DEMOLITION LANDFILL

located on Quarry Lane off NC HWY 16 in Lincoln County, North Carolina based on the site plan submitted to the Section dated February 1998 and referenced as item #1 in the approved documents; in accordance with Article 9, Chapter 130A, of the General Statutes of North Carolina and all rules promulgated thereunder and subject to the conditions set forth in this permit. The facility is located and described by the legal description of the site on the attached sheet.

James C Coffey
James C. Coffey, Supervisor
Permitting Branch
Solid Waste Section

401 OBERLIN ROAD, SUITE 150, RALEIGH, NC 27605
PHONE 919-733-4996 FAX 919-715-3605
AN EQUAL OPPORTUNITY / AFFIRMATIVE ACTION EMPLOYER - 50% RECYCLED/10% POST-CONSUMER PAPER

PERMIT NO. 55-04
ISSUED 21 AUGUST 1998

LAKE NORMAN LANDFILL

SOLID WASTE PERMIT
CONSTRUCTION AND DEMOLITION LANDFILL

CONDITIONS OF PERMIT:

General:

1. This permit shall not be effective unless the certified copy is filed in the Register of Deeds office and indexed in the grantor index under the name of the owner of the land in the county or counties in which the land is located. The certified copy of the permit, affixed with the Register's seal and the date, book, and page number of recording shall be returned to the Division of Waste Management (the Division).

2. When this property is sold, leased, transferred or conveyed, the deed or other instrument of transfer shall contain in the description section in no smaller type than that used in the body of the deed or instrument, a statement that the property has been used as a sanitary landfill.

3. This permit is for a period of five years and is subject to review on or before 21 August 2003, as per 15A NCAC 13B .0201(c), according to the issuance date of the permit. Modifications to the facility may be required in accordance with the rules in effect at the time of review. This facility may receive solid waste that is generated within a service area consisting of North Carolina and South Carolina.

4. The approved plan for this facility is described in Attachment 1, "List of Documents for Approved Plan". Where discrepancies exist, the most recent submittal and these Conditions shall govern. Some components of the approved plan are reiterated in these Conditions.

5. This permit is not transferable.

6. A copy of this permit and the approved plan shall be maintained at the facility.

7. The owner/operator is responsible for obtaining any and all permits and approvals necessary for the development of this project including approval from appropriate agencies for a General or Individual NPDES Stormwater Discharge Permit.

Construction and Operation:

1. This permit is for the development of the Lake Norman Construction and Demolition Landfill, Cells 1A, 1B, and 1C within the approved facility description, in accordance with the approved plan. Initial development shall begin with Cell 1A.

2. This solid waste management facility is permitted to receive the following waste types:

   a. Land-clearing debris as defined in G.S. 130A-290, specifically, solid waste that is generated solely from land-clearing activities, such as stumps, trees, etc.;
   b. Inert debris defined as solid waste which consists solely of material that is virtually inert, such as brick, concrete, rock and uncontaminated soil;
   c. Asphalt in accordance with G.S. 130A-294(m);
   d. Construction and demolition debris defined as solid waste resulting solely from construction, remodeling, repair or demolition operations on pavement, buildings, or other structures;

   Note: Yard trash defined as solid waste consisting solely of vegetative matter resulting from landscaping maintenance (see G.S. 130A-290) is banned from disposal in this facility as per NC General Statutes.

3. All sedimentation and erosion control measures will be conducted in accordance with the Sedimentation Control Act codified at 15 NCAC 4. Native vegetation shall be established on the completed landfill.

4. The following requirements shall be met prior to operation of this facility:

   a. Lake Norman Landfill or its consultant shall provide documentation to the Division that the site preparation (grading, placement of fill if applicable, etc.) has occurred in accordance with the construction plan and the conditions specified herein.
   b. Site inspection shall be made by a representative of the Division.
   c. Signs shall be posted at the facility in accordance with the Access and Safety Requirements under Operation Condition No. 5 listed below.
   d. Surface water monitoring locations shall be established and groundwater monitoring wells (see Monitoring and Reporting Requirements) shall be installed. A baseline sampling event for background water quality shall be performed. Well construction records and sampling analysis results shall be submitted to the Section Hydrogeologist for review and approval prior to operation (see Monitoring and Reporting Conditions below).
   e. Recordation procedures for the permit shall be implemented as described above in General Conditions Numbers 1 and 2.
   f. A comprehensive Operations Plan shall be submitted to the Division in accordance with 15A NCAC 13B .0505.

5. Operation of the facility shall occur in accordance with the NC Solid Waste Management Rules 15A NCAC 13B .0505, "Operational Requirements for Sanitary Landfills", the approved Operations Plan, and the following specific conditions:

Waste Acceptance and Disposal

a. The facility shall accept only those solid wastes which it is permitted to receive.
b. No municipal solid waste, hazardous waste, or liquid waste shall be accepted for disposal.
c. Waste shall be restricted to the smallest area feasible and compacted as densely as practical into cells.
d. The permittee shall implement a program at the facility for detecting and preventing the disposal of unacceptable wastes. The program shall include, at a minimum:
   i. Random inspections of incoming loads or other comparable procedures;
   ii. Record keeping which documents these inspections;
   iii. Training of personnel to recognize hazardous, liquid, and other unauthorized waste types;
   iv. Development of a contingency plan to properly manage any identified hazardous or problem wastes; The plan must address identification, removal, storage, and final disposition of these wastes.

Cover Material Requirements

a. Operational soil cover of at least six inches shall be placed at least once per week or when the active area reaches 1/2 acre in size or more often as necessitated by the nature of the waste so as to prevent the site from becoming a visual nuisance and to prevent fire, windblown materials, vectors or water infiltration.
b. Areas which will not have additional waste placed on them for 12 months or more, but where final termination of operations has not occurred, shall be covered with a minimum of one foot of soil cover.
c. After final termination of disposal operations at the site, or major part thereof, or upon revocation of a permit, the final cover system shall be installed.

Access and Safety

a. The facility shall be adequately secured by means of gates, chains, berms, fences, or other security measures approved by the Division to prevent unauthorized entry.
b. An attendant shall be on duty at the site at all times while it is open for public use to ensure compliance with operational requirements.
c. The access road to the site shall be of all-weather construction and maintained in good condition.
d. Dust control measures shall be implemented when necessary.
e. Signs providing information on dumping procedures, the hours of operation, the

permit number, the emergency contact, and other pertinent information shall be posted at the site entrance.

f. Signs shall be posted stating that no MSW, hazardous waste or liquid waste can be received.

g. Traffic signs or markers shall be provided as necessary to promote an orderly traffic pattern to and from the discharge area and to maintain efficient operating conditions.

h. The removal of solid waste from the facility is prohibited unless the owner/operator approves and the removal is not performed on the working face.

i. Barrels and drums shall not be disposed of unless they are empty and perforated sufficiently to ensure that no liquid or hazardous waste is contained therein, except fiber drums containing asbestos.

j. Open burning of solid waste is prohibited.

k. The concentration of explosive gases generated at the facility shall not exceed:
   i. twenty-five percent of the limit for gases in site structures (excluding gas control or recovery system components); and
   ii. the lower explosive limit for gases at the facility boundary.

Erosion and Sedimentation Control

a. Adequate sedimentation and erosion control measures shall be practiced to prevent silt from leaving the site.

b. Adequate sedimentation and erosion control measures shall be practiced to prevent excessive on-site erosion.

c. Provisions for a vegetative ground cover sufficient to restrain erosion must be accomplished within 30 working days or 120 calendar days upon completion of any phase of C&D landfill development.

Drainage Control and Water Protection Requirements

a. Surface water shall be diverted from the operational area.

b. Surface water shall not be impounded over or in waste.

c. A separation distance of at least four feet shall be maintained between waste and the ground-water table.

d. Solid waste shall not be disposed of in water.

e. Leachate shall be contained on site or properly treated prior to discharge. An NPDES permit may be required prior to discharge of leachate to surface waters.

6. All pertinent landfill operating personnel will receive training and supervision necessary to carry out their duties and operate this landfill in a safe manner.

7. A closure and post-closure plan must be submitted for approval at least 90 days prior to closure or partial closure of any landfill unit. The plan must include all steps and measures necessary to close and maintain the facility in accordance with all rules in effect at that time.

At a minimum, the plan shall address the following:

a. Design of a final cover system;
b. Construction and maintenance/operation of the final cover system and erosion control structures;
c. Surface water, ground water, and explosive gas monitoring.

Monitoring and Reporting:

1. Ground water quality at this facility is subject to the classification and remedial action provisions referenced in Rule .0503 (2)(d) of 15A NCAC 13B. Water quality monitoring for the C&D landfill shall occur according to the following conditions:

   a. The permittee shall sample the monitoring wells semi-annually or as directed by the Division Hydrogeologist.
   b. Monitoring well design and construction shall conform to the specifications outlined in Attachment 2, "North Carolina Water Quality Monitoring Guidance Document for Solid Waste Facilities."
   c. Sampling equipment, procedures, and parameters shall conform to specifications outlined in the above-referenced guidance document, (Attachment 2), or the current guidelines established by the Division at the time of sampling.
   d. A total of four monitoring well locations as illustrated in the approved plans shall be established to monitor the facility.
   e. A geologist shall be in the field to supervise well installation. The exact locations, screened intervals, and nesting of the wells shall be established after consultation with the Division Hydrogeologist at the time of well installation.
   f. Prior to the acceptance of any waste at the facility, a baseline sampling event shall be completed. The results of this sampling event shall be submitted to the Division Hydrogeologist in a timely manner (see Construction and Operation Condition 4 (d)).
   g. Well completion records and boring logs shall be submitted to The Division at the same time as the results of the initial sampling event or within 30 days upon completion of any new wells.
   h. In order to determine ground-water flow directions and rates, each monitoring well shall be surveyed, and hydraulic conductivity values and effective porosity values shall be established for the screened intervals for each monitoring well.
   i. A readily accessible unobstructed path shall be initially cleared and maintained so that four-wheel drive vehicles may access the monitoring wells at all times.

2. The permittee shall establish two locations for surface water sampling. Surface water shall be sampled and analyzed semi-annually according to the protocol and parameters required by the Division at the time of sampling.

3. The permittee shall maintain a record of all monitoring events and analytical data. Reports of the analytical data for each water quality monitoring sampling event (1.h. & 2.) shall be submitted to the Division in a timely manner.

4. Explosive gas monitoring shall be performed as needed to ensure compliance with the standards in Rule .0503 (2)(a).

5. The permittee shall maintain a record of the amount of solid waste (in tons) received at the facility, compiled on a monthly basis. Scales shall be used to weigh the amount of waste received.

6. On or before 01 August (or an earlier date as requested by the Division) of each year, the permittee shall report the amount of waste received at this facility and disposed of in the landfill to the Division and to all counties from which waste was accepted, on forms prescribed by the Division. This report shall include the following information:

   a. The reporting period shall be for the previous year, beginning 01 July and ending on 30 June;
   b. The amount of waste received and landfilled in tons, compiled on a monthly basis, according to Condition 5 described above; and
   c. Documentation that a copy of the report has been forwarded to all counties from which waste was accepted.

7. All pertinent records and reports shall be maintained on site and made available to the Division upon request.

PERMIT NO. 55-04
ISSUED 21 AUGUST 1998

ATTACHMENT 1

List of Documents for the Approved Plan

The following documents are incorporated into the approved plan for Permit No. 57-04:

1. Combination Site Plan and Construction Plan Application; Submitted by S&ME, Inc. on 20 February 1998.

2. Official Zoning Documentation and Lincoln County Permitting Status submitted 14 July 1998 by S&ME, Inc.

3. Response to Hydrogeologic Technical review letter, submitted 4 August 1998 by S&ME, Inc.

4. Revised Grading Plan and Cross Sections depicting Phase 1A, 1B, and 1C of the landfill; Submitted 10 August 1998 by S&ME, Inc.

5. Legal Description of the Facility.

LEGAL DESCRIPTION

Lying and being in Lincoln County, North Carolina, and more particularly described as follows:

To find the point and place of beginning; commence at N.C.G.S. "DOT" having coordinates of N = 187,641.082 and E = 427,050.142 (NAD 83), said N.C.G.S. "DOT" lying in Lot 5 of the Edward Lorraine Dellinger Subdivision shown in Plat Book G, Page 324, Lincoln County Public Registry; thence N 44-47-41 W 1,592.97 feet to a concrete monument lying on the northern boundary of Lot 2 of the property conveyed to Kenneth Eugene Dellinger by instrument recorded in Deed Book 909, Page 223, Lincoln County Public Registry, said point having coordinates of N = 187,985.583 and E = 426,708.101 (NAD 83); thence N 21-47-53 W 455.39 feet to a set magnetic nail (passing a found 1" iron pipe at 334.42 feet and a concrete monument at 337.47 feet); thence N 21-47-53 W 308.00 feet to a found crowbar; thence N 47-48-19 E 849.83 feet to a concrete monument found at witness tree (as reflected on the survey recorded in Plat Book 9, Page 106, Lincoln County Public Registry) lying on the eastern boundary of the property conveyed to B.V. Hedrick Gravel & Sand Co. by instrument recorded in Deed Book 641, Page 845, Lincoln County Public Registry, said concrete monument found also marking THE POINT AND PLACE OF BEGINNING; thence running with the eastern boundary of the B. V. Hedrick Gravel & Sand Co. property (now or formerly) the following three (3) courses and distances: (1) N 25-41-04 W 1,136.18 feet to an axle found (passing a dimple in SW Plates at 445.58 feet); (2) N 27-41-17 W 1,321.55 feet to an axle found; and (3) N 46-09-16 W 529.77 feet to a point lying in the centerline of Forney Creek (passing a 3/4" iron pin found at 504.06 feet), said point marking the southernmost corner of Tract 5 of the property conveyed to East Lincoln Land Company by instrument recorded in Deed Book 711, Page 508, Lincoln County Public Registry; thence with the centerline of Forney Creek the following forty-seven (47) courses and distances: (1) N 64-18-32 E 41.28 feet to a point; (2) N 50-17-32 E 196.68 feet to a point; (3) N 63-27-33 E 56.30 feet to a point; (4) N 58-18-33 E 63.03 feet to a point; (5) N 61-59-56 E 77.77 feet to a point; (6) N 83-11-53 E 73.43 feet to a point; (7) N 57-31-27 E 38.37 feet to a point; (8) N 29-03-38 E 113.86 feet to a point; (9) N 57-11-59 E 75.48 feet to a point; (10) N 66-03-44 E 100.14 feet to a point; (11) N 35-39-36 E 80.09 feet to a point; (12) N 56-01-52 E 65.73 feet to a point; (13) N 03-06-56 E 74.69 feet to a point; (14) N 58-36-50 E 95.82 feet to a point; (15) N 17-57-06 E 37.59 feet to a point; (16) N 15-05-26 E 50.98 feet to a point; (17) N 37-44-34 E 53.94 feet to a point; (18) N 73-48-44 E 67.09 feet to a point; (19) N 67-59-28 E 70.37 feet to a point; (20) N 41-54-42 E 67.67 feet to a point; (21) N 64-48-22 E 48.94 feet to a point; (22) N 78-12-26 E 67.78 feet to a point; (23) N 66-44-21 E 64.51 feet to a point; (24) N 65-54-59 E 80.93 feet to a point; (25) N 86-40-48 E 88.51 feet to a point; (26) N 45-29-19 E 44.36 feet to a point; (27) N 10-32-14 E 71.31 feet to a point; (28) N 14-16-57 E 27.66 feet to a point; (29) N 34-30-38 E 29.10 feet to a point; (30) N 49-47-41 E 192.16 feet to a point; (31) N 35-08-06 E 24.44 feet to a point; (32) N 11-45-57 E 48.93 feet to a point (passing a point marking the southernmost corner of the property conveyed to Joe Scruggs & wife Mary A. Scruggs by instrument recorded in Deed Book 357, Page 239, Lincoln County Public Registry); (33) N 32-03-51 E 42.72 feet to a point; (34) N 56-37-27 E 49.49 feet to a point; (35) N 38-21-34 E 62.71 feet to a point; (36) N 30-24-43 E 131.90 feet to a point; (37) N 63-35-24 E 71.50 feet to a point; (38) N 14-17-25 E 103.01 feet to a point; (39) N 50-28-58 E 65.35 feet to a point; (40) N 11-50-10 E 66.00 feet to a point; (41) N 47-27-37 E 64.79 feet to a point; (42) N 26-28-29 E 33.63 feet to a point; (43) N 08-14-05 E 228.83 feet to a point; (44) N 24-52-04 E 177.72 feet to a point; (45) N 12-13-52 W 145.53 feet to a point; (46) N 11-02-03

E 127.39 feet to a point; and (47) N 25-31-08 E 45.45 feet to a point; thence S 63-45-49 E 264.86 feet to an axle found (passing a 3/4" iron pin found at 47.21 feet); thence S 03-58-50 W 1,632.10 feet to an iron pipe found; thence N 85-59-58 W 20.14 feet to an axle found; thence S 03-58-27 W 399.77 feet to an axle found; thence S 86-09-48 E 19.88 feet to an axle found; thence S 03-58-50 W 1,243.26 feet to a #4 rebar set (passing an iron pipe found at 1,024.98 feet); thence S 02-45-34 W 74.76 feet to a #4 rebar set; thence S 02-45-34 W 144.80 feet to a #4 rebar set; thence with the arc of a circular curve to the left having a radius of 1,537.39 feet (said curve being subtended by a chord bearing S 00-28-05 E with a chord distance of 45.55 feet) for an arc distance of 45.55 feet to a #4 rebar set; thence S 34-10-43 W 1,407.67 feet to a #4 rebar set; thence S 25-41-04 E 1,129.84 feet to a #4 rebar set; thence N 55-11-07 E 458.11 feet to a #4 rebar set; thence with the arc of a circular curve to the right having a radius of 243.22 feet (said curve being subtended by a chord bearing N 77-26-38 E with a chord distance of 184.26 feet) for an arc distance of 188.97 feet to a #4 rebar set; thence S 80-17-52 E 86.09 feet to a magnetic nail set; thence S 15-24-39 W 15.07 feet to a magnetic nail set; thence N 80-17-52 W 84.59 feet to a magnetic nail set; thence with the arc of a circular curve to the left having a radius of 228.22 feet (said curve being subtended by a chord bearing S 77-26-38 W with a chord distance of 172.89 feet) for an arc distance of 177.32 feet to a magnetic nail set; thence S 55-11-07 W 521.29 feet to a magnetic nail set; thence N 25-41-04 W 789.89 feet to a concrete monument found; said concrete monument found also being THE POINT AND PLACE OF BEGINNING, containing 117.258 acres, more or less all as shown as Tract 1 on that certain survey entitled "Boundary survey of Portion of Revision of Tracts 1 & 2, P. B. H, Pg. 329 & 330 NORTH W. JONES, ELLA B. MILLER, BEN McCLEAN & NANCY E. WILLIAMSON TRACTS," prepared by James R. Hobbs, North Carolina Registered Land Surveyor (Registration Number L-3703), of Duke Energy Corporation, dated June 4, 1997 and last revised May 13, 1998, and identified as project Number 7999, reference to said survey being made in aid of description.

TOGETHER WITH a non-exclusive easement for vehicular and pedestrian ingress, egress, and regress and the installation and maintenance of utilities and the roadway from the right-of-way of North Carolina Highway 16 over and through the right-of-way of Quarry Lane and any additional property acquired within or adjacent to the right of way of Quarry Lane.

NORTH CAROLINA

AFFIDAVIT

LINCOLN COUNTY

The undersigned, being first duly sworn, deposes and says that:

1. She is the duly appointed and acting Clerk to the Board of Commissioners of Lincoln County, North Carolina.

2. She is familiar with the application of Barrett Grading, Inc., and/or its successor, Lake Norman Landfill, Inc., for the various permits necessary to construct and operate a construction and demolition landfill facility in Lincoln County, North Carolina.

3. Lincoln County has no franchise ordinance in effect with respect to construction and demolition landfills. For Lincoln County's purposes, the other approvals herein described are in essence a franchise agreement.

4. Lincoln County has a zoning ordinance in effect covering the property where the proposed facility is to be located, and Barrett Grading, Inc., and/or its successor, Lake Norman Landfill, Inc., secured all necessary approvals under the Lincoln County Zoning Ordinance in the form of a conditional use permit issued in June 1997. The proposed facility as it would be operated under the permit applied for will be consistent with the requirements of the Lincoln County Zoning Ordinance.

5. Lincoln County has a subdivision ordinance in effect covering the property where the proposed facility is to be located. Since Barrett Grading, Inc., and/or its successor, Lake Norman Landfill, Inc., does not contemplate subdividing the proposed site, the proposed facility as it would be operated under the permit applied for will be consistent with the requirements of the Lincoln County Subdivision Ordinance.

6. Lincoln County has in effect an Ordinance for the Regulation of Construction and Demolition/Land Clearing and Inert Debris Landfills. Barrett Grading, Inc., and/or its successor, Lake Norman Landfill, Inc., received a permit under said ordinance dated February 2, 1998, and so the proposed facility as it would be operated under the permit applied for will be consistent with the requirements of the said ordinance. The Lincoln County Health Department will monitor compliance with the provisions of said ordinance on an ongoing basis as the facility is being operated.

7. All ordinances described herein were adopted and made effective more than 90 days prior to the applicant's request for this affidavit.

8. None of Lincoln County's permits described herein for the proposed facility of Barrett Grading, Inc., and/or its successor, Lake Norman Landfill, Inc., places a limit on the amount of waste that can be placed therein.

9. None of Lincoln County's permits described herein for the proposed facility of Barrett Grading, Inc., and/or its successor, Lake Norman Landfill, Inc., places a geographic limit on the area to be served or the source of materials that may be placed in the facility.

10. None of Lincoln County's permits described herein for the proposed facility of Barrett Grading, Inc., and/or its successor, Lake Norman Landfill, Inc., places a limitation as to the useful life of the facility.

11. This affidavit is executed for the purposes of satisfying the requirements of the North Carolina General Statutes and regulations promulgated thereunder in general and N. C. G. S. 130A-294 in particular.

12. This affidavit was prepared in consultation with the County Attorney of Lincoln County.

This 17th day of August, 1998.

[County Seal]

Amy S. Long

Amy S. Long
Clerk to the Board of Commissioners
Lincoln County, North Carolina

Sworn to and subscribed before me
this 17th day of August, 1998.

Leslie T. Hoffman

Notary Public

My Commission Expires: 9-7-98

NORTH CAROLINA
LINCOLN COUNTY

CONSTRUCTION AND DEMOLITION/LAND CLEARING AND INERT DEBRIS LANDFILL PERMIT

DATE ISSUED: February 2, 1998
PERMIT NO.

Barrett Grading, Inc. and/or its successor in interest, Lake Norman Landfill, Inc. are hereby issued a Construction and Demolition/ Land Clearing and Inert Debris Landfill Permit (Permit) to operate a Construction and Demolition/ Land Clearing and Inert Debris Landfill (Facility) on the property located at NC Hwy. 16 and Quarry Lane, Lincoln County, North Carolina. This Permit is issued in accordance with the Ordinance for the Regulation of Construction and Demolition/Land Clearing and Inert Debris Landfills in Lincoln County, North Carolina (hereinafter "The Ordinance"). The Facility is located on the property described as follows:

PROPERTY DESCRIPTION:

A portion of Tax Parcel Number 56204 located off NC Hwy. 16 and Quarry Lane in the Catawba Springs Township and consisting of approximately 112 acres.

CONDITIONS OF PERMIT:

1. The Facility must be operated and closed in accordance with the rules cited as 15A NCAC 13B "North Carolina Solid Waste Management Rules", the provisions contained in the Ordinance and the conditions imposed by the Lincoln County Board of Commissioners at its August 4, 1997 regular board meeting.

2. The Facility shall be operated for the disposal of inert, non-decomposable waste and debris such as concrete, brick, steel, clean fill dirt, and other similar materials associated with construction, remodeling or demolition of pavement or structures as well as the disposal of organic, decomposable landclearing debris such as stumps, trees, brush, grass and other vegetative matters.

3. This Permit is issued subject only to the conditions contained in The Ordinance, which are hereby incorporated herein by reference and include the payment of the permit fee.

4. The issuance of this Permit was approved by vote of the Board of Commissioners of Lincoln County on August 4, 1997.

This 2nd day of February, 1998.

LINCOLN COUNTY

By: Louis E. McConnell
Louis E. McConnell, Chairman
Board of Commissioners

PPAB-CH1/262025.1