

Permit No.	Scan Date	DIN
2613	February 27, 2012	16166

Frost, Larry

From: Aaa Hauling of NC Nc [aaahaulingofnc@yahoo.com]
Sent: Wednesday, February 22, 2012 11:52 AM
To: Frost, Larry
Subject: Relocation of Pad
Attachments: Pad relocation.pdf

Good morning Mr. Frost,

Attached is the diagram for the Transfer Station. Due to permanent power being installed, we would like to relocate the concrete slab from it's current location to the other side of the picking station. The new pad will be the same size as the old one and we feel that relocating there would greatly benefit us in the long term.

Thank you,

Sherri Barbour
AAA Hauling of North Carolina, Inc.
1171 S Eastern Blvd
Fayetteville, NC 28306
910.868.5800 Office
910.868.3643 Fax
www.aaahaulingdemo.com

RECYCLING CENTER

REMOVE LEACHATE TANK AND SEAL SLAB DRAIN

30' x 40' CONCRETE SLAB

HATCHED AREA INDICATES TRANSFER STATION BOUNDARY

REMOVE PAD

RELOCATE PAD TO HERE

100' x 100' AREA for WOOD/YARD DEBRIS
100' x 100' AREA for CONCRETE DEBRIS

LIQUIDS ON SLAB WILL BE CONTAINED ON THE SLAB AND FREQUENTLY CLEANED UP WITH ABSORBENT MATERIAL, SUCH AS OIL-DRI QUICKSORB ABSORBENT. SOLIDIFIED MATERIALS WILL BE DISPOSED OF PROPERLY.


EXCAVATE AND REMOVE EXISTING 4'x7' LEACHATE TANK (300 GAL.) BACK FILL AND COMPACT SOIL.

6" x 6" CONCRETE CURB

REMOVE STRAINER AND FILL DRAIN BASIN WITH CONCRETE.

30'-0"

40'-0"




LEACHATE TANK REMOVAL

NOT TO SCALE

R

DRAWN BY:	B. J.
CHECKED BY:	B. JENKINS
DATE:	18 JAN 2011
SCALE:	



JENKINS CONSULTING ENGINEERS, PA
 DOUGLAS L. "BUDDY" JENKINS, PE 7740 McARTANS FORD LINDEN NC 28356
 910.822.1724 FAX 910.822.4646 buddy.jenkins@embarqmail.com