

July 12, 2013

NCDENR-DWM, Solid Waste Section Mail Service Center # 1646 Raleigh, North Carolina, 27699-1646

Attention: Ms. Jacylnne Drummond

Reference: MONITORING WELL REPLACEMENT

White Street Landfill, Phase II, Permit No. 41-03

Greensboro, North Carolina S&ME Project No. 1584-98-081

## Dear Ms. Drummond:

On behalf of the City of Greensboro, S&ME Inc. (S&ME) requests permission to replace compliance monitoring well II-4 with a new well of similar design. Well II-4 monitors the shallow aquifer in an area north of a portion of White Street Landfill, Phase II (e.g. closed MSW landfill with an active C&D landfill piggy backed on top). The location of well II-4 is depicted on **Figure 3**, a recent groundwater flow map. Monitoring well II-4 has exhibited higher than normal turbidity for a number of years. As evidenced by the attached *Groundwater Sampling Field Data* form for April 30, 2013, well II-4 was purged at approximately 100 milliliters per minute for over 1 hour, with little to no water level drawdown, yet turbidity levels remained well over 200 NTU. For groundwater sampling, a turbidity level of 10 NTU or less was established as the one of the target stabilization criteria. The April 2013 turbidity levels are not atypical for this well.

Previously, S&ME redeveloped the well on more than one occasion in an effort to reduce the turbidity; however, the turbidity problem has persisted. It has been our contention that the high turbidity level exhibited by the water yielded from this well is a source for the somewhat elevated metals concentrations detected at this location.

To remove the turbidity variable from the post-closure water quality assessment analyses we plan to replace the well with a new one installed less than 10 feet away, constructed with a similar total depth and well screen interval. The original well had a 10 foot well screen interval, which left the top of the well screen below the surface of the water table at times. We propose the use of a 15 foot well screen to reduce such occurrences. The replacement well will improve the performance of this compliance well, which is an integral part of the Facility's detection monitoring system.

Attached is a copy of the *Well Completion Record* for well II-4 and a diagram depicting proposed construction details for the replacement well to be named II-4A. Following installation, the new well will be developed and slug testing conducted to determine the



hydraulic conductivity for the monitored portion of the aquifer. A Well Construction Record, well boring log, and slug test results will be provided to you within 30 days of well completion.

Please review this request and provide the Facility with your written approval to proceed with the planned well replacement. Do not hesitate to call our office at (336) 288-7180 if you have any questions or comments. We appreciate your assistance in the management of this project.

Sincerely, S&ME, Inc.

Edmund Q.B. Her

Environmental Departe

Wayne H. Watterson, P.E.


Senior Engineer

EQBH/WHW/wj

Attachments: Figure 3: Groundwater Flow Map

Groundwater Sampling Field Data for well II-4 Well Completion Record for Well No. 9 / II-4 Proposed – Monitoring Well Installation Sketch

Gail Hay, P.E. City of Greensboro cc:



## **GROUNDWATER SAMPLING FIELD DATA**

Location:	White Street Landfill						Purge Date:	Tuesday, April 30, 2013			
Project No.:	1584-98	-081				_	Purge Time:				
Source Well:	4103-II4					_	Sample Date:	Tuesday, April 30, 2013			
							Sample Time:		17	10	
Locked?:	Yes:	x		No:			Weather:		Clo	udy	
Sampled By:	Gary Sin					_	Air Temp:		55	*F	
. ,						-	' .				
Water Level	& Well D	ata									
Depth to water from measuring point:				9.50	feet						
Depth to well bottom from measuring point:				30.00	feet						
Height of water column:				20.50	feet						
Measuring point:					Top of Casing						
Wall Donain		.l. O.									
Well Purging	-		llection								
Purge Method	Bladder					_		Purge <sup>-</sup>			
Sample Method		Pump				-	Start	1545	Stop	1705	
Purge Rate	100					ml/min	Saı	mple Colle	ction Time		
Control Settings	On:	3.5	sec.				Start	1705	Stop	1710	
	Off:	26.5	sec.								
	Pressure:	26	psi								
Volume of water											
	2" well:										
		height:	20.5	x .163 =		3.3415	<u>-</u>				
Volume of water	removed		7.0					gallons		liters	х
			.,								
Was well purged	d dry		Yes		_ No	X	-				
Field Analys	06		*Stabilization	Doromo	toro						
rielu Alialys	ES		Stabilization	i Parame	ters						
		Time	Date	Temp	рН	Conductivity	*ORP	*D.O.	*Turbidity	DTW	
		1545	4/30/2013	теттр	T PIT	Conductivity	OKI	Б.О.	Turbluity	DIW	
		1550	4/30/2013	16.65	7.33	0.851	227	3.82	123.00	9.82	
		1555	4/30/2013	16.59	7.33	0.886	228	3.72	81.00	9.78	
		1600	4/30/2013	16.75	7.34	0.892	229	3.46	76.40	9.77	
		1605	4/30/2013	16.82	7.36	0.887	230	3.18	81.20	9.77	
		1610	4/30/2013	16.92	7.40	0.893	230	2.93	74.40	9.76	
		1615	4/30/2013	16.93	7.40	0.895	230	2.87	89.90	9.78	
		1620	4/30/2013	16.63	7.42	0.900	231	3.02	107.00	9.77	
		1625	4/30/2013	16.81	7.37	0.907	231	2.76	89.40	9.77	
		1630	4/30/2013	16.60	7.39	0.918	232	2.66	142.00	9.77	
		1635 1640	4/30/2013 4/30/2013	16.10 16.11	7.39 7.40	0.926 0.946	235 237	2.62	161.00 217.00	9.77 9.76	
		1645	4/30/2013	15.75	7.40	0.946	239	2.48	141.00	9.77	
		1650	4/30/2013	16.00	7.37	0.960	240	2.32	214.00	9.76	
		1655	4/30/2013	15.87	7.37	0.975	241	2.28	258.00	9.75	
		1700	4/30/2013	15.78	7.38	0.990	242	2.64	253.00	9.76	
		1705	4/30/2013	15.79	7.36	0.990	244	2.24	251.00	9.76	
			.,		T	1					
Final Readings		1705	4/30/2013	15.79 * C	7.36 units	0.990 mS/cm	244 mV	2.24 mg/L	251.00 NTU	9.76	
				-				- J. –			

## WELL COMPLETION RECORD

PLETE ALL INFORMATION REQUESTED BELOW FOR EACH WELL INSTALLED, AND RETURN FORM TO THE N.C. ARTMENT OF HUMAN RESCURCES, SOLID AND HAZARDOUS WASTE MANAGEMENT BRANCH, BOX 2091, RALEIGH, N.C. 27602

·	
E OF SITE:	PERMIT NO.:
Greensboro Landfill	Well No. 9 / II - 4
RESS:	OWNER (print):
Off White Street in Greensboro, NC	City Of Greensboro
LING CONTRACTOR:	REGISTRATION NO.:
Engineering Tectonics, P.A.	835
Type:   SCH 40 PVC   dia.   2 in.	Grout Depth: from 0 to 13 ft dia. 6 in Bentonite Seal: from 13 to 14 ft dia. 6 in Sand/Gravel PK: from 14 to 26 ft dia. 6 in Total Well Depth: from 0 to 26 ft dia. 6 in Date Measured 7 /12 / 8  Casing is 3.42 feet above land surface
	LOCATION SKETCH
DRILLING LOG	(show distance to numbered roads, or other map reference points)
DM TO FORMATION DESCRIPTION  See Attached Boring Log	G R E E I N S B O R O S S S S S S S S S S S S S S S S S
ARKS:	
T. 7-14-89 SIGNATURE:	

## - Proposed MONITORING WELL INSTALLATION SKETCH

PROJECT _ White Street Landfill GROUND ELEVATION  BENCH MARK DATA  ELEVATION OF TOP OF PIEZOMETER	PIEZOMETER NUMBER A  DEPTH TO WATER LEVEL  ELEVATION OF WATER LEVEL			
S&NE BAYRONMENTAL SERVICES BHGINEERING - TESTING	PROTECTIVE BOX W/LOCKING CAP  SEAL CAP			
GROUND SURFACE	THICKNESS OF SURFACE SEAL TYPE OF SURFACE SEAL  I.D. OF RISER PIPE	0'-6' bgs portland 2-inch		
25'	TYPE OF RISER PIPE  TYPE OF BACKFILL	PVC portland 6' bgs		
	TYPE OF SEAL  TOP ELEVATION OF FILTER SAND	bentonite 81 bgs		
Is'	BOTTOM ELEVATION OF RISER  SIZE OF SCREEN OPENINGS PIEZOMETER SCREEN DIAMETER  TYPE OF FILTER SAND	10' bgs 0.010 2-inch #2 25' bgs		
	BOTTOM ELEVATION OF PIEZOMETER  DIAMETER OF BOREHOLE	25' bgs		

bgs = below ground surface